ENGINEERING NEWS-RECORD

A McGRAW-HILL PUBLICATION



Good sewers lead a double life

Experienced sewer designers have long known that every sewer must have *structural integrity* as well as *material durability*. However, materials that withstood severe corrosion were often structurally weak. The result was frequent failure, high maintenance and loss of efficiency.

Then Armco engineers found a perfect answer.

They developed Armco ASBESTOS-BONDED Pipe—a pipe that would take severe corrosion in stride and had all the structural advantages of corrugated metal design.

Millions of rot-proof, non-deteriorating asbestos fibers are inseparably bonded by zinc to the base metal. When thoroughly impregnated with a special saturant and seal coat they assure great resistance to acid, alkaline and saline conditions. Equally important, Armco Pipe has structural strength to withstand the impact and weight of heavy loads, maintains alignment and has strong, tight joints to stop leaks and prevent infiltration of ground water.

Providing better products to meet specific needs has been standard practice at Armco for more than 40 years. A few examples are FLEX-BEAM Guardrail, PIPE-ARCH, Steel Buildings and sturdy MULTI-PLATE Bridges.

Today you can bring your drainage and construction problems to Armco with full assurance you will receive all the benefits of long experience, extensive research facilities, and a real interest in helping you solve these problems.

Armco has a complete range of engineered products and convenient, authoritative data to help you. If your problem is difficult or unusual, why not talk it over with us.

ARMCO

ARMCO DRAINAGE & METAL PRODUCTS, INC.

MIDDLETOWN, OHIO • OFFICES AND PLANTS IN PRINCIPAL CITIES
SUBSIDIARY OF ARMCO STEEL CORPORATION

Berkeley, California • Middletown, Ohio • South Bend, Indiana • Baltimore, Maryland
Denver, Colo. • Des Moines, Iowa • Atlanta, Ga. • Topeka, Kansas • Houston, Texas
Minneapolis, Minnesota • Portland, Oregon • Washington, D. C. • Guelph, Ontario

FRANCIS TURBINES



SUPPLYING a fundamental need in the field of hydraulics, the Smith-Francis Turbine has been in the forefront of the industry for many years. It is ideal for that long range of heads existing between the lower medium and very high. Completely described in a new Bulletin No. 152—just off the press! Write for your copy NOW!

S. MORGAN SMITH CO., YORK, PENNA.

POWER by SMITH

F/S OPTICAL TRANSIT



F/S Model 4150R

The newest and most modern transit for surveyors and engineers

F/S Model 4150R special features include:
OPTICAL PLUMMET—eliminates plumb bob.
OPTICAL READING SYSTEM—vertical and horizontal readings to 6" at a glance thru reading scope next to telescope.
REPEATING LEVER—speeds repetitions, prevents errors.
FULL "BEHIND INSTRUMENT" OPERATION—no walking around.

F/S Optical Planimeter

F/S Model 236/v



Exclusive F/S patent design eliminates eye-strain, increases precision and speed

- New free-wheeling wide angle magnifying lens glides smoothly along outline—no sticking or parallax
- Finger-flick zero-setting control brings both wheels automatically to zero
- Enclosed wheel carriage keeps out dust and maintains high precision

Full Service and Repair Facilities Available
TRANS-GLOBAL COMPANY
1480 Broadway, New York 18, N. Y.

American Distributors for
FILOTECHNICA SALMOIRAGHI
Milan

ENGINEERING NEWS-RECORD

ABP Member ABC

Volume 149 December 4, 1952 No. 23

WALDO G. BOWMAN
Editor

FEATURES IN THIS ISSUE

George Meany named to head AFL 29
Building a city from scratch, by A. J. Fox, Jr 34
How much stress can a rivet take? by T. R. Higgins & W. H. Munse 40
Analogs used to solve flow problem, by Karl O. Vartia 44
Propose 24-mi expressways for Milwaukee 47
T. C. Forrest, Jr., next NSPE president 64
November Contract awards heavy 116
Power anywhere on job with portable generator 136

DEPARTMENTS

Reader Comment 11
Calendar of Meetings 15
Construction Week 17
Construction Trends 19
News of the Week 21
Labor 29
Municipal 47
International 56
Men and Jobs 64
Obituaries 74
Meetings 76
Legals 78
Construction Reports 81
Material Prices 105
Business and Finance 116
New Products 144
Editorials 144

Number of copies of this issue printed, 55,154

Managing Editor—Eugene E. Halmos, Jr.
Associate Editors—*New York*, V. T. Boughton (senior associate), J. M. Connolly, R. H. Dodds, F. S. Merritt, Arthur J. Fox, Jr., Ken Maxcy, Jr.; *Chicago*, J. R. Carr; *San Francisco*, L. L. Wise; *Washington*, V. B. Smith.
Assistant Editors—*New York*, T. D. MacGregor, Clyde Henning, Abner A. Layne, Howard Jacoby, George T. Orick.
Staff Assistants—Robin Bragg, Henry G. Compton, Ethel Lyon, *copy desk*; John Greenough, Leo Tarpey, *printing*; Madalene Smith, *editorial*; Joan Ash, *research*.
Business News—Elsie Eaves, *Manager*; J. A. Mahoney, M. Wetzel, *Reports*; J. H. Webber, M. W. Roessler, E. M. Huber, *Statistics*; Dori Spielberg, *Research*.
Contributing Editor—N. A. Bowers.
Domestic News Bureaus—Atlanta, Chicago, Cleveland, Detroit, Houston, Los Angeles, San Francisco, Washington. Correspondents in 71 cities in the United States, Canada and Mexico.
Foreign News Bureaus—London, Frankfurt, Paris, Moscow, Tokyo, Bombay, Melbourne, Rio de Janeiro, Mexico City. *Correspondents*—Athens, Rome, Caracas, Buenos Aires, Santiago, Shanghai, Zurich, Johannesburg and 40 other cities.

ROBERT F. BOGER
Publisher

December 4, 1952 ENGINEERING NEWS-RECORD Vol. 149—No. 23
Member ABC and ABP

Published weekly by McGraw-Hill Publishing Company, Inc., James H. McGraw (1860-1948), Founder. **Publication Office, 99-129 North Broadway, Albany 1, N. Y.**

Executive, Editorial and Advertising Offices: McGraw-Hill Building, 330 W. 42nd St., New York 36, N. Y. Curtis W. McGraw, President; Willard Chevalier, Executive Vice-President; Joseph A. Gerardi, Vice-President and Treasurer; John J. Cooke, Secretary; Paul Montgomery, Senior Vice-President, Publications Division; Ralph B. Smith, Vice-President and Editorial Director; Nelson Bond, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Director of Circulation.

Subscriptions: Address correspondence to Engineering News-Record—Subscription Service, 99-129 North Broadway, Albany 1, N. Y., or 330 W. 42nd St., New York 36, N. Y. Allow one month for change of address.

Subscriptions are solicited only from persons with an identifiable commercial or professional interest in construction and building. Position and company connection must be indicated on subscription orders.

Single copies 35¢. Subscription rates—United States and possessions, $6.00 a year; $8.00 for two years; $12.00 for three years. Canada, $8.00 a year; $12.00 for two years; $16.00 for three years. Other Western Hemisphere countries, $15.00 a year; $25.00 for two years; $30.00 for three years. All other countries, $20.00 a year; $30.00 for two years; $40.00 for three years. Entered as second class matter October 29, 1936, at the Post Office at Albany, N. Y., under Act of Mar. 3, 1879. Printed in U. S. A.

Copyright 1952 by McGraw-Hill Publishing Co., Inc.—All Rights Reserved.

where
SMOOTH HANDLING
is a
requirement!
IT is when smooth handling is a requirement that you find out about crane operation. When you have to balance 50 ft. of 60 in. pipe and shove it into the next section—when you have to lower a cage down a pier face for the inspector to look the concrete over—when you have to hold steel for welding or riveting, set stone or balance a concrete bucket six stories up and hit the elephant trunk, that is when you appreciate the value of smoothness of operation.
The Northwest "Feather-Touch" Clutch Control gives easier operation with freedom from the complications of delicate parts such as pumps, valves, compressors and tubing. Uniform Pressure Swing Clutches give smooth swing, reduce the danger of whipping and give increased accuracy in setting. Throttle control permits minute movements in handling the load and there is a Northwest Boom Hoist to fill every operating requirement.
These Northwest advantages mean time saved on the job and greater safety for the setters! They mean money! Why not plan to have a Northwest? Talk to a Northwest Man. It will pay you to place an order.
NORTHWEST ENGINEERING COMPANY
1502 Field Building, 135 South LaSalle Street
Chicago 3, Illinois
WEIGH ALL THE ADVANTAGES
NORTHWEST
CRAWLER and TRUCK MOUNTED SHOVELS • CRANES • DRAGLINES • PULLSHOVELS

MAINTAIN

SIMPLIFY YOUR LUBRICATION — Contractors everywhere are saving time and money with the Texaco Simplified Lubrication Plan. With it, they can handle all their major lubrication with *only six* Texaco Lubricants. Nothing like it to prevent confusion and costly lubrication errors . . . to keep equipment on the job and working. Ask your Texaco Lubrication Engineer for details.

TUNE IN . . . TEXACO STAR THEATER starring MILTON BERLE, on television Tuesday nights. METROPOLITAN OPERA radio broadcasts Saturday afternoons.

TEXACO REG. T.M.

TEXACO

FULL PRESSURE under ALL conditions...

Use the recommended Texaco air compressor oil

You can keep full air pressure at your drills only by keeping your compressors running cleanly and efficiently. Here you must depend on effective lubrication . . . and because *no one oil* can assure this under *all* operating conditions, there is a complete line of Texaco air compressor oils . . . one exactly right for *your* conditions.

For example, a Texaco *straight mineral* air compressor oil is your best bet for normal conditions. If "wet cylinders" are causing excessive wear, you should use a Texaco *compounded* air compressor oil. If rusting is a problem, you can overcome it by using a Texaco *rust-inhibited* air compressor oil.

FOR YOUR ROCK DRILLS use *Texaco Rock Drill Lubricant EP.* You get superior lubrication plus longer drill life and reduced maintenance costs because of its "extreme pressure" properties. In addition, it protects against rust whether drills are running or idle.

A Texaco Lubrication Engineer will gladly help you select the proper lubricants to get top performance from all your equipment. Just call the nearest of the more than 2,000 Texaco Distributing Plants in the 48 States, or write The Texas Company, 135 East 42nd Street, New York 17, N. Y.

Lubricants and Fuels

FOR ALL CONTRACTORS' EQUIPMENT

Faithfully yours TEXACO 50 *for Fifty Years*

More Profits ON EVERY JOB

WITH HENDRIX BUCKETS



3/8 to 40
CUBIC YARDS

A TYPE & SIZE
FOR EVERY
DIGGING PURPOSE

HENDRIX *Lightweight* **DRAGLINE BUCKETS**

More and more dirt-moving men notice the number of Hendrix Dragline Buckets being used on other jobs. They ask questions and learn that Hendrix Buckets move more dirt . . . easily . . . quickly . . . and without breakdowns . . . RESULTING IN MORE PROFITS. That is why more and more bucket users try Hendrix Buckets . . . then turn around and specify that ALL their draglines be equipped with money-making Hendrix Dragline Buckets!

Hendrix Buckets May Be Special Ordered Without Perforations

HENDRIX MANUFACTURING CO., INC.

MANSFIELD — LOUISIANA



RAYMOND

solves another tough job!

at left
Sinking Gow caissons for Detroit's City-County Building

FOUNDATION CONTRACTOR:
O. W. Burke Co.

ARCHITECTS & ENGINEERS:
Harley, Ellington & Day, Inc.

CONSTRUCTED FOR:
Detroit-Wayne Joint Building Authority

. . . **To provide** the foundation for the City-County Building in Detroit's new Civic Center, Raymond placed 126 Gow caissons, with diameters of 48 to 74 inches, to depths exceeding 100 feet to hardpan. The caissons were belled out on the hardpan to varying diameters. Completion of this project ahead of schedule is another example of how Raymond engineers combine knowledge and experience with specially designed equipment to provide any type foundation anywhere. We would like to serve you on your next project.

RAYMOND CONCRETE PILE CO.

140 CEDAR STREET • NEW YORK 6, N. Y.

BRANCH OFFICES *IN THE PRINCIPAL CITIES OF UNITED STATES AND CENTRAL AND SOUTH AMERICA*

THE SCOPE OF RAYMOND'S ACTIVITIES . . .

Foundation Construction . . . Harbor and Waterfront Improvements . . . Soil Investigations . . . In-Place Pipe Lining . . . Specialized Construction.

To save surface maintenance . . . BUILD THE BASE with a SEAMAN

OLD 9 FOOT ROADWAY widened with crushed stone macadam. Bituminous surface (at left) covering SEAMAN-mixed macadam shows no defects after 2 years. Cracks in surface over old pavement (right) reflect cracks and shrinkage in the old base.



SEAMAN Self-Propelled PULVI-MIXER. Gasoline or diesel powered. 7 ft. mixing width.

SEAMAN Mixer mixing crushed stone for water-bound macadam base. An excellent type of road. Ideal for stabilizing sub-grade prior to laying concrete pavement.

★ This 20 page, illustrated SEAMAN Bulletin, *"Macadam Base Construction Methods"* is yours for the asking. Shows how modern methods can build strong, weather-resistant macadam bases quickly and economically. Send a post card requesting Bulletin 60.

MOST cracks and faults on a highway are a mark of insufficient stability in the base, sub-base or in both. Repairs simply hide the symptoms temporarily; they don't correct the cause.

Here's a case in point: a very old rigid type of roadway 9 feet wide, laid on a none too stable sub-grade, was widened by adding a crushed stone macadam base 11 feet in width. The stone was mixed, keyed and interlocked with the SEAMAN MIXER. In the same pass the SEAMAN also blended the fines to fill the voids more perfectly than by the costly, old method of hand-brooming. After pneumatic rolling the entire 20 foot roadway 8 miles in length was given a bituminous topping.

Two years later. The SEAMAN-mixed macadam showed no surface defects. (See left half of photo above) But the surface of the old road was badly marred by a series of cracks over the entire 8 miles. These faults reflect shrinkage, settling and cracks occurring in the original base.

The moral? Whatever type of construction you use — bituminous, soil-cement, macadam, gravel or any method of stabilizing soil, — build the base with a SEAMAN. Lowest in the original construction cost, it will pay back a hundred-fold in years and years of minimum maintenance.

SEAMAN MOTORS, INC.

281 N. 25th STREET MILWAUKEE 3, WISCONSIN

Always the same . . . product quality that never varies . . . that's the secret of Aeroquip's leadership. Nothing is spared in time, money and effort to obtain the newest, most accurate inspection equipment to assure the Aeroquip standard, highest in the industry. That is why Aeroquip Products are "Always First" in quality.

- Flexible Hose Lines
- Detachable, Reusable Fittings
- Self-Sealing Couplings
- Breakaway Couplings

Aeroquip

REG. TRADE MARK

AEROQUIP CORPORATION, JACKSON, MICHIGAN

SALES OFFICES: BURBANK, CALIF. • DAYTON, OHIO • HAGERSTOWN, MD. • HIGH POINT, N. C. • MIAMI SPRINGS, FLA. MINNEAPOLIS, MINN. • PORTLAND, ORE. • WICHITA, KAN. • TORONTO, CANADA

AEROQUIP PRODUCTS ARE FULLY PROTECTED BY PATENTS IN U.S.A. AND ABROAD

users specify AMSCO DREDGE PUMPS

More **Amsco** Pumps have been placed in dredges for sand and gravel recovery, river and harbor dredging, shell reclamation, and more recently, ores such as titanium, than those of any other manufacturer. The reasons for this preference are clear:

Amsco Pumps, with working parts made of manganese steel, can withstand the terrific abrasion of sand and the sledge hammer blows of rock much longer than any others.

Amsco Pumps are designed from experience and engineered for your job.

▶These six basic types of Amsco Dredge Pumps—actually there are 40 different models—give a general idea of the complete line. The basic differences are in rated capacity, weight and construction of bearings, and in proportionate shaft sizes. Such modifications are made for economy...There is no dollar-wasting excess weight on the Amsco Pump engineered for your job. Water end parts are also available in ABK metal subject to our engineers approval.

Amsco has a complete line of welding rods and electrodes to assure prolonged life and economical service of Amsco Dredge Pumps.



16-inch type XH—directly connected design; right hand bottom discharge. Can be fitted with "standard" or "counter-flow" water ends.



6-inch type SB-CF, form 24—antifriction bearing; stub base or belt driven; right hand bottom discharge.



10-inch type M—left hand top discharge. Built in 6-, 8- and 10-inch sizes. Can be fitted with "standard" or "counter-flow" water ends.



20-inch type XHRB-CF—left hand bottom discharge; antifriction thrust and radial bearings.



12-inch type H-CF, form 40—right hand, top vertical discharge; belt driven. Combination two directional-type ball thrust bearing and sleeve-type radial bearings.



8-inch type C, form 30—belt driven; left hand bottom discharge; combination ball thrust and ring oiling sleeve main bearings. Available with "standard" or "counter-flow" water ends.

Brake Shoe **AMERICAN MANGANESE STEEL DIVISION**

379 EAST 14th STREET • CHICAGO HEIGHTS, ILL.

Other Plants: New Castle, Del., Denver, Oakland, Cal., Los Angeles, St. Louis. In Canada: Joliette Steel Division, Joliette, Que.
Amsco Welding Products distributed in Canada by Canadian Liquid Air Co., Ltd.

READER COMMENT

Unfinished structural business

Sir: At a national meeting of engineers some time ago, a lengthy, informal discussion was held by a chance group of engineers about some features of structural design, materials, and fabricating practices which do not appear to be adequate, in view of the tendency towards reducing the size of joints and other members and increasing spans as more precise analyses are made of the stresses encountered in structural assemblies. It has occurred to me that some of the thoughts expressed might also be of interest and value to other engineers.

They are:

1. The compression flanges of long span, especially continuous, girders should have greater width or have more resistance built into them against lateral forces. Some bridges with this type of main members have been observed which had considerable undesirable side wobble or deflection during erection and even up to the time of the actual hardening of the concrete decks.

2. The compression joints in truss systems should be strengthened to resist considerable bending moment. The practice of butting compression chord components and relying mainly on the gusset plate or plates for continuity can produce a structure inherently weak in vertical and lateral shock or impact resistance, particularly during erection and possibly later in service.

Such joints should be re-examined, and consideration given to full splice plates over the top cover plates, some splice metal across the webs, plus ample splice metal carried across the bottom flanges of the chord members. In other words, the compression joints should have considerable moment resistance and continuity of component members, even if the existence of the gusset plates is entirely disregarded.

3. Specifications for welded gusset plates should call for a steel that will withstand bend tests, both in the direction of and at right angles to the direction of final rolling. In addition, plates for gussets in welded construction should be required to be free from internal defects which might let considerable areas of a plate separate when members are welded to opposite sides.

4. Under no circumstances should it be permissible to increase the size of or piece out a gusset plate by welding.

YE GOOD KING WENCESLAUS
by YE GOOD SAINT "VIC"

Sad King Wenceslaus looked out
At the royal piping,
Faulty lines lay all about
(Those leaks and breaks were griping!)
Then he saw with much delight
What was in his stocking,
He found Couplings sure leak-tight
(Victaulics famed for locking!)

"Ah! Victaulic Fittings, too,"
Roared the King now smiling,
"Elbows, Tees all grooved and true,"
(And Full-Flow in their styling!)
Good Saint "Vic" was in the know,
Vic-Groover tools were waiting,
Kingly smiles began to grow
(Their grooving's tops in rating!)

Zip! The King hooked up those sections,
Saint "Vic" did him rightly
With these very best connections
(No leaks and drips unsightly!)
For a Method that's complete
Wenceslaus is liking
Easiest way to make ends meet
(Victaulic's Four Star Piping!)

VICTAULIC COMPANY OF AMERICA
P. O. Box 509, Elizabeth, N. J. Office & Plant: 1100 Morris Ave., Union, N. J.

EASIEST WAY TO MAKE ENDS MEET
VICTAULIC ★ METHOD OF PIPING
★ VICTAULIC COUPLINGS
★ VICTAULIC FULL-FLOW FITTINGS
★ VIC-GROOVER TOOLS
★ ROUST-A-BOUT COUPLINGS

TELSMITH®

NEW Tyrone Rock Products Co. plant PRODUCES 3000 TONS A DAY at low cost...with TELSMITH Conveying and Screening Equipment

TELSMITH Equipment in this Plant

One (1) 5′ x 12′ Pulsator Single Deck Scalping Screen

One (1) 5′ x 12′ Pulsator Double Deck Scalping Screen

One (1) 4′ x 10′ Pulsator Double Deck Rinsing Screen

Eight (8) 5′ x 12′ Vibro-King Single Deck Finishing Screens

Two (2) 4′ x 10′ Vibro-King Single Deck Finishing Screens

Twelve (12) Telsmith-BG Conveyors 18″ to 42″ wide, 42′ to 200′ long

Fifteen (15) 16″ x 18″ Bin Gates Boquad Tunnel Type

• To serve the rapidly growing Atlanta market, this modern plant at Tyrone, Ga., is a remarkably efficient, low-cost operation. Designed and engineered by Telsmith, its average capacity is about 300 tons per hour with peaks of 450 tons. Highly efficient screening is supplied by 13 Telsmith vibrating screens making 8 sizes of crushed granite (−2″ to −8 mesh) for railroad ballast, and concrete and asphalt construction.

Finished sizes are stockpiled over a reclaiming tunnel, then rinsed and delivered to bins for loading cars and trucks. Telsmith did all engineering, including detailed drawings, furnished all screens and conveyors and carefully co-ordinated all equipment for smooth, efficient operation. To relieve yourself of technical details and to be sure of satisfactory results, consult Telsmith without obligation. Send for Bulletin 266.

SMITH ENGINEERING WORKS
500 EAST CAPITOL DRIVE, MILWAUKEE 12, WISCONSIN

ENGINEERED

VIBRO-KING

For Finished Screening of Medium and Small Sized Aggregate

With its two bearings, the Vibro-King is simpler, more efficient, and upkeep is lower. Telsmith-patented automatic counter-weights assure smooth starting and stopping as well as exceptionally smooth operation. Its circular screening movement is uniform everywhere on the screen cloth, and is constant under any load. Entire vibrating mechanism, including vibrating unit and screen cloth, floats on nests of springs. Welded and reinforced main frame is *horizontal* for rigidity and easy installation. Cable suspension, if desired. Five sizes, 1, 2, or 3 decks.



Changing Screen Cloth is Simple and Quick — The upper end of the Vibro-King is readily removable, making it a much easier job to change screen cloth and saving a great deal of time.

Screen Cloth Mounting—At customer's option — screen cloth may be mounted in rubber on steel screen trays; or stretched over steel screen supports—protected by rubber—on any deck or decks.

PULSATOR

For Heavy-Duty Scalping

A four-bearing, heavy-duty vibrator . . . for all kinds of screening, especially scalping, or large sized aggregate . . . Pulsator's circular movement gives uniform, efficient screening on all decks and under heaviest loads. The best alloy steels, the finest anti-friction bearings, protected by both labyrinth and piston ring seals, give longer life and lower upkeep. Eleven sizes, with 1, 2, or 3 decks.



PULSATOR
4-Bearing Screen

QS-12

Cable Address: Sengworks, Milwaukee

51 East 42nd St. New York 17, N. Y. • 211 W. Wacker Drive Chicago 6, Ill. • 713 Commercial Trust Bldg. Philadelphia 2, Pa. • 239 Main Street Cambridge 42, Mass. • Beebe Eqpt. Co. Milwaukee 2, Wis. • The McLean Co., 3525 Lakeside Ave. Cleveland 14, Ohio • Marens Eqpt. Co., 432 Main St., Rochester, Mich. • Clyde Eqpt. Co., Portland 9, Ore., & Seattle 4, Wash. • Mines Eng. & Eqpt. Co., San Francisco 4, Calif. • Rish Eqpt. Co., Charleston 22, & Clarksburg, W. Va.—Roanoke 7, & Richmond 19, Va. • Interstate Equipment Co., Statesville, N. C.

4 STEPS TO BETTER WATER

1. PERMUTIT PRECIPITATORS—For coagulation of turbid or colored waters and for softening hard waters. Uniform upward filtration through sludge blanket saves from 10% to 40% in chemicals . . . up to 50% in space and 75% in time. Available in horizontal or vertical designs, in single units or batteries, with unit capacities up to 10,000,000 gpd.



2. PERMUTIT ZEOLITE (Ion Exchanger) WATER SOFTENERS—Simplest method of removing hardness to any required degree. Completely automatic operation assures uninterrupted service and reduces operating costs. Supplied in single units or batteries to fit all requirements.



3. PERMUTIT SPIRACTORS®—New principle—*catalytic precipitation*—shortens detention time, eliminates sludge disposal, saves steel, floor space. No moving parts. Total reaction time is 8 minutes.



4. PERMUTIT MONOCRETE UNDERDRAINS—Rugged monolithic construction. Non-corrodible, easy to install. Large laterals and header assure uniform collection and distribution of water. Laterals are formed by specially designed inflatable rubber tubes which are removed after the concrete is set.

For full information on these and other types of water conditioning equipment, write to The Permutit Company, Dept. AC-7, 330 West 42nd Street, New York 36, N. Y., or The Permutit Company of Canada, Ltd., 6975 Jeanne Mance Street, Montreal.

PERMUTIT®

WATER CONDITIONING HEADQUARTERS FOR 40 YEARS

READER COMMENT

5. Rough riding, caused by slight dips on some steel beam or girder bridges, has been traced to excessive cantilever overhang. The cantilever portions of continuous spans should be examined for adequate depth and vertical stiffness. Where suspension hangers are introduced at contraflexure points, the overhang to such points on cantilevering should be kept on the short side.

The writer realizes that the points raised above could be the subject of endless debate or letter writing. He is not asking for either, but hopes that these items may be placed on the agenda of the proper committees of the technical societies which normally are concerned with such matters.

G. C. Greulich
Consulting Engineer
Pittsburgh, Pa.

Delete privy data

Sir: In your article on the new system for home sewage disposal (ENR Oct. 30, p 39), it is regretted that the figures 6.2 and 30.9, appear in the column "Aeration Tank D.O.", Period III. These figures are not reliable and should not have appeared in the table. Materials accumulating in the effluent so interfered with the dissolved oxygen determination that it was impossible to obtain reliable information.

Don E. Bloodgood
Professor of Sanitary Engineering
Purdue University

CALENDAR

Society for Experimental Stress Analysis, Hotel McAlpin, New York City, Dec. 3-5.

American Association of State Highway Officials, annual meeting, Municipal Auditorium, Kansas City, Mo., Dec. 10-12.

Illinois traffic engineering conference, University of Illinois, Urbana, Dec. 11-12.

American Society of Photogrammetry, annual meeting, Shoreham Hotel, Washington, D. C., Jan. 14-16.

National Association of Home Builders, Conrad Hilton Hotel, Chicago, Ill., Jan. 18-22.

Mason Contractors Association of America, Sherman Hotel, Chicago, Ill., Feb. 1-4. California Street and Highway Conference, University of California, Berkeley, Feb. 4-6.

American Road Builders Association, Hotel Statler, Boston, Mass., Feb. 9-11.

Ohio Water Clinic, Ohio State University, Columbus, Feb. 19-20.

Illinois Confernce on Highway Engineering, Urbana, Feb. 24-26.

Industry conference on air pollution abatement, Hotel Statler, Detroit, Mich., Feb. 26-27.



When you buy an Ellicott Dredge you buy SERVICE!

Your dredge is *engineered* to the job!

Designing a dredge is a highly specialized job—and the dredge *you* need must be engineered with *your* problems in mind. That's why Ellicott maintains a large staff of engineers, who consult with you, study your requirements, and recommend the proper equipment for your job.

Ellicott carries through on delivery and assembly!



Perhaps your dredge can be built complete at Ellicott's yard and towed to its destination—or shipped by rail or water and then assembled by Ellicott or you. In any case, Ellicott engineers are there—at your site—when you need them. Ellicott assumes complete responsibility for performance!

Ellicott engineers are always at your service!

At any time while your dredge is in operation, an Ellicott engineer will visit your site . . . perhaps give suggestions for improving performance, or using the dredge for another job. In addition, you are invited *at any time* to request Ellicott to help with any problems you have.

Consult Ellicott on all your dredging problems!

Perhaps you already own dredging equipment that is not doing the job it should. Here, too, Ellicott will be glad to help you. Drop us a line, outlining your problem. And ask for complete, illustrated Catalog No. 825. Address: Ellicott Machine Corporation, 1603 Bush Street, Baltimore 30, Md.

ELLICOTT®

ELLICOTT DREDGES

Main Street Merchant

The Golden Rule Store in Kemmerer, Wyoming, where J. C. Penney started his business in 1902. Now, fifty years and some 1624 stores later, comes Penney's beautiful new store, on Monument Circle, in Indianapolis.

J. C. Penney's Great, New Indianapolis Store Gives Concrete Expression to Principles which Built an Ideal into a Billion Dollar Business

● Clearly, J. C. Penney meant it when he called his first store The Golden Rule, for he and his associates have built that precept into a nation-wide institution, with 1624 stores and over a billion dollars annual volume. One of the newest in the Penney chain is this handsome Indianapolis store, on Monument Circle, the hub of the world's largest city not on navigable water.

The durable, fire-safe character of the building's concrete construction is as staunch as the business it houses. Hailed as a fine example of modern architecture, this new $6-million building, with 182,000 sq. ft. of total area on three floors, is windowless and completely air-conditioned. Counter and display arrangements also strike a new note in design.

Here is a structure well expressing the traditions of quality, value and friendly service which are distinguishing attributes of the business it houses, as indeed they are of the company which produced the 25,000 barrels of Lone Star Cement that went into this construction.

J. C. PENNEY COMPANY BUILDING, Indianapolis, Indiana
Built and owned by: **EQUITABLE LIFE ASSURANCE SOCIETY OF THE U. S.**
Architects:
SKIDMORE, OWINGS & MERRILL, New York, Chicago, San Francisco
Contractors:
Substructure: **CARL M. GEUPEL CONSTRUCTION CO.**, Indianapolis
Superstructure: **FRANK MESSER & SONS, INC.**, Cincinnati
Masonry: **LEON JOYCE**, Indianapolis
Cement requirements, all Lone Star:
Substructure: **READY MIXED CONCRETE CORPORATION**
Superstructure: **CARLSEN CONCRETE SUPPLY**
Wall and Partition Units: **CINDER BLOCK & MATERIAL CO.**
Masonry: **H. W. LINABURRY BRICK & TILE CO.**
—all of Indianapolis, Indiana



LONE STAR CEMENTS COVER THE ENTIRE CONSTRUCTION FIELD

LONE STAR CEMENT CORPORATION

Offices: ABILENE, TEX. • ALBANY, N. Y. • BETHLEHEM, PA. • BIRMINGHAM
BOSTON • CHICAGO • DALLAS • HOUSTON • INDIANAPOLIS
KANSAS CITY, MO. • NEW ORLEANS • NEW YORK • NORFOLK
PHILADELPHIA • RICHMOND • ST. LOUIS • WASHINGTON, D. C.

LONE STAR CEMENT, WITH ITS SUBSIDIARIES, IS ONE OF THE WORLD'S LARGEST CEMENT PRODUCERS: 17 MODERN MILLS, 125,600,000 SACKS ANNUAL CAPACITY

DECEMBER CONSTRUCTION SCOREBOARD









ENR INDEXES (1913 = 100), 20-cities' average	1952 December	% Change from last Month	% Change from last Year
Construction Cost	587.49	−0.2	+ 7.2
Building Cost	425.26	−0.2	+ 4.8
WAGE RATES, 20-cities' average			
Common	$1.817	0.0	+10.0
Skilled (aver. 3 trades)	2.942	+0.2	+ 6.8
Bricklayers	3.263	0.0	+ 6.1
Structural Ironworkers	2.863	0.0	+ 6.4
Carpenters	2.700	+0.5	+ 8.2
MATERIAL PRICES, 20-cities' average			
Cement, bulk, per bbl	$3.219	0.0	+ 1.6
Structural Steel, (3-mill aver.), per cw	3.850	0.0	+ 5.5
Sand, per ton	2.108	0.0	+ 0.3
Lumber, 2x4 Fir, per M. ft. bm.	107.722	−1.7	+ 0.9
Lumber, 2x4 Pine, per M. ft. bm.	93.033	−0.4	+ 1.4
Common brick, per M	31.601	0.0	+ 1.6
Ready-mixed concrete, per c. y	11.365	+0.5	+ 3.1
Structural Clay Tile, 3x12x12 per M	151.350	0.0	+ 1.1

CONTRACTS AWARDED (Millions)	1952 Nov. 4-weeks#	11-Mos.	% Change from '51 Nov. 5-weeks#	11-Mos.
Total U. S. (ENR reported)	$1,079.9	$14,782.3	+31.7	+15.7
Private	664.0	6,582.4	+30.0	−5.0
Public	415.9	8,199.9	+34.5	+40.4
Federal	151.3	4,370.8	+85.9	+104.3
ENR Volume Index, '13 = 100	504	591	+24.7	+10.9
NEW CAPITAL (Millions)				
Total	333.9	14,649.5	−91.1	−6.9
State & Municipal Bond Sales*	185.0	2,759.2	−21.0	+20.4
Corporate Security Sales	134.4	3,419.6	−53.7	+ 6.4
Federal (non-federal work)	14.5	883.9	+87.2	+26.5
Federal (federal work)	———	7,586.8	−100	−20.4

* Excluding public housing.
\# Computed on Weekly Average.

MATERIAL SHIPMENTS & LABOR SUPPLY (Millions)	1952 Sept. (s) Oct. (o)	9-Mos. (9) 10-Mos. (10)	% Change from '51 Mo.	Yr.-Cum.
Cement bbls. Bu. of Mines	26.243(S)	190.406(9)	+12.8	+2.7
Fabr. Struc. Steel, tons AISC	259(O)	2.211(10)	+7.9	−3.0
Lumber, mil. ft. bm., NLMA	3.450(S)	27.916(9)	+17.4	−2.2
Lumber Prod., mil. ft. bm., NLMA	3.464(S)	28.211(9)	+ 8.2	−5.7
Contract Constr. Employ., BLS	2.686(O)	2.548(10)†	−2.7	−0.7

† Average.







ENR Business News

Ryerson® Re-bars Ready When Needed

HI-BOND RE-BARS FOR GREATER GRIP

First of the new high-strength bars, Hi-Bond reinforcing gives stronger construction and increased resistance to the formation of tensile cracks. Every bar meets or exceeds ASTM spec. A. 305.

PRINCIPAL PRODUCTS IN STOCK

CARBON STEEL BARS—Hot rolled, cold finished.
STRUCTURALS—Channels, angles, beams, etc.
PLATES—Many types including Inland 4-Way Safety Plate.
SHEETS—Hot, cold rolled, many types—coatings.
TUBING—Seamless and welded, mechanical and boiler tubes.
ALLOYS—Hot rolled, cold finished, heat treated. Also tool steel.
STAINLESS—Allegheny bars, plates, sheets, tubes.
MACHINERY & TOOLS—For metal fabrication.

You can be sure the reinforcing materials you order from Ryerson will be ready on the job when you need them. Ryerson deliveries are timed to the job's progress, follow a dependable day-to-day schedule.

With the Hi-Bond type bars you order from Ryerson goes complete, time-saving Ryerson reinforcing service—setting plans, accurate cutting and bending, and every piece metal-tagged for quick identification and placement. And to speed up purchasing, you can include your other construction requirements with your re-bar order—spirals, wire mesh, joist forms—any other steel product.

Ryerson deliveries are flexible—can be stepped up should the job jump ahead of schedule, slowed down if materials begin to pile up on the site. So be sure of a fast start and completion on schedule. Next job, let us quote you our lump sum or average pound price.

RYERSON STEEL

JOSEPH T. RYERSON & SON, INC. PLANTS AT: NEW YORK • BOSTON • PHILADELPHIA
CINCINNATI • CLEVELAND • DETROIT • PITTSBURGH • BUFFALO • CHICAGO
MILWAUKEE • ST. LOUIS • LOS ANGELES • SAN FRANCISCO • SPOKANE • SEATTLE

• **Problem for defense**—One of the toughest problems for the new administration is already sitting squarely in the lap of Charles E. Wilson, incoming Defense Secretary:

The large-scale outpouring of defense contracts will slow down in the next 18 months—and with that slowdown comes the specter of slowing construction, possibly a business letdown. The new Secretary will have to fix the leveling off point, with an eye to business as well as military implications.

Just what the arms buildup has meant to business in general is easily apparent: Between World War II and Korea, Congress voted only $50 billion for the entire defense establishment, but it has had to vote another $160 billion since Korea, to rebuild the U. S. forces. The upcoming military budget (partly because the pace of letting contracts did not keep up with appropriations) will scale down to somewhere between $35 and $40 billion, (from $67 billion in fiscal 1952). There will be about $3 billion for military construction in that request, by the way.

• **Bridge play starts**—Armed finally with legal authority—and two-state backing—the Delaware River Port Authority is getting set to make big news for construction men, as well as industrialists and city planners.

Governors of both New Jersey and Pennsylvania have named the 12 members of the joint authority, Congress has approved the needed two-state pact, Army Engineers have OK'd the structure as no bar to navigation.

What is planned is a $90-million bridge between south Philadelphia and Gloucester, N. J., a $32.5-million expressway on the New Jersey side to feed the bridge. There is authorization for planning transit lines, tunnels, piers, and other bridges.

First move will be a $90-million authority bond issue, probably in January.

• **Work abroad**—If you are interested in work in foreign fields—it is a good idea to watch the North Atlantic Treaty Organization.

NATO is about to launch a new phase of its program to mass-produce air bases across Western Europe from Norway to Italy. To date, the program has reached the halfway mark, and the new phase, which might cost in the neighborhood of $400 million, will take it up to three-quarters.

What's on the fire: some 31 air bases, ranging in cost from $5.6 million to $11.5 million, each to have a standard 8,000-ft runway, a parallel landing strip, and fuel and ammunition storage facilities. Troop housing is a separate item.

• **St. Lawrence pressure**—The pressure is building up around that hearing set for Dec. 7, by the Federal Power Commission, on New York state's application to join Ontario in building the St. Lawrence Seaway.

The New York State Power Authority got some unexpected—and powerful—support when the Great Lakes-St. Lawrence Association (composed of state and municipal governments and private organizations and citizens) reversed its previous opposition, urged FPC to let New York go ahead with the job. And at the same time, R. B. McWhorter, U. S. member of the International Joint Commission had some economic cautions: (1) Canada shouldn't build and regulate the seaway alone, thus setting tolls for U. S. shipping which will predominate; (2) Power sales shouldn't carry so heavy a share of the costs—and the way IJC approved plans makes no provision for apportioning costs of navigation-power installations.

• **Which economy d'ya read?**—Construction as a key to U. S. economic health gets some careful study and some startling conclusions—from economists Miles Colean and Robinson Newcomb in a new book "Stabilizing Construction: The Record and Potential."

Say Colean and Newcomb: Construction isn't subject to 18-20 year cycles of depression-triggering declines; public works can't be counted on to halt depressions unless aided by long-term planning, budgeting and cooperation.

Better Concrete

from superhighways to sidewalks is made with DURAPLASTIC*



Penn-Lincoln Parkway,
Allegheny Co., Pennsylvania.
Placed in 1947.

YOUR NEXT PAVING JOB can prove it! Thousands of contractors, on jobs both large and small, have found that they can get better concrete with Atlas Duraplastic, the *original* air-entraining portland cement.

Because the use of Duraplastic cement minimizes bleeding and segregation, the finished concrete is fortified against the effects of freezing-thawing weather and the scaling caused by de-icing salts.

Moreover, Duraplastic is *easy* to use—no additives, no unusual changes in procedure. Duraplastic requires less mixing water for a given slump. The mix is more workable, more uniform. It dumps, spreads, finishes easily . . . permits finishing closer to the paver and earlier protection for curing.



O'Hare Field,
Park Ridge, Illinois.
Placed in 1942.



Plant paving, U. S. Rubber Co.,
Eau Claire, Wisconsin.
Placed in 1944.



Sidewalk,
Babylon, Long Island.
Placed in 1944.

YET DURAPLASTIC COSTS NO MORE

All these advantages are yours *simply by specifying Duraplastic.* It sells at the same price as regular cement; complies with both ASTM and Federal Specifications. For more information, write Universal Atlas Cement Company (United States Steel Corporation Subsidiary), 100 Park Avenue, New York 17, N. Y.

*"*Duraplastic" is the registered trade mark of the air-entraining portland cement manufactured by Universal Atlas Cement Company.*

ENR-D-148

ATLAS®

DURAPLASTIC

AIR-ENTRAINING PORTLAND CEMENT

Makes Better Concrete at No Extra Cost

"THE THEATRE GUILD ON THE AIR"—*Sponsored by U. S. Steel Subsidiaries—Sunday Evenings—NBC Network*

U.S. agencies see $32 billion building in '53

Predictions of a boom year for construction in 1953, made (ENR Oct. 9, p. 21) in a survey of experts have been backed by the Departments of Commerce and Labor. A survey, released over the weekend, estimates that construction next year will total $32.333 billion—which is $333 million over the earlier estimate.

The Commerce and Labor Departments make this qualification: The outlook is based on the assumption that business will remain good, helped out by increasing defense expenditures in the first part of the year, at least.

Private construction is expected to total $22.2 billion, compared with a $20-5-billion estimate made in ENR in October. As the accompanying table shows, the biggest increases in private construction are in warehouses, office and loft buildings, and stores, restaurants and garages. The estimates:

- Warehouses, office and loft buildings, up from $479 million to $575 million, up 20%.
- Stores, restaurants and garages, up from $622 million to $825 million, up 33%.

These increases offset an expected decrease in industrial construction of 28%, or $2.2 billion down to $1.6 billion. In October, ENR reported industrial construction would fall from $2.3 billion this year to $1.9 billion in 1953.

Among predicted increases in private building were: public utilities, up 11% (see table); educational, up 6%; residential, up 4%.

In public works, every category shows an increase in 1953 over 1952 public and defense housing, hospital, military and naval construction, highways, sewers and waterworks. The biggest increase in public building will come in hospitals and institutionals, up 11% and military construction, up 18%.

The Commerce-Labor survey estimates that housing next year will beat the one-million mark, with expenditures totaling over $10 billion.

Outlays for military and naval facilities will probably go up one-fifth to a total of around $1.6 billion. This building will be substantially completed during 1953.

Commercial building will go up one-fourth, continuing the brisk activity it has experienced since materials restrictions were eased, and since the removal of credit controls.

Estimated new construction activity

1952–1953

(Millions of Dollars)

	1952*	1953	Percent change
Total New Construction	32,318	33,500	+4
Private total	21,681	22,200	+2
Residential (excluding farm)	11,029	11,450	+4
New dwelling units	9,820	10,200	+4
Additions and alterations	1,026	1,050	+2
Nonhousekeeping	183	200	+9
Nonresidential building	4,945	4,600	−7
Industrial	2,289	1,650	−28
Warehouses, office and loft buildings	479	575	+20
Stores, restaurants and garages	622	825	+33
Other nonresidential building	1,555	1,550	†
Religious	397	425	+7
Educational	354	375	+6
Hospital and institutional	388	350	−10
Social and recreational	125	150	+20
Miscellaneous	291	250	−14
Farm construction	1,700	1,700	0
Public utility	3,925	4,350	+11
Railroad	400	425	+6
Telephone and telegraph	550	575	+5
Other public utility	2,975	3,350	+13
All other private	82	100	+22
Public total	10,637	11,300	+6
Residential	643	575	+11
Nonresidential building	4,104	4,250	+4
Industrial	1,649	1,700	+3
Educational	1,618	1,775	+10
Hospital and institutional	478	375	+22
Other nonresidential building	359	400	+11
Military and naval	1,355	1,600	+18
Highway	2,740	3,000	+9
Sewer and water	686	725	+6
Miscellaneous public service enterprises	202	200	+1
Conservation and development	843	875	+4
All other public	64	75	+17

* Ten months actual; November and December estimated.
† Decrease less than 0.5%.

AFL plumbers' leaders take key posts

Plumbing union leaders took the spotlight in the labor scene this week and last.

Martin P. Durkin, 58-year-old president of the AFL Plumbers and Pipefitters, was named Secretary of Labor. George Meany, also a former plumber and once president of the New York City local, moved into presidency of the AFL (see page 29).

Durkin was a surprise choice. A registered Democrat, he did not support President-elect Eisenhower in the cent campaign. Durkin sees a "good possibility" for a union of the AFL and CIO, and "will be glad to do everything in my power" to bring about unity between the two labor organizations.

A rotund, curly-haired Irishman, Durkin is described by friends as calm, judicious and soft-spoken. Chicago-born, he started his career as a steamfitter's apprentice in 1911. By 1941, he was secretary-treasurer of the plumbers' union. Durkin is a vice president of the Catholic Conference on Industrial Problems and a director of the Union Labor Life Insurance Co., of New York City.

Atomic energy may spark new boom in construction

- **Petrochemicals pace chemical expansions**
- **Pipeline projects spurt to new records**

Since the end of World War II, speculation on when industry will be able to use atomic energy for commercial purposes has run high. As atomic war weapons—from H-bombs and A-bombs through atomic reactors for propulsion of submarines, aircraft and surface vessels—have developed at an astonishing pace under the Atomic Energy Commission, the day when atomic energy also will be entrusted to competitive private enterprise has drawn steadily closer.

Last week T. Keith Glennan, president of Case Institute of Technology and former member of the AEC, indicated that day may arrive soon—and with it a new boom for construction.

Speaking before the Manufacturing Chemists' Association in New York, he called attention to the commission's decision to permit eight private concerns to come into the program to study the feasibility of producing atomic power in privately owned plants. Several additional companies began to make similar studies this year.

At first their questions were not too difficult, Glennan said. They wanted to know about materials, construction costs, and operations, today their questions are getting harder:

"If we put up some of our own money, what rights can we expect in return? Can we own atomic energy facilities? Can we locate those facilities wherever economic factors dictate? Can we own patents on things we develop at our own expense? Will we have access to nuclear fuel needed if we build a reactor for power?"

"Instead of technical questions, they are now primarily questions which any prudent investor might ask," Glennan said. He added:

Industry built the atomic energy program and is operating it under the AEC. The time has arrived for it to work out a program for development and use of the peaceful applications of atomic energy under competitive enterprise. To expedite this move, he suggests setting up an association of interested industrial concerns to work with the AEC toward that goal.

Said Glennan: In atomic energy, there is untold promise for the future—in power, in propulsion, in the use of nuclear radiation in a thousand ways which have not even been dreamed of as yet.

T. KEITH GLENNAN foresees early developments in atomic energy.

"Let's make our play, put in some chips and hasten the realization of some of this promise. Let's bring atomic energy out into the main stream of the economic life of America," he concluded.

• **The outlook**—For construction men the outlook is an encouraging one. Releasing atomic energy to private industry will mean piling up new backlogs, primarily on the already huge volume of power and chemical construction that lies ahead.

And some idea of what the addition of atom-power projects will mean to the construction picture is easily apparent from a look at these sample figures.

Expansion of power and light facilities is the biggest single program that has been fostered under fast tax-amortization, and involves a cost of $3.1 billion. Next year expenditures for power equipment are expected to climb another 15% over this year to a total of $468 million. The chemical industry is in the middle of an expansion program requiring $6 billion in new facilities between 1951 and 1955.

• Chemicals outlook bright

Whatever influence atomic energy development may have on chemical expansion in the future, today the industry is feeling its biggest impact from the development of petrochemistry.

The size of this impact was indicated last week in a report by William H. Ward, who is chairman of the Manufacturing Chemists' Association.

Analyzing $2.3-billion fast tax amortization certificates for 789 chemical expansion projects granted by the Defense Production Administration through Oct. 15, covering nearly 70% of the new projects, Ward came up with this trend:

Availability of oil and natural gas in the West-South-Central region has attracted new chemical projects which received certificates totaling $706 million.

This is nearly twice the $373 million granted for projects in the East-North-Central region.

Other certificates were issued for: $300 million in the south Atlantic region; $297 million in the Middle Atlantic; $200 million in the east-south-central; $137 million in the Pacific area; $103 million in the west-north-central; $74 million in the mountain region; $31 million in New England.

Texas and Louisiana are leading the individual states with expansions respectively of $435 million and $202 million.

In 1940, there was an estimated capital investment of $350 million in petrochemical plants. By 1945, this had grown to $1.2 billion. Today, investment is over $2 billion, and is still soaring. About 25% of the chemicals now being made are petrochemicals—materials derived from petroleum and natural gas—and by 1960 the proportion is expected to climb about 50%.

• **Looking ahead**—Among the petrochemical plants still in the future are: an American Cyanamid Co. plant in Jefferson Parish, La., under construction by Chemical Construction Corp. and J. A. Jones Construction Co.; a plant planned by Carbide & Carbon Chemicals Div. at Texas City, Texas; a plant at Pointe a la Hache, La., planned by Delta Chemical Co.; a plant planned by Lion Oil Co. to be constructed at Luling, La.; a plant for Phillips Chemical Co., nearing completion at Pasadena, Tex., being built by Chemical Construction Co.; a plant under construction for Monsanto Chemical Co. at Texas City, Tex.; a plant planned by Sid Richardson Gasoline Co., at Pointe a la Hache, La.; and a plant planned by Spencer Chemical Co. at Vicksburg, Miss.; a plant for Humble Oil & Refining Co. at Baytown, Tex., under construction by C. F. Braun Construction Co.

CONSTRUCTION of installations such as this one for Cities Service at Lake Charles, La. will continue high.

In addition there are nine sulfur-conversion plants under construction and two more in the planning stage; 12 new natural gasoline plants being built and 12 in the planning stage.

Expansion of crude-oil refinery facilities is slated to continue high next year, although at a less rapid rate than during the present year. Total refinery capacity for the present and the next two years is estimated at: 1951—6.9 million bbl per day; 1952—7.3 million bbl per day; 1953—7.5 million bbl per day; 1954—8 million bbl per day. Oil men use the rule-of-thumb estimate that each barrel per day expansion means an outlay of $1,500 for refinery construction.

• Pipelines forge ahead

Feeding the huge expansions in petrochemical plants and refineries, and pushing through to new consumer markets, is a vast network of pipelines. Construction of pipelines for transport of oil, oil products, and natural gas is slated to hit a peak next year, exceeding the present record-breaking year.

Petroleum Administration for Defense, materials claimant agency for the pipelines, is requesting allotment of 647,000 tons of steel for large pipe during the second quarter of next year. This is by far the largest amount ever requested by PAD.

It compares with allotments of 348,000 tons for the first quarter of next year and 387,000 tons for the present quarter. Because of lack of steel, pipeline manufacturers are now turning out only 400,000 tons of large piping—16 in. diameter and above— per quarter.

During the first quarter of next year, natural gas producers and pipelines will initiate construction on three projects costing nearly $40 million. They are:

- Two new underground gas storage reservoirs to be constructed in West Virginia by United Fuel Gas Co. at a cost of $8.1 million. The project is scheduled for completion by end of next year.
- Looping of a section of the 34-in.







GAS UTILITY and pipeline construction continues high.

pipeline in California to bring additional Texas gas to California. This $16.8-million project is being undertaken by Pacific Gas and Electric Co. and completion is set for the second and third quarters of next year.

• Additional transmission lines to be built by the Texas Co. to serve two industrial customers in Louisiana at a cost of $3.9 million. These are to be completed by the third quarter of next year.

• **More coming**—PAD also is extending priorities assistance to five other natural gas pipeline projects already underway.

Projects, firms involved, cost and date of completion are:

• Looping of existing Texas-California system; El Paso Natural Gas Co.; $63.7 million; slated for the second quarter of 1953.

• Looping and extension of existing system; Southern Natural Gas Co.; $77.7 million; 1954.

• Additional compressor-station horsepower and lateral transmission line; Texas-Illinois Natural Gas Pipeline Co.; $21.9 million; third quarter of 1953.

• Looping of existing Texas-New England system; Tennessee Gas Transmission Co.; $133.7 million; fourth quarter of 1953.

Total cost of these projects is $323 million, and pipe alloted for the first quarter of next year totals 140,000 tons.

In addition, PAD has allocated tons. In addition, PAD has allocated projects, including gathering lines, distribution lines and other facilities. This allotment includes the pipe needed for maintenance, repair and operation of natural gas systems.

Already completed this year, are more than 1,600 miles of lines; projects now underway will reach 2,500 when completed. The size of the job ahead can be measured by the 17,740 miles of new lines which are still in the planning stage.

• **More oil and products lines**—While expansion of natural gas lines has provided the most spectacular phase of new pipeline construction, the trend toward more pipelines for transport of crude oil to refineries and oil products to consumer markets is growing at a rapid pace.

Last week, as DPA was preparing to announce first quarter allotments of pipe to crude-oil and oil-product pipelines, it estimated that the cost of projects of the type now underway is more than $390-million. Crude oil lines now under construction will total 2,150 miles when completed, and products lines will reach a total of 2,330 miles.

Looking ahead, crude oil projects in the planning stage call for another 3,600 miles of pipeline, and products lines being planned will stretch for 4,550 miles. Pipelines, already are vying with water carriers and railroads in volume transported, are continuing to gain as the demand for petroleum products climbs from its 1951 average as the demand for petroleum products climbs from its 1951 average of 7.5 billion bbl per day to an expected 8.4 billion by 1955.

Typical of the crude-oil line expansions are: the 1,075-mile 16- to 20-in. line underway from Worland, Wyo., to Wood River, Ill., for Platte Pipeline Co., and the 674-mi 20- to 24-in. pipeline under construction from Drumright, Okla., to E. Chicago, Ind., for Sinclair Pipeline Co.

Typical of what's ahead: a proposed 900-mi 24-in. pipeline from the Permian Basin in west Texas to California for Progress Pacific Pipeline Co.; the planned 986-mi 20- to 22-in. pipeline from Snyder, Tex., to Norwalk, Calif., for West Coast Pipeline Co.

Largest domestic product pipeline planned is a 1,000-mi project for United States Pipeline Co. from the Gulf Coast via Memphis and Nashville, Tenn., Lexington and Paducah, Ky., to Cincinnati, Ohio.

Stronger central control urged in Maryland building

Maryland's system for construction of state buildings is about to get an overhauling.

A new report from the state's "Little Hoover Commission" proposes changes designed to cut red-tape, aid planning, speed construction, provide better supervision, and reduce costs.

In the center of the proposed changes expected to go before the next session of the legislature, is the Department of Public Improvements, main construction agency for all state departments. Said the report: Its functions should be strengthened.

In addition to its present job of making preliminary estimates, DPI should render site-planning services, the report says.

• No project should be included in the state's capital improvement program, until the DPI has completed a thorough study of probable cost. This would reduce occasions where the state takes on construction of new buildings, but the money appropriated is "grossly inadequate."

• DPI, along with the Department of Budget and the State Planning Commission, should work more closely together, and with other department heads in the planning, financing and engineering aspects of the capital improvements program—assigning teams to various phases of it.

• DPI should have final authority to approve change orders not exceeding more than 10% of the amount of the contract—relieving the Board of Public Works of this responsibility.

• DPI should make an effort to keep building costs within approved amounts, if necessary revising plans and specifications to do so. Revisions

also should be approved by the using agency.

• Under DPI supervision, inspection of construction in progress by the architect or engineer should be strengthened by employment of a "clerk-of-the-works," and the architect or engineer should be compensated for this service in addition to his fee.

• DPI should have centralized responsibility for periodic investigation and reporting on the condition of state-owned public works, and should function as a service agency for the departments in the planning and execution of maintenance work.

Also recommended were changes in financial procedure which apply primarily to the Department of Budget and Procurement.

The report was submited by Simon E. Sobeloff, chairman of the Commission on Administrative Organization of the state. It was prepared for the commission by a committee headed by Dr. Abel Wolman, consulting engineer and professor at Johns Hopkins University.

• **Other reports**—The commission also proposes changes in highway administration and in health and welfare administration which affect construction.

A report on highway relationships calls for legislation to encourage cooperation between state and local officials in developing the highway program.

It would clearly define the authority and responsibility within the State Roads Commission and local roads organizations.

Among the recommendations were these:

• Within the State Roads Commission, responsibility for state-local highway activities should be consolidated in a single staff unit.

• Local standards should be developed for road construction and maintenance, and for state and local road classification.

• Ultimately all county road operations should be treated as a local responsibility.

A study on health and welfare administration produced a recommendation calling for the elimination of conflict and overlapping in control of water purity by doing away with the Water Pollution Control Commission and assigning its functions to the State Department of Health.

The recommendations were submitted to Gov. Theodore McKeldin, to the Legislative Council of Maryland, and to the General Assembly. Legislation to put them into effect is now being studied.

Ohio Turnpike paving costs challenged at hearings on asphalt vs. concrete

Hearings in a suit to require the Ohio Turnpike Commission to take bids on both concrete and asphalt paving for the Ohio Turnpike (ENR Nov. 27, p. 24) were continued in Columbus the last two weeks.

Testimony was centered chiefly on efforts by lawyers for asphalt-paving interests in Ohio to show that estimates of the cost of bituminous paving used by the J. E. Greiner Co., consulting engineers for the commission, were unrealistic; also that comparative cost figures submitted to the commission by the Greiner Co. did not cover all the costs going into the two types of pavement.

Principal witnesses were Bernard E. Gray, president of the Asphalt Institute; Charles F. Parker, chief engineer of W. H. Hinman, Inc., general contractors of Maine, and formerly with the Maine Highway Department; W. LeSeur of the J. E. Greiner Co., and J. K. Knoerle, a former employee of the Greiner Co.

Mr. Gray testified that as long ago as May of this year he had advised H. H. Allen of the Greiner Co. that responsible contractors estimated that asphalt paving as specified in the comparative designs set up for the turnpike by the Greiner Co. could be built for $1 less per square yard than the specified concrete pavement.

• **Other arguments**—Mr. Parker's and Mr. Knoerle's testimony related chiefly to soils on which the pavement is to be laid as affected by frost. It was in support of the claim of the companies bringing suit against the turnpike commission that for a true comparison of costs it would be necessary to include the cost of removing a layer of all soils weakened by frost, action from below the concrete pavement.

This would not be necessary in the case of the bituminous pavement, it was stated, because that pavement is specified to be 28 in. thick, or deep enough to be below frost action in Ohio. That would not be true of concrete pavement, the witnesses stated, which with its base would be only 16 in. deep.

Mr. Knoerle estimated that concrete pavement built according to the Greiner designs would cost $59,900,000 as against $52,934,000 in the Greiner estimate of August 4, 1951, and that bituminous pavement would cost $53,400,000 as against the Greiner figure of $55,738,000, or a saving of $6,500,000 through the use of bituminous paving. Mr. Knoerle said he could find nothing in the Greiner estimates to indicate that the contingency of having to replace unsuitable soil under the concrete pavement had been considered.

Other testimony at the hearings related to the comparative costs of maintaining rigid and flexible types of pavement. The Greiner estimates had placed the total cost of maintaining a flexible pavement on the turnpike at $14,228,000 over a 35-year period, and the cost of maintaining a rigid pavement for a like period at $11,956,000.

Algonquin lacks ok to use new pipeline

Algonquin Gas Transmission Co. is out on the end of a limb with a $50-million investment in its New England pipeline system.

The trouble is that Algonquin has most of its system built, but lacks a valid federal certificate to put it into operation. To point up the situation further, Federal Power Commission ruled in a three-to-two decision last week that it has no authority to grant Algonquin a temporary certificate to serve the New England markets.

There may be a resort to the courts on that decision, but thus far they have decided against the Algonquin plan. The only other alternative left to Algonquin is to continue its fight for a permanent certificate before FPC. That it was doing this week at hearings which almost certainly will continue well into December.

FPC gas experts know of no previous case in which $50 million of investment was in the balance.

• **The challenge**—Northeastern Gas Transmission Co., which already has a certificate for about half New England, is putting up a stiff battle for the share claimed by Algonquin.

Northeastern is serving most of the customers assigned to it under a certificate issued by FPC in 1950. These are in Massachusetts, Connecticut and New Hampshire.

The disputed markets, which Algonquin says it could serve within a month if allowed to proceed with present construction, are in Massachusetts, Connecticut and Rhode Island.

Algonquin told FPC it already has spent some $46 million on pipeline construction and probably several million more has been obligated. A large portion of this expenditure would be lost if Algonquin fails to get the certificate.

Report ok's $82-million crossing of Puget Sound west of Seattle

Early construction of an $82-million crossing over Puget Sound was recommended to the Washington State Toll Bridge Authority in a report submitted last week. Authors of the report—consulting engineers Ralph Smillie of New York, John L. Parcel of St. Louis, and Ralph Tudor of San Francisco—confirmed the need for the crossing, concluded that it would be structurally sound and that revenue bond financing would be feasible.

After studying four alternate routes, the board endorsed adoption of the southernmost (Route I). This would provide a floating bridge between the south city limits of Seattle and Vashon Island and a high-level suspension bridge from there to the Kitsap Peninsula. Construction of the crossing would mark the first time a floating bridge of this magnitude would span a tidal channel. Plans are patterned after the successful Lake Washington crossing east of Seattle.

The two-mile-long floating bridge would consist of a series of multi-cell concrete pontoons, each having outside dimensions of 405x65x14 ft. The 48-ft wide, four-lane roadway would be elevated above the pontoons 15 ft to raise it 20 ft above water level and prevent wave action interference with traffic.

The units would be anchored in alignment but free to rise and fall with the tide. Bridging between fixed approaches and the floating highway would be 280-ft-long truss spans with one end supported on a floating pier. Vessels up to medium draft will be able to pass under the approach trusses.

• **Other plans**—Heavy ocean-going ships would have to use Colvos Passage for access to Tacoma to the south. This seaway will be spanned by a 50-ft-wide suspension bridge with a 3,400-ft main span and 1,250-ft side spans. Tower piers will be in 165-ft water depths, necessitating 200-ft deep caisson-type foundations.

A second two-lane-wide, main span suspension bridge would link the Kitsap Peninsula with Bainbridge Island.

The board based its selection on several considerations, including these:

• The selected route will attract the highest traffic volume.

• It is the only one giving access to Vashon Island.

• It offers least navigational interference.

• It involves the least structural uncertainty.



FOUR PUGET SOUND CROSSINGS were studied to determine the most feasible route for vehicular traffic. Consulting engineers favored Route I—a floating bridge-suspension bridge combination.

• It is the least expensive crossing that would provide reasonable good traffic service (Route IV is actually cheapest but traffic volume over it is questionable).

• It will present the least interference with Seattle's internal traffic.

• Water depth is less.

The board said that to insure financing, all ferry routes in the general vicinity of the crossing must be abandoned on completion of the bridge.

Also considered was a floating-tunnel-type crossing. This was rejected because of coast hazard and construction difficulties.

The report was based on studies of plans and foundation explorations. Cost estimates and traffic surveys were made by the toll bridge authority staff under the direction of C. E. Andrew.

The authority approved the report of the consulting engineers and will ask the 1953 state legislature, convening in January, for $770,000 to cover the expense of preparing detailed plans and other information.

Some opposition is expected from Tacoma interests as the crossing will reduce traffic across the Tacoma Narrows Bridge by an estimated 20% and cause some interference with waterborne traffic. This won't affect the financial success of the Narrows Bridge as traffic is far in excess of pre-construction estimates. But it may take business from the city. If the legislature provides funds, construction could begin in two years and be completed perhaps as early as 1958.

• Other planning active

Progress on plans for two new crossings over San Francisco Bay, a toll-financed tunnel under Loveland Pass in Colorado, and a new parkway along the Niagara River—highlighted other transportation developments across the country last week.

• **New crossings**—The Bay Area Council in San Francisco threw its weight behind Mayor Elmer E. Robinson's revival of plans to build two new bay crossings simultaneously.

Under consideration: (1) A $170-million bridge from north of Market St. to Yerba Buena Island to Oakland, (2) an $80-million crossing from south of Hunters Point to Alameda County, (3) a $170-million bridge paralleling the present San Francisco-Oakland Bay Bridge, (4) a $200-million crossing from Army St. to Alameda.

The council said $250 million—the limit on financing new projects—could be raised by:

• Increasing tolls on the San Francisco-Oakland Bay Bridge.

• Increasing the tolls suggested for the new crossings.

• A proposed $50-million increase in bonded indebtedness of the San Francisco-Oakland Bay Bridge now



waiting State Supreme Court decision.

• **Toll tunnel**—Colorado's State Highway Commission has before it a recommendation by the state legislative long-range highway planning commission for construction of an all-weather toll highway with a tunnel under 12,000-ft Loveland Pass crossing the Continental Divide.

The tunnel would be 5,400 ft long, with its roadbed 710 ft below the summit of the pass. It would by-pass four and one-half miles of the pass. The committee's report said a 32-ft wide bore could be drilled under the pass on U. S. Route 6 at a cost of $7 million. Two one-way tunnels, each 18 ft wide, would cost only about $6.5 million.

The tunnel or tunnels would follow the line of a pioneer bore drilled by the State Highway Department several years ago. Tolls of 75 cents for passenger cars and light trucks and $2 for medium and heavy trucks were recommended to amortize revenue bond issues.

• **Niagara parkway**—The Niagara Frontier Park Commission has announced a $64-million plan for developing park and parkway facilities along the Niagara River. Major project of the plan is a $42-million divided highway along the Niagara River (see map). It will join Grand Island's West River Parkway, Grand Island Parkway, and the New York State Thruway. Plans for financing the program are expected to be submitted to the next session of the legislature.

Florida bridge near completion

Jacksonville, Fla., city officials are busy making plans to dedicate the $12.5-million John E. Mathews Bridge on Dec. 27. The 7,375-ft-long bridge, key structure in the Jacksonville expressway system, will carry four lanes of traffic.

The east side approach to the main span is 3,447 ft long, including three truss spans totaling 986 ft. The west approach is 2,306 ft long. The main span over the terminal channel consisting of two anchor spans each 406 ft long and a central span 810 ft long, measures 1,622 ft in overall length. Crown of the roadway is 161 ft above St. John's River at mean sea level.

Steel erection by Bethlehem Steel Co. was completed late last month (see accompanying photos). Most of the substructure was constructed by Merritt-Chapman & Scott Corp.





THE 67-FT CLOSING CHORD MEMBER rises from a barge . . . to join two cantilevered arms of the main span.



STEEL ERECTION COMPLETED, flooring of reinforced concrete and decking of steel grid on the main span, is being readied for the bridge dedication Dec. 27.

ASCE section offers Texas water policy

When in 1951 T. C. Forrest, Jr. (see also p. 64) assumed the presidency of the Texas section, American Society of Civil Engineers, he led the section into assuming some responsibility for one of the state's knottiest engineering problems: water resources.

And recently, Gov. Allan Shivers received his copy of a summarized statement intended as a guide in engineering concepts of a sound water policy. A year of research by a five-man committee from the local ASCE section had produced the document, called "A water policy for Texans."

• **Recommendations**—Noting the importance of water to Texas and the present troubles with drought, the report stresses need for:

• A complete new surface water code, or at least separate acts to remedy present ills.

• Statewide regulation of groundwater supplies.

• Legislation to centralize pollution abatement in an agency with authority and funds.

• Provision of authority and funds for the existing State Board of Water Engineers, administrative group.

• Reestablishment of the principle of state ownership of waters so that proposed federal uses of water will require approval of the governor after public hearings by the State Board of Water Engineers.

• Amendment of the National Reclamation Act so that the U.S. Bureau of Reclamation can operate effectively in Texas (on other than municipal supply problems).

• Cooperation of the state (even to the extent of contributing funds) toward inclusion of conservation benefits in Corps of Engineers projects.

• State approval before any Dept. of Agriculture reservoirs are built.

• Expansion of water studies with the U.S. Geological Survey.

• Amendment of federal law requiring a 50-year recapture clause under licenses from the Federal Power Commission.

• Support of the Engineers joining council's recommended principles of a sound water policy.

• Compacts for control over interstate streams.

• State financial assistance for local projects as a means of avoiding use of federal money.

The Texas section's Committee on State Water Policy, making these recommendations, was: Simon W. Freeze, James A. Cotton, G. Lockwood, Houston; Harry N. Roberts, and R. A. Thompson, Jr.



Alcoa starts up another new plant

Aluminum poured from the first operating potline of Aluminum Company of America's Rockdale, Tex., Works last week. A second potline will be ready for production this month, and the third and fourth lines are scheduled for completion next spring. When all are in operation the new $115-million installation will produce about 170,000,000 lb of aluminum a year.

For Alcoa it marks another milestone in a current $350-million expansion program. This summer brought in an expansion of smelting facilities at its Point Comfort Works, in Texas; finishing touches are going on a $60-million smelting plant at Wenatchee, Wash., this month. Two months ago Alcoa started production at its $55-million Bauxite, Ark., alumina works; last week it announced it would build another $5-million addition.

Altogether, when these new projects are in full operation, they will boost Alcoa's annual capacity to produce aluminum by some 410,000,000 lbs. Coupled with current expansion by Kaiser Aluminum and Chemical Co., Reynolds Metals Co., Anaconda Copper Co., and Olin Industries—they will be of great help in pushing the total output of aluminum toward the 3,000,000,000-lb rate by the end of next year.

The Rockdale plant just going into operation, will be the first in the country to use electric power generated by burning lignite. The power plant is being designed and built by Ebasco Services. Bethlehem Steel Co. fabricated and erected 11,000 tons of structural steel for the plant's 20 acres of buildings (See photo above). Al Johnson Construction Co. did the concrete work.

Still in the offing: Alcoa's proposed $400-million aluminum smelting project near Skagway, Alaska. Legislation to expedite this project will go before the next session of Congress.

Harvey plans aluminum plant in Northwest

Another aluminum reduction plant in the Pacific Northwest is projected by Harvey Machinery Co. The plant with an annual capacity of 45,000 ingot-tons would be located near The Dalles, Oregon, and use electricity to be generated at McNary Dam.

Lawrence, vice president of the machinery firm, said work on the $45-million project would begin as soon as Defense Production Administration allocates needed construction materials.

In Washington, a spokesman for DPA's Office of Aluminum reported that the Harvey proposal had not yet been approved. Main reason for delaying a decision, the spokesman said, is that final arrangements have not been presented for financing.

Bauxite from Surinam on the Caribbean coast would move by ore carrier to The Dalles, via the Columbia River channel and Bonneville Dam Locks. The inland river port has had ocean barges and small freighters berthed at municipal dockside, but on rare occasions.

The Pacific Northwest is currently curtailing firm power industrial loads because of summer drought-induced shortages of water in the Columbia's reservoir, and this may figure in whether the DPA approves additional primary aluminum loads in the region. Sources close to both Harvey and The Dalles interests admit there is opposition.



GEORGE MEANY (at microphone) newly elected president of the AFL at a press conference watched by the AFL elder statesmen. (ENR photo by Compton)

Building trades veteran heads AFL

By Joe Gambatese
Washington Staff

The building trades unions this week hailed one of their own as the fourth president of the American Federation of Labor—George Meany, plumber and son of a plumber.

AFL secretary-treasurer since 1939 and actually running the AFL during the recent illness of President William Green, the 58-year-old former business agent of a New York City plumbers local was the natural, and unanimous, choice of the AFL executive council to succeed the late William Green.

Green, a miner, died Nov. 21 at his home in Coshocton, Ohio. He was 82 and had been president of the AFL since Samuel Gompers' death in 1924.

On Jan. 1, William F. Schnitzler, 48, president of the Bakery & Confectionery Workers, will become secretary-treasurer of the AFL. This will give the AFL a rather youthful front-office leadership, by AFL standards, although old-timers still run the 13-member executive council. Septuagenarians William L. (Big Bill) Hutcheson of the carpenters and Daniel J. Tobin of the teamsters have relinquished the presidency of these unions—largest two in the AFL—but keep their seats on the executive council, the AFL's powerful ruling body.

Meany is an able union leader, aggressive, outspoken. He can hold his own with the best of them, will put new vitality into the AFL, which until recently was overshadowed by the younger, more imaginative CIO. He is cheerful, friendly, yet adamant.

What does Meany's ascendancy to the top of the AFL mean to the construction industry? To the AFL and the labor movement as a whole? To the country?

Meany's elevation was a popular choice among AFL leaders, and this was especially true among those in the building trades.

President Richard J. Gray of the Building & Construction Trades Dept. is a Meany booster from back in the days when the new AFL president was active in the New York Federation of Labor. Gray, former business agent for a bricklayers local in Albany, backed Meany for vice president of the New York Federation in the 1920's. Meany was elected and, in 1934, became president of the state body and served until he became AFL secretary-treasurer in 1939.

Gray's high regard for Meany is reciprocated by Meany, who included Gray among several labor leaders he suggested to President-elect Dwight D. Eisenhower for Secretary of Labor. This despite the fact Meany was one of those who was largely responsible for the AFL convention making a presidential endorsement—for the losing Democratic candidate, Gov. Adlai E. Stevenson—for the first time since 1924.

Gray himself liked Ike, felt the AFL should not make any commitment for either candidate.

Others echoed Gray's applause for Meany, including President Daniel W. Tracy of the Electricians and President William E. Maloney of the Operating Engineers. Even President Albert J. Hayes of the Machinists described Meany as the "logical choice" for the top job.

• **Disputes**—There remains, of course, the problem of jurisdictional disputes in the building trades crafts. The National Joint Board for Settling Jurisdictional Disputes in the construction industry will not be affected by the change. The board is the creature of

(Continued on page 31)

McKIERNAN-TERRY PILE HAMMER *helps build a dam in* India

The land of the Taj Mahal is going modern in a big way. In fact, the Damodar River project, which includes two dams and a steam power station, will supply power for the most highly industrialized region of India. Harza Engineering Company served as consultants on this project.

Naturally, a McKiernan-Terry Pile Hammer was called on to do a vital pile-driving job on this $142,000,000 project. Hundreds of steel piles for the cofferdam, shown in the photographs, were punched down with a McKiernan-Terry No. 7 Double-Acting Hammer.

Yes, in the far corners of the world . . . as well as on hundreds of pile driving jobs in the United States . . . McKiernan-Terry Pile Hammers and Extractors are the first choice of contractors. The wide range McKiernan-Terry line includes 16 sizes of hammers and 2 sizes of extractors. Bulletin gives full details. Write for your copy.



McKiernan-Terry
No. 7 Double-Acting Pile Hammer

OTHER McKIERNAN-TERRY PRODUCTS



MEAD-MORRISON COAL AND ORE UNLOADERS AND BRIDGES
Available in a variety of designs and in capacities of 300 to 1500 tons per hour. Exceptional durability proven by installations in service for half a century. Simple controls afford convenient, comfortable and speedy operation.

GRAB BUCKETS
Range of types and sizes take bulk materials loads up to 25 tons. Ruggedness without excess weight.

HONING UP TO 42-IN. I.D. X 55-FT. LONG
Typical of the extensive facilities of McKiernan-Terry for unusual jobs.

McKIERNAN-TERRY CORPORATION
Manufacturing Engineers
13 PARK ROW, NEW YORK 38, N.Y.
Plants: Harrison, N.J. and Dover, N.J.

McKIERNAN TERRY

MK 318

the Building Construction Trades Dept. and the construction industry. It will continue, with improvement from time to time. The problem of the "withdrawal" by the International Brotherhood of Electrical Workers will come up for discussion at the next meeting of the building trades executive council at Miami in February.

But there are disputes which extend beyond the building trades, notably that involving the machinists. The machinists, not a member of the building trades group, have been running into conflict with the carpenters and operating engineers on construction projects. Meany plans to dig in and try to clear up these and other jurisdictional squabbles.

The AFL executive council has taken steps several times to clear them up, without luck. Meany takes a practical view.

"Decisions don't settle anything," he says, pointing out that sometimes more can be accomplished by individuals. He intends to use personal persuasion to achieve intra-AFL peace.

The machinists are hopeful. Haves says they have no intention of pulling out of the AFL again.

"We are in the AFL and we will remain in the AFL," he told ENGINEERING NEWS-RECORD. "We have problems, and they will be cleared up."

• **Executive council**—Building trades strength on the executive council is not affected by the change. The 19 building trades unions, with 3,000,000 members, continue to have five of the 13 places on the council, not including Meany. Elevation of Meany and selection of the under-50 Schnitzler for secretary-treasurer may speed up the placing of younger men on the executive council. Tobin, Hutcheson and Herman Winter, former president of the Bakery & Confectionery Workers, have all been retired by their unions but have hung on to their places on the executive council.

Some top AFL circles feel that those who are too old to serve their unions as president should not serve on the executive council. This subject will be discussed at Miami on Feb. 2.

• **More militant**—The AFL should become more militant under Meany, with the CIO a prime target despite Meany's proffer of unity. Meany wants to raise AFL membership, already at a record level around 9,000,000 (8,098,000 paid per capita tax on June 30). He gave the AFL textile workers inspiration to engage the CIO in a struggle now in progress for dominance in the textile industry. In six months, the AFL has gained 20,000 new members in textiles.

CONGRATULATIONS ARE GIVEN to George Meany by old friend and backer, Richard J. Gray (left), president of the AFL Building Trades Dept.

Meany is against functional unity with the CIO. He was responsible for the breakup a year ago of the United Labor Policy Committee, through which the AFL and CIO worked together on mobilization problems. Meany wants "organic unity."

"We can't work together without organic unity," he says, asserting that his role in breaking up ULPC shows his desire for bringing about complete unification.

The AFL is reactivating its nine-man committee which held unity talks with the CIO in mid-1950. But Meany will leave it up to the CIO to make the first move toward resumption of those meetings. Meany will not insist on Green's oft-repeated position that the CIO must "return to the house of labor," like a prodigal son. But he will want the CIO to recognize that the AFL is twice as big and has been around for 71 years. **In other words, Meany will be president of any new organization, or there won't be any.**

New leadership in both AFL and CIO should intensify the inter-union rivalries. This means increased activity in the legislative and political areas as well as in organizing and bargaining.

• **Taft-Hartley**—Meany is reconciled to revision, rather than repeal of Taft-Hartley. A committee headed by AFL Vice President Matthew Woll is making an analysis of AFL experience under various parts of the law for presentation to Congress. This includes the experience in the construction industry.

Meany told Eisenhower, just a few hours before Green's death, that the AFL will continue to press for improvements in the standard of living and in legislation affecting labor. And it will fight any attempts "to push labor back."

• **Background**—Meany, a Catholic, has always fought Communists. He denounced the World Federation of Trade Unions, which the CIO helped organize at the end of the war and which the AFL refused to join because of its tie with Communist unions. Later, when the CIO took the same view and quit the WFTU, Meany helped organize the International Confederation of Free Trade Union with both the AFL and CIO unions participating.

Meany was born in New York in 1894, son of the president of a plumbers local. He got his plumber journeyman's card in 1915, was elected a local business agent in 1922. During the five years he was president of the New York Federation of Labor, 1934-1939, the state passed more pro-labor legislation than in any previous period.

Meany has four daughters, lives in Bethesda, Md. Like Eisenhower, he loves golf, but can't play as much as he would like. When he does, he drives a hard bargain with his opponent on the first tee. He shoots a respectable game in the 80s at Columbia Country Club, one of Washington's better clubs. His salary is $25,000.

Strike for same-union subcontractors does not violate Taft-Hartley

There is no violation of Taft-Hartley where a union strikes to force an employer to agree to select only subcontractors having contracts with the same union.

The new application of the Taft-Hartley jurisdictional strike ban by the National Labor Relations Board was made last week. It cost Anheuser Busch a round in its fight with the AFL machinists over the right to select contractors for extra machinery installation work, and it may have a far-reaching effect on the construction industry.

NLRB dismissed a complaint by the company alleging IAM conducted a jurisdictional strike at the St. Louis plant. Just what Anheuser Busch can do now is not clear, but the ruling does not wind up the matter by any means.

• **Feud**—Behind the action last week is a long history of strikes and feuding between the machinists and the AFL carpenters union at Anheuser. Both unions have contracts covering separate groups of Anheuser's inside employees. But the trouble stems from Anheuser's practice of hiring outside contractors for machinery repair and installation known as millwright work.

Anheuser operations require constant additions and improvements in its facilities. The company sometimes uses its own employees for such work, but frequently hires outside contractors for the job. Both the IAM and carpenters want Anheuser to exclude contractors having bargaining agreements with the other union.

As far back as 1939, the carpenters struck to protest assignment of millwright work to IAM contractors.

In 1949 IAM signed a contract with Anheuser which, among other things, limited outside contractors to those having agreements with IAM. The same provision was dropped from the 1950 contract but put back into the 1951 contract.

• **Threats**—Meanwhile the carpenters and the St. Louis Building and Construction Trades Council notified Anheuser that no contract between them could be signed until the IAM contractor provision was stricken. The Associated General Contractors were also told that no work on Anheuser projects would be performed unless all work—including millwright work—was performed by AFL Building Trades craftsmen.

And, during 1950 and 1951, the carpenters stopped work on several Anheuser projects because those terms were not followed.

In order to get the work finished, Anheuser gave written assurance to the carpenters that, after the 1951 IAM contract expired, the company would not renew the contractor provision.

IAM tried to renew the provision in 1952 negotiations but the company refused, living up to its promise to the carpenters. In protest, the machinists walked off the job and set up picket lines around the plant.

• **Enter Taft-Hartley**—Under the Taft-Hartley law, a strike to force an employer to assign particular work to members of one union rather than to members of another is illegal.

Anheuser charged that the IAM strike, as a demand for the contractor limitation, amounted to a violation of this section of the law.

But the labor board said no.

At the time of the strike, only one of several construction projects at the plant required millwright work—and that was being performed by an IAM contractor. Because of that fact, said the board, the strike was not over a work assignment of the employees of a contractor doing millwright work for Anheuser.

In previous decisions on jurisdictional strikes, the disputes arose when two or more unions claimed the same work assigned by the employer. Here, said the board, there is no dispute over work assignment to any of Anheuser's employees, but over IAM's demand to limit Anheuser's selection of contractors by terms of a collective bargaining contract.

Therefore, said the board, this dispute—including IAM's demand and its strike—is not the same thing as a "present demand for the assignment of work" outlawed by Taft-Hartley.

Chairman Paul Herzog and members Murdock, Styles and Peterson signed the NLRB opinion.

Informing doesn't help

Wage-control violators who "inform" on others will not get any special consideration when it comes to their own penalty. The National Enforcement Commission has made that clear in a case involving Miami Plastering Co., Miami Beach, Fla.

NEC rejected a settlement reached by its regional commission in which Miami Plastering Co. agreed to have $1,398 of its payroll disallowed as a cost deduction for tax purposes. This amount represented only one-third of the excess wage payments of 25 cents an hour the firm paid to plasterers over a three-month period last year. Total payroll in violation amounted to more than $16,000.

The regional commission cited the Miami Plastering Co.'s cooperation in naming other probable violators as a mitigating circumstance in agreeing to the light penalty. NEC rejected "informing" as a mitigating factor and instructed its regional officials to reconsider the case.

Wage control violations draw $75,000 tax penalty

The largest penalty yet imposed for violation of wage controls has been agreed to by the builders of "Hoffman Heights" homes in Aurora, Colo., a suburb of Denver.

The government and two companies owned by the same family—F. & S. Construction Co. and Hoffman Plastering Co., both of Phoenix, Ariz.—agreed that $75,000 in excess wage payments will be disallowed as a cost deduction for income tax purposes by the Bureau of Internal Revenue, according to Reid Williams, regional counsel for the Wage Stabilization Board.

The amount is double the $38,000 disallowance against Hedin Construction Co. (ENR April 24, p. 32) in the first big construction-industry enforcement case.

The $75,000 represents above-ceiling overpayments in wages to bricklayers, cement finishers, plasterers, lathers, plasterer tenders and mason hodcarriers, covering the entire stabilization period from Feb. 1951 until the present. The government had 37 witnesses ready to testify at a public hearing in Denver last week when the settlement was reached.

Investigation of the two company payrolls was directed by WSB from Washington after complaints reached the Capital that the illegal wages were disrupting normal wage scales and that scarce construction workers were being pirated.

The contractors have also been building homes in Pueblo, Colo.; Albuquerque, N. M.; Cleveland, Ohio; and Phoenix and Tucson, Ariz.

DRIVE-IT

FASTENS WOOD TRIM TO STEEL WINDOWS AT IBM



Wood trim was fastened to the steel window frames with Drive-It at the new IBM plant at Poughkeepsie, New York. Over 20,000 drive pins were used by Stewart-Scott Construction Corp. Drive-It offered the quickest, easiest, most economical method. No drilling, tapping or power lines.

split-second fastening to concrete steel

Drive-It uses a small powder load to drive hardened steel pins into concrete or steel. No power lines! No drilling!

UL

DRIVE-IT, the *first* powder actuated tool approved by Underwriters' Laboratory.

DRIVE-IT cannot be discharged accidentally due to the push and turn sequence. This, plus the large safety pad makes *DRIVE-IT* triple safe.



Exclusive Automatic Barrel Extension for fastenings inside junction boxes or other recesses.

DRIVE-IT is the only powder-actuated tool which requires but one standard power load regardless of penetration desired.



Exclusive Swivel Safety Pad easily rotated for getting into close quarter work.

DRIVE-IT "300", lowest cost fastening tool. Low original cost and low operating cost.



OVER 50 TYPES AND SIZES

See our *display*, **PLANT MAINTENANCE SHOW,** Cleveland, January 19-22, 1953.

MAIL THIS COUPON TODAY!

POWDER POWER TOOL CORP.

0716 S. W. Woods St., Portland 1, Oregon

Canada: Ammo Power Tool Co., Ltd.
735 Broadway, Vancouver, B. C.

☐ Please send FREE catalogue and literature.
☐ I want a FREE demonstration of *DRIVE-IT*.

Name_____

Street_____

City_____ State_____

Levittown, Pa. . . . a city from scratch

Arthur J. Fox Jr.
Associate Editor

WHILE LEVITT the homebuilder whips together 40 houses a day with a practiced left hand, Levitt the city-builder—a new alter ego—tries an agile (if less experienced) right hand at municipal engineering.

Levittown, Pa., may become the Quaker State's tenth largest city. And Levitt & Sons, world renowned builders of houses, this time will wrap up a complete community.

This is not to say that the 17,500-home Levittown on Long Island is just so many houses. Far from it. Brother Alfred Levitt had his hand in laying out what is considered to be a well-planned residential community. But the new Levittown—where over 2,000 of an eventual 16,000 families are already settled in 3,000 completed units—has demanded planning, plus.

There, on a vast tract of Pennsylvania farmland near Trenton, N. J., a municipal entity to house Fairless Works steelworkers (among others) is being built from scratch.

There were no ready water suppliers big enough to tie in with; land to be developed was not the uniform, absorptive sand that makes most of Long Island a cesspool paradise; there was no simple solution to the problem of draining the 6,000 flat, river-valley acres.

(On Long Island, Levitt was able to space borrow pits all over his project, later run storm sewers to them, fence them in and call them groundwater recharging basins.)

CLARENCE A. MONROE . . . Levitt's chief engineer (left), was a consultant on land planning and municipal engineering before joining the famed homebuilder 17 years ago. Earlier experience as a civil engineer in highway and railway jobs followed correspondence-school education. He's a young-looking 52.

NORMAN DENNY . . . 32-year-old vice-president in charge of purchasing and supply (right), heads up subsidiary North Shore Supply Corp. He came to Levitt from the Navy in '46 after service as a Seabee supply officer; succeeded deceased predecessor in 1947 to take over big supply and logistics job.



PUMPING STATIONS and sewers were designed by Levitt's own engineers. Utility poles go in and power is delivered as families move into the area this station serves.



STORM WATER DRAINAGE will be grassed and graded open-channels and concrete pipe up to 48-in. diameter, as in this triple culvert.



UTILITY CONSTRUCTION requires coordination to keep up with the mass production of houses. The scraper-ditcher team prepares for sidewalks and streetlight cables.

MID-SPAN CONNECTION of house lines to power lines running along the rear of property made possible great savings in poles.

• **Costs can't wander**—The way the Levitt operation is organized it is Brother Bill Levitt's job, as president, to build and sell houses. It is Chief Engineer Clarence A. Monroe's worry to keep the house costs profitably under the sale price.

With its mass production methods and its great experience, the Levitt organization by this time knows what it costs to build a house—down to the nearest couple of cents. And fairly easily it can break down to a per-house basis the price of septic tanks, streets, water pipe or recreation facilities. But the building of a water supply, sewage treatment plant, and an extensive drainage system were new and formidable problems for Levitt—full scale municipal problems, all inextricably tied in with the set $10,500 price of a house.

The fact is, $22 million worth of water supply, sewerage, land development and recreational construction will go into Levittown, Pa. Half the man-hours to be spent in building the place will go into site preparation and community facilities.

For these facilities Levitt has lots of engineering brains. Under Clarence Monroe a fluctuating force now 40 strong picks up with the original land surveys and goes through all design of streets, sewers, drainage structures, gas and electric utilities, parking facilities and commercial buildings.

Meanwhile, Norman Denny, as boss of the subsidiary North Shore Supply Corp., works his staff of 10 engineers in the buying and supplying of all materials, plus supervising a myriad of small contractors engaged in some step or other in mass producing houses.

• **Everything regimented**—North Shore Supply Corp., wholly owned by Levitt, operates in a singularly peculiar manner. It is at one and the same time owner's representative and general contractor, responsible for all the logistics and construction operations right up to the on-site assembly of the house. Briefly, this includes maintenance of one mile of railroad siding, 40 acres of materials, stock yards, 10 acres of prefabrication shops, a 2,500-cu yd per day, $165,000 concrete plant—plus coordination of all subcontracted materials-handling operations.

Subcontractors under North Shore unload freight cars; precut and package lumber into "house bundles"; prefabricate plumbing; build formwork or deliver materials to the site. It is said that Levitt's forces at the home-site can put together a house with hatchets, just trimming and nailing with no need to use a saw unless a piece breaks, requiring replacement.

These subcontractors, it should be noted, are mostly long-time Levitt associates. Many were foremen in the Long Island operation. As an incentive to productivity, Levitt saw early in the game an advantage to setting a man up as boss of an operation and giving him a contract for the whole job, rather than a wage. Some of these Levitt-made specialty contractors have left the fold. But many followed along to the Pennsylvania job. There is no competitive bidding; the contractors and Levitt just "bang heads a while" and come up with a negotiated price for the work involved.

• **Engineering talent added**—Despite his concentration of engineering brain power and his inbred contracting arrangement, the world's biggest private home-builder had to seek help on some of the new (to him) problems in Pennsylvania. Levitt engineers laid out and designed drainage and sewerage; Albright & Friel were consulted for a check on this work. And the Philadelphia consulting firm fully designed sewage-treatment facilities. Hydrotechnic Corporation and Geologist Max Legette, both of New York, consulted on water supply and purification.

Water supply and sewage facilities

SEWAGE WORKS, complete activated-sludge treatment for 70,000 people, was designed for Levitt by a consultant, as was shallow-well water supply on the Delaware River shore. Contractors bid before sewage plant design was complete.

for Levittown, Pa., have been described generally in ENGINEERING NEWS-RECORD's earlier (May 15, p. 51) story of Fairless Works' impact on the whole lower Bucks County region.

Design of these utilities is for the most part conventional. Speed—in getting them under contracts and built—was what distinguished their construction.

In sewage disposal, having primary treatment and chlorination ready for the date of first occupancy of homes was the basic problem. Albright & Friel were called upon to design the works in late August, 1951. The first families arrived June 23, 1952.

• What treatment for sewage?—Basis of design had to be arrived at quickly. Conferences were held by the consulting firm with Clarence Monroe, Fred J. Biele, his sanitary engineer, and the Pennsylvania Department of Health. Decisions were made on whether to allow for possible industrial wastes or use of garbage grinders. (No definite type of industrial wastes could be foreseen and provision for ground garbage was figured as an unjustifiably added half-million-dollar cost of plant, so both decisions were negative.) A plant to serve 30,000 persons now, as many as 70,000 later, was considered—with complete activated sludge treatment of the domestic sewage.

Several contractors were called to quote lump sum bids, based on outline plans and guided by complete plans for another, similar plant. The three bids submitted on this basis varied less than 10%, high to low. The contract went to R. M. Luff Construction Co. of Willow Grove, Pa.

Bids received were interesting in that in their price for a plant to serve the future 70,000 population they were only 30% above a price on a plant to serve 30,000. Levitt decided to go ahead with the expanded plant, take the more than double capacity at the 30% increase in cost.

Construction began Jan. 1, 1952, and by May 1 primary settling tanks, chlorination facilities and the outfall to the Delaware River were ready to use. Primary treatment awaited first occupants of Levittown, Pa. By the end of '52, secondary treatment will be available; the plant will be finished completely by next May.

The nature of the community dictated some design features. Levittown land is at a premium, desirable for commercial development. So the plant had to use up as little space as possible, create no nuisance, and offer a pleasant appearance. Thus:

1. There are no sludge drying beds; sludge is to be vacuum filtered, and wet cake will be disposed of to farms.

2. To avoid septic conditions, all channels are aerated from primary tank effluent through secondary tank influent.

3. A spray system is being installed at the surface of aeration tanks to minimize frothing.

4. The plant will be landscaped to look like a high-class industrial establishment. But frills and expensive interior finish have been avoided in the interest of economy.

Sewers throughout the city were designed by Levitt's own engineering force, and their design was checked by Albright & Friel. It was not only required to have house connections made to completed sewers when families moved in. It was also necessary to have water flowing in the sewers to prevent septic conditions from developing before design flow of sewage could be attained. A flow of 100,000 gpd had to be introduced from the start to carry sewage to the disposal plant. Eight pumping stations throughout the system eventually will boost sewage across the flat terrain toward its treatment.

• Water supply and distribution—Water comes from five shallow (40-ft) wells in the bank of a bay on the Delaware River—a bay that has been manmade by dredging operations of War-

ANNOUNCING

A new Dodge truck parade of power!





NEW! More powerful engines!

A parade of power! See the new Dodge "*Job-Rated*" trucks at your Dodge dealer's today. A total of 7 big, rarin'-to-go engines, including 3 brand-new power plants with high compression ratios and higher horsepower, greater cooling capacity, increased displacement, twin carburetion available on larger models. Plus famous features like 4-ring pistons with chrome-plated top ring, exhaust valve seat inserts.

In addition, the new Dodge trucks offer outstanding new brakes, new no-shift transmission, and over 50 other new features. See your Dodge dealer for the biggest truck buy on record!

For a truck, ½-ton through 4-ton that fits the job, see the NEW...

NEW! Extra-powerful brakes!

Stop easily on steep grades, fully loaded. Super-safe brakes give silky-smooth braking, reduced driver fatigue, greater load protection . . . new increased stopping ability on 1- through 2½-ton trucks! *PLUS* Dodge's oversize braking surface with Cyclebond linings.



NEW! Truck-o-matic transmission!

New Truck-o-matic transmission . . . available on ½- and ¾-ton models of Dodge "*Job-Rated*" trucks . . . saves shifting, cuts driver fatigue, lets you rock out of snow, mud, sand. Only Dodge offers shift-free Truck-o-matic! *PLUS* famous gyrol Fluid Drive, to lengthen truck life, protect your load.

NEW! Over 50 features!

50 ways new! Reinforced cab construction, improved exhaust system, extra-capacity radiators. Tinted glass, heaters with stepped-up heat output available. *PLUS* moistureproof ignition, high-torque capacity starting motors, and other dependability features. See your Dodge dealer.

DODGE "Job-Rated" TRUCKS

At your dealer's, Thursday Dec. 4th

it takes experience...



Torrington has had many years of experience in the manufacture and application of all types of anti-friction bearings. It knows the advantages of each bearing and the requirements of almost every kind of mechanical equipment. Thus, manufacturers and users of everything from hand tools to rolling mills have learned to rely on Torrington for improved bearing performance.

Next time you have a friction problem, call your nearest Torrington office. They will be glad to help you select the bearing best suited to your application.

THE TORRINGTON COMPANY
South Bend 21, Ind. Torrington, Conn.
District Offices and Distributors in Principal Cities of United States and Canada

TORRINGTON BEARINGS

Spherical Roller • Tapered Roller • Straight Roller • Needle • Ball • Needle Rollers

ner Sand & Gravel Co., Philadelphia. Pumps actually draw river water in through the gravelly river bank, as well as tap groundwater.

When Hydrotechnic Corp. was consulted on water supply, it was told only the land area and an estimated population density. And, it was told when water would have to be available. Before a single house had been started a complete schematic distribution system was sketched as a basis for the waterworks design. And now that houses are being completed, the final design and construction of the distribution system must keep ahead.

Speed required by the necessarily early delivery date influenced design and construction—as with the sewage works. Shallow wells were chosen not only as the cheapest water source but as the source that could be made to produce soonest. Each of the five wells now in use is rated at 1,050 gpm; five more are proposed.

Eventually, supply must be built up to meet an expected 15-mgd demand. This demand is based on 100 gal per capita per day and no industry.

Two 750,000-gal elevated storage tanks will serve the system. One of these is now under construction. Thus far, water has been pumped directly to the point of consumption, with special pressure-relief provisions built into the system. The present supply is chlorinated but requires no other treatment. One well is on auxiliary power for operation in the emergency of a power failure.

Three deeper wells in Levittown draw water for air conditioning use in commercial buildings. Deep wells in the area were discounted as domestic water supply because of objectionably high iron content.

• **Storm water**—Storm water drainage is a problem of some proportion, for this city is partly on flat, relatively impervious land. Drainage lines get up to 48-in. diameter—then drainage ditches take over. Ditches reach 60-ft bottom width, will be graded to 1 on 1 side slope and will be seeded. As pictured in the accompanying illustration, batteries of big-diameter concrete pipe culverts carry drainage ditch flow under roads and streets.

Some 150 miles of streets will be built before Levittown, Pa., becomes a city. Widths are 26 and 34 ft. Arterial and feeder routes are dual 22-ft roadways divided by 20-ft center strips. Five-inch unreinforced concrete slabs are laid first, curb to curb. This surface is used by traffic throughout construction. With some $40 million worth of houses already built, the work of putting asphalt on streets was just started in October.

• **Utilities conveniently located**—Sewer pipes are buried at rear property lines, so streets won't ever be dug up for services. Only street lighting cables and water mains run in front of the houses, and these are buried alongside the sidewalks.

Power lines are strung from poles along rear property lines. And the number of poles needed has been cut about in half by Levitt's success in selling the mid-span connection (illustrated) to Philadelphia Electric Co. for its first large-scale application.

Some $25 million worth of commercial buildings is planned for shopping centers. And in addition there are Levitt's administration building plus his house sales layout of home and building product exhibits. Recreation areas will take up 200 acres of space. The largest single portion of this will include a 30-acre artificial lake now being dug near the center of the future city as construction forces work it for borrow.

Lastly, school sites sold at cost, and church sites, deeded over gratis by Levitt, will round the development out into a city.

Dam pouring speeded

Concrete pouring, delayed until a month ago, is being pushed in a race with the weather by contractors for the $58-million Folsom Dam on the American River near Sacramento, Calif.

The pouring was held up when contractors Merritt-Chapman & Scott Corp., of New York, and Savin Corp., of Hartford, Conn., had to excavate deeper for foundations than had been anticipated. Soft granite, showing signs of disintegration and sliding, was encountered, even though core drill samples had indicated the original foundation depth to be sound.

Aim now is to pour enough concrete to raise the dam to stream level. A tunnel diverting the river's flow is not big enough to handle heavy winter storm flows of the American, and a washout of the upstream cofferdam would undo much of the excavation work if the stream level is not reached.

Meanwhile, work on Nimbus Dam, the reregulating dam for the Folsom power plant, is proceeding on schedule. The dam and 162,000-kw power plant are slated for operation by late 1954 or early 1955.

Contractors for the job are Winston Bros. Co., and Al Johnson Construction Co., of Minneapolis, Minn. First concrete pouring began Oct. 22.



HERE IS THE FIRST 4-cu yd bucket of concrete being lowered for Monolith 28 at Folsom Dam guided by Michael Krumpotic, left, concrete foreman for the contractors, and Robert B. Jenkinson, project engineer for the Corps of Engineers.



FIG. 1. JOINT to be tested, made with one rivet, was placed between . . .



FIG. 2. TWO SEMI-CIRCULAR DISKS in a tension testing machine so that . . .



FIG. 3. OBLIQUE FORCE could be applied to create both shear and tension.

How much combined stress can a rivet take?

T. R. Higgins
Director of Engineering
American Institute of Steel Construction
New York, N. Y.

and

W. H. Munse
Research Associate Professor
University of Illinois
Urbana, Ill.

DESIGN SPECIFICATIONS are pretty much in agreement on how much shear to allow in a rivet. But they are far apart on how much tension a rivet might carry, let alone on what to permit for a combination of tension and shear. So the Research Council on Riveted and Bolted Structural Joints sponsored laboratory tests to learn how much combined stress a rivet can take.

The test results indicate the type of revisions of present design specifications for tension and shear in rivets that might be warranted.

Two somewhat dissimilar conditions arise in engineering practice for which specification provisions would be desirable. The first involves a determination of the maximum tension stress that may be permitted in a rivet subject to a given amount of shear, or conversely, the maximum shear stress that may be imposed on a rivet loaded with a given amount in tension. The second concerns the proportioning of rivets in a connection to resist an oblique load.

• **What current specs allow**—Until recently, design specifications have frowned on the use of rivets to carry tensile forces. The American Association of State Highway Officials' specification for design of highway bridges, for example, states that "rivets in direct tension shall, in general, not be used, but if so used, their value shall be one half that permitted for rivets in shear."

The American Railway Engineering Association specification for design of railroad bridges does not mention rivets in tension.

In the 1946 revision of the American Institute of Steel Construction specification, the allowable tensile stress on rivets was increased from the value permitted for shear to one and one-third times that value, after tests indicated higher tensile stresses were justified. However, for a rivet subjected to a combination of shear and tension, the resulting stress was limited to the shear value because of a lack of definite information as to the true interaction relationship.

In 1950, the Research Council on Riveted and Bolted Structural Joints initiated a program of tests in which the strength of rivets subjected to combined tension and shear was studied. Also included in the program was a study of the manner in which the strength of the rivets was affected, under several shear-tension ratios, by such variables as the rivet grip, rivet diameter, method of driving and the way in which the rivets were manufactured. The principal variable, however, was the tension-shear ratio, or the ratio of the tensile component of force acting along the rivet axis to the shearing component of force acting normal to the rivet axis.

• **Ingenious test setup**—The tests were conducted in the Structural Research Laboratory of the Department of Civil Engineering at the University of Illinois by H. L. Cox. He used a clever, but simple device to apply various ratios of tension and shear with a tension testing machine. (This type of loading device had been used at Penn College by R. H. Pancoast in connection with a research thesis on bolts.)

Each test rivet connected two identical cylindrical pieces of steel, which provided a shoulder for receiving and transmitting a pull to the rivet head. The specimen was inserted between two large, semi-circular steel disks that had been formed by making a zigzag cut through the center of a single disk (Fig. 1 and 2). These disks had holes around the circumference for connecting to the moving heads of the testing machine.

When the specimen was placed in the machine in a vertical position (A and B aligned vertically in Fig. 2), it was subjected to pure tension. When it was horizontal (C and D aligned vertically) it carried only shear. And when it was in an intermediate position, it took both shear and tension, in a fixed ratio.

Rivets were driven in accordance with typical shop practice for hand-pneumatic and machine-driven rivets.

• **Effect of rivet size**—The results of the tests may be summarized briefly as follows:

1. An increase in grip from 1 to 5 in. produced a reduction in ultimate strength of approximately 8%.

2. Rivet diameter, varying from ¾ to 1 in., had little, if any, effect on the stress at failure in the rivets (computed from area of rivet as driven).

3. When loaded only in shear, the machine-driven rivets (from one fabricator only) appeared to be slightly weaker than the hand-pneumatic driven rivet. When loaded in tension, the rivets showed negligible difference in strength.

4. The effect of method of rivet manufacture (hot or cold-formed) upon the ultimate strength was insignificant.

5. Character of fracture and ductility of the rivets changed materially as the loading varied from shear through combined shear and tension to tension.

• **Failure stresses compared**—Data from tests of 230 rivets were plotted to indicate the relationship between the strength of a rivet and the direction of loading (Fig. 4). Ordinates and abscissas of this plot are, respectively, the tensile and shearing components of the oblique failure load divided by the failure load in pure shear.

Table I shows average ultimate strengths obtained for four tension-shear ratios. Most of the rivets were tested at these four ratios.

• **Tests yield stress equations**—It is interesting to note that the average ultimate strength of 52 rivets loaded in pure tension, as reported in Table I, was 1.325 times the ultimate strength of 51 rivets loaded in shear alone. This ratio is almost identical with that of allowable tension to shear stress recommended for rivets in the 1946 revision of the AISC specification (20/15 = 1.333). The maximum deviation from this 1.33 strength ratio, for all test rivets having identical characteristics, was less than 7%.

TABLE I—SUMMARY OF ULTIMATE RIVET STRENGTHS

Tension-Shear Ratio	Ultimate Strength Based on Nominal Area, psi	Ultimate Strength Based on Hole Size,* psi
0 : 1.0	51,580	44,890
0.577 : 1.0	52,330	45,540
1.0 : 0.577	62,020	53,920
1.0 : 0	68,370	59,470

* Rivet hole was 1/16 in. larger than nominal diameter of rivet.

In Fig. 4, the test data is compared graphically with the plot of:

$$\frac{a^2}{1.00^2} + \frac{b^2}{1.33^2} = 1.0 \qquad (1)$$

where a is the ratio of the shear component of force on the rivet at ultimate strength to the ultimate shear strength of the rivet, and b is the ratio of the tensile component of force on the rivet at ultimate strength to the ultimate shear strength of the rivet.

Here again, the maximum deviation for any of the test series was under 7%, indicating that a safety factor might reasonably be applied to this elliptical expression to obtain allowable tension and shear stress for a rivet subject to combined loading.

If a tensile stress equal to 1¼ times the allowable shear stress is permitted in the design specification, intermediate working values for various combinations of tension and shear loading can be derived from:

$$x^2 + \left(\frac{3y}{4}\right)^2 = v^2 \qquad (2)$$

where x is the allowable combined shear stress; y, the allowable combined tension stress and v, the allowable stress for shear alone.

With either x or y given, you can compute the corresponding working value for the other concurrent stress, or you can read it directly from a chart (Fig. 5), where the prescribed value of v has been taken as 15,000 psi. In everyday practice, you generally can obtain sufficiently accurate values by interpolation from Table II.

If you wish to determine the required number of rivets when the load to be resisted by a riveted connection is represented as an oblique force, P, applied at an angle ϕ, to the contact (shear) plane of the connected parts, three methods of solution are possible:

1. The shear component of P can be divided by a rivet shear value x appropriate to the angle ϕ.

2. The tension component of P can be divided by a rivet tension value y



FIG. 4. ELLIPTICAL CURVE closely approximates the average shear-tension relationships at failure for rivets. Dots indicate 1 to 9 tests.



FIG. 5. ALLOWABLE UNIT STRESSES for rivets can be obtained from above curve derived from Fig. 4, or from . . .



FIG. 6. LINES ABCD, which give nearly as accurately, the combined stresses rivets may be allowed.

appropriate to the angle ø.

3. Or the load P can be divided by a combined (oblique) rivet stress z appropriate to angle ϕ.

The shear component and tension component of the applied load may be calculated as $P \cos \phi$ and $P \sin \phi$, respectively. The tension-shear ratio produced by the given oblique load is given by tan ϕ. Appropriate values for x and y may be obtained from Fig. 5. They are given by the coordinates at the intercept of the ellipse and a line drawn between the origin and the proper point on the shear-tension or tension-shear scale.

The corresponding combined stress z is represented by the segment of this straight line included between the origin and the intercept, measured to the scale of the graph. Algebraically, it can be expressed as

$$z = \sqrt{x^2 + y^2}$$

If we let m = tan ϕ = tension-shear ratio = y/x and n = cot ϕ = shear-tension ratio = x/y, then, from Eq. 2:

$$x^2 = \frac{v^2}{1 + \left(\frac{3m}{4}\right)^2} = \frac{(vn)^2}{\left(\frac{3}{4}\right)^2 + n^2}$$

$$y^2 = \frac{(vm)^2}{1 + \left(\frac{3m}{4}\right)^2} = \frac{v^2}{\left(\frac{3}{4}\right)^2 + n^2}$$

from which the value of z can be expressed, in terms of v and m or n, as

$$z = v\sqrt{\frac{1 + m^2}{1 + \left(\frac{3m}{4}\right)^2}} \qquad (3)$$

$$z = v\sqrt{\frac{1 + n^2}{\left(\frac{3}{4}\right)^2 + n^2}} \qquad (4)$$

Values for z are given in the right-hand column in Table II.

• **Alternative stress formula**—In Fig. 6, a different interaction relationship (lines ABCD) is compared with the ellipse. As indicated by lines ABCD, no reduction in tension stress would be required if the concurrent shear stress did not exceed 6.0 kips per sq in. Also, no reduction in shear stress would be required if the concurrent tension stress did not exceed 5.0 ksi. For combined stresses between these limits, the working stress in shear, x in ksi, could be calculated in terms of the concurrent working stress in tension, y, from the equation:

$$x = 18 - 0.6y \qquad (5)$$

If this interaction rule is compared with that expressed by the ellipse in Fig. 5, it will be found that when the tension component is one-third the shear component, the rule permits a combined stress 2.9% higher than that permitted by Eq 2. When the tension component is 3¼ times the shear component, the rule permits a combined stress 7.7% higher.

In the interest of simplification of routine design practice, such differences would not appear to be altogether unwarranted. As a matter of fact, percentagewise the maximum deviation of individual test results here is no greater than in the case of the ellipse. However, it is not the purpose of this report to make specific recommendations, but rather to suggest the type of revisions in present design specifications that would seem to be justified on the basis of the test data now at hand.

TABLE II—WORKING SHEAR-TENSION STRESSES FOR RIVETS*

Angle ϕ deg	Tension-Shear Ratio	Shear-Tension Ratio	Allowable Shear Stress—ksi	Allowable Tension Stress—ksi	Allowable Oblique Stress—ksi
0	0	∞	15.00	0	15.00
27	0.51	1.95	14.00	7.18	15.72
38	0.77	1.30	13.00	9.98	16.40
45	1.00	1.00	12.00	12.00	16.96
49	1.14	0.88	11.40	13.00	17.30
53	1.31	0.77	10.71	14.00	17.63
56	1.50	0.66	9.92	15.00	17.96
61	1.79	0.56	9.00	16.00	18.37
65	2.15	0.46	7.90	17.00	18.75
70	2.75	0.36	6.54	18.00	19.16
76	4.06	0.25	4.68	19.00	19.58
90	∞	0	0	20.00	20.00

*Based on an allowable stress for shear alone of 15 ksi.

Rodgers Hydraulic JACKING EQUIPMENT...

- JACKING CYLINDERS (50 TO 600 TONS)
- HAND AND POWER PUMPS
- QUICK COUPLERS
- VALVES AND HOSE



Photo shows two Rodgers 300-Ton double-acting jacking cylinders (operated by Rodgers power-driven hydraulic pumps) jacking 72" compressed concrete pipe. Hose connects cylinders with pump.

SAVES YOU TIME AND MONEY ON JOBS LIKE THESE...

SEND FOR NEW CATALOG

To learn advantages of Rodgers Jacking Cylinders on construction jobs . . . get the new Rodgers Catalog No. 317. It gives full information.

Wherever you need versatile, efficient jacking power on the job — you'll want a Rodgers jack. A complete selection of hydraulic cylinders in various capacities and lengths of ram travel are available — to be used with either hand-operated or power-driven hydraulic pumps.

Cylinders may be operated either singly or as a group for a straight jacking of compressed concrete pipe, corrugated pipe, well casing, etc., or used in the operation of the shield jacking method. Two sizes of quick couplers, 4-way and metering valves, and high pressure hose are available accessories.

Complete specifications, illustrations and suggested uses are included in the new Rodgers Jacking Equipment Catalog.

- JACKING COMPRESSED CONCRETE PIPE
- JACKING CORRUGATED PIPE
- JACKING WELL CASING
- JACKING SHIELD FOR TUNNELING

HYDRAULICS Rodgers THE WORLD MOVES

Rodgers Hydraulic, Inc.

7441 WALKER ST., ST. LOUIS PARK, MINNEAPOLIS 16, MINN.

HYDRAULIC POWER EQUIPMENT



PLOTTED WATER SURFACES, electrically measured, indicated economical feasibility of tailwater-channel improvement for a USBR hydro plant.

Analog circuit solves open channel problem

KARL O. VARTIA
Chief, Engineering Division
USBR Area Planning Office, Austin, Tex.

WHAT WILL HAPPEN in a sluggishly flowing, almost empty channel when a flow of several thousand cubic feet per second of water is turned into it for a few hours, then turned off again? What happens when the cycle is repeated day after day? And if these aren't enough variables to consider in design, suppose both the width and depth of channel continually decrease for several miles downstream.

This was the problem faced by the Area Planning Office of the U.S. Bureau of Reclamation in Austin, Tex., on one of its proposed projects. The solution was by electric analogs, a device that has been so helpful in complex distribution network problems (ENR Aug. 30, 1951, p. 35).

• **The problem**—A proposed storage dam many miles upstream from the point where irrigation waters were to be diverted seemed a likely place for a small hydroelectric power plant. It was desired to study the economics. Average flow at the damsite would be only on the order of 800 cfs, so a peaking type of plant was the only thing considered economically feasible. A low dam, and narrow channel width below, meant a high tailwater level in periods of increased flow. This dictated a small power plant with a maximum flow of about 1,500 cfs, the only possibility.

This plant was then found to have, at best, only marginal economic feasibility.

A full study of the area power requirements showed that peaking capacity with enough water to operate at a load factor as low as 16% could be integrated into the power system as dependable capacity. Consideration was given, therefore, to enlarging the narrow channel and thus lowering the tailwater level for larger plant capacities.

The obvious questions then arose: How much excavation was justified, and, to determine this, how should the channel be designed? In computing resulting backwater curves for tailwater elevation, what flows were to be expected at various points downstream as a result of power plant releases that could be as non-uniform as four hours at full flow followed by 20 hours at no flow?

• **Comparative studies**—It was reasoned that distributed channel storage between the dam and some point downstream could "iron out" intermittent flows substantially into average flow.

Flow was considered to decrease uniformly downstream from the maximum rate at the plant to the average (ironed-out) flow at the point downstream.

To figure the maximum water surface, these asumptions were made: velocity, 2.5 fps; n=0.030; side slopes, 2:1; bottom width, not less than 80 ft nor more than 10 times the depth. Various discharges were assumed for a range of power production.

Then the backwater curve was figured back from a depth required for average flow at the downstream point being considered.

When a point was located that would reconcile storage and flow for the plant capacity in question, the proposed channel cross section was plotted to that point, and the additional excavation that would be required was figured.

Flows up to 7,200 cfs were investigated in this manner, and investigations showed that further study was warranted.

• **Enter the analog**—More exact hydraulic analyses of the slug flow in a narrowing channel appeared an impracticably rigorous exercise. Model study would solve the problem, of course, but it was decided that a quick electric analog check would be an



DISCHARGE CURVES for points downstream indicate ironing-out effect of time and distance on non-uniform flows in the non-uniform channel.

inexpensive means of determining whether costlier model studies were justified.

Analogous quantities in the free-surface hydraulic flow problem are: condenser capacity to channel storage capacity; resistance to friction; inductance to mass of moving water. At the low velocity and shallow depths worked with in this problem, mass is not a necessary consideration. So inductance was omitted from the circuit without any real loss of accuracy.

For computing condenser capacities and resistances, estimates were made of average flow and mean depth at various points along the channel, from which surface area, hydraulic radii and average velocities were determined and converted into analogous electrical values. To avoid large electrical equivalents, a 24-hr cycle in the prototype was reduced to 1/20 second of analog time by an oscillator-controlled relay switch.

Linear resistors were used, with the conclusion that they would introduce no significant error. The analog circuit was divided into 20 sections, each representing a mile of channel, with resistance increasing from an initial value of 116 ohms for the first and widest section of excavated channel to 587 ohms for each one-mile section of natural channel downstream from the point of assumed uniform flow. Capacitances, reflecting decreasing width, varied from 1.21 down to 0.635 microfarads. In operation of the electrical device, one volt equaled one foot, and one milliampere was 500 cfs.

Water-surface at the end of mile 20 was the base from which head was measured electrically.

Analog circuit operation was first noted on an oscilloscope that showed voltage variations at different points. When results by this method looked satisfactory, operation of the analog circuit was recorded by an oscillograph on sensitized paper.

Voltage variations at points representing miles 2, 4, 6, 8, 10 and 12 are plotted in the accompanying graph; they indicate the sequence of surface fluctuations along the channel. Bottom elevations and bottom widths of the channel are shown on the graph for reference. Maximum and minimum flows at each section are also listed for reference.

No claim can be made at this time for the quantitative corrections of data obtained from the analog. But close agreement between analytical studies using simplified assumptions and corresponding values from the analog study makes it reasonable to assume a thorough hydraulic study will not materially alter the conclusion that the channel improvement is feasible.

The analog study was made in Denver research laboratories of the Bureau of Reclamation under supervision of R. E. Glover. C. R. Daun supervised electrical work. And the author was in charge of initial channel rectification studies for this project.

Air pollution control unit set up by New York

Dr. Leonard Greenburg, executive director of the Division of Industrial Hygiene and Safety Standards of the New York State Department of Labor has been appointed the first commissioner of New York City's new department of Air Pollution Control.

William S. Maxwell, deputy director of the city's present Bureau of Smoke Control, will serve as deputy commissioner.

The Department of Air Pollution Control and its policy-making arm, the Board of Air Pollution Control, will have jurisdiction over control of all forms of atmospheric pollution including smoke, fly ash and chemical fumes from all sources.

Dr. Greenburg, as commissioner, will be chairman of the policy-making board. Also on the board as ex-officio members will be the Housing and Buildings Commissioner Bernard J. Gillroy and Health Commissioner John F. Mahoney.

Retention of Maxwell in the city's smoke control program came as a surprise to those who had opposed the bills creating the new department on the ground that they were actually measures to get rid of Maxwell, who has been an aggressive fighter against illegal smoke pollution of the city's atmosphere.

• **Dr. Greenburg**—Holding an unusual combination of professional qualifications, Dr. Greenburg is both a physician and a sanitary engineer. He is licensed to practice both professions in New York State.

A graduate of the city's public schools and the Townsend Harris Hall High School, he received his degree in sanitary engineering from Columbia University in 1915, a doctorate in public health from Yale University in 1923 and his medical degree from the Yale School of Medicine in 1930.

Among the many professional organizations in which Dr. Greenburg holds membership are: the American Society of Heating and Ventilating Engineers, the New York Academy of Medicine, the American Public Health Assn. and the American Medical Assn.

Before accepting his present job with New York State, Dr. Greenburg was public health officer in New Haven, Conn. For more than 15 years before that he had worked for the U. S. Public Health Service as an expert on air pollution.

He is co-inventor of the standard impinger apparatus for measuring air pollution, and in 1923-24 was in charge of the installation of the present air purifying systems in the houses of Congress.

4 easy ways to hang forms

UNIVERSAL Products . . "TOPS" IN CONCRETE FORMING

Eliminate Costly Shoring and Falsework



1 **Wire Beam Saddles**—For non-fireproofed construction . . . bridges, overpasses, etc. Saddles are accurately made to insure correct relationship between deck form and beam flange.



2 **TWISTYE Hangers**—For fireproofed construction . . . accurately fabricated to provide a positive spreader . . . guaranteed breakback . . . easy installation, quick removal.

3 **Beam Clamps with Band Iron and Soffit Spacers**—For fireproofed construction . . . Beam Clamp has a double grip on Band Iron which develops the band's full strength. Soffit Spacers act as spreaders. Installed from above . . . no scaffolding necessary.



Send your hanging problems to us!

4 **"U" Bolts**—For fireproofed construction. Recommended where hangers must carry heavy loads.



Plain round rods and Form Clamps.

Threaded tie rods and SPIROLOC Form Ties.

Write for the Universal Catalog 902

UNIVERSAL FORM CLAMP CO.

GENERAL OFFICES AND FACTORY: **1238 N. KOSTNER • CHICAGO 51, ILLINOIS**

OFFICES AND WAREHOUSES:

SAN LEANDRO, CALIF. . . . 2051-9 Williams St.
HOUSTON, TEXAS . . . . . 2314 Preston Ave.
CLEVELAND, OHIO . . . . 24901 Lakeland Blvd.
BALTIMORE, MD. . . . . . 661 S. Monroe St.

DISTRIBUTORS IN PRINCIPAL CITIES

Service Wherever You Build . . . Coast to Coast

Copyright 1952 by Universal Form Clamp Co., Chicago 51, Ill.



Consultants propose expressway plan to relieve Milwaukee's congestion

Plans for the first 20.5 mi of Milwaukee's proposed expressway system were submitted last month by Ammann and Whitney, consulting engineers of Milwaukee, Wis., and New York. The plans must now be acted upon by the mayor, the city council and the Department of Public Works.

The plans and the report represent eight years of study of Milwaukee's traffic needs by city, state and federal agencies and private consultants.

Here is the gist of Ammann & Whitney's report:

Traffic congestion is now costing citizens thousands of dollars in daily operating losses. With traffic increasing at a steady rate, and little remaining of unused vehicular capacity, the situation is becoming critical. If substantial additions to trafficways are not provided within a few years, motorists will experience rapidly increasing delays and accidents. Additional congestion would bring further economic losses to every segment of the local economy, and result in noticeably accelerated depreciation of property values.

The proposed system of expressways was designed for the expeditious movement of vehicles within, into, out of, and through the city. It was predicated on factors of land use, economics, and a comprehensive city traffic pattern as predicted for the year 1980. Today the traffic rate on Milwaukee streets is 600,000 daily. In thirty years an increase of 50%—900,000 trips daily—may be expected.

• **System**—The proposed system consists essentially of four parts: Two east-west routes, and two north-south routes. Totaling nearly 24 mi, the routes form an interior cordon of limited-access roads connecting with the principal highways leading into the city.

The primary expressway is the East-West Route which bounds the downtown area on the south. Another major element is the North-South Route passing just west of the downtown area. A third is the 44th Street Route, extending from the south city limits to the northwest corner of the city. The fourth is the North Avenue Route, providing a northerly connection between the North-South and 44th Street Routes.

Four complete interchanges provide for the flow of traffic between the four routes, permitting through and turning movements to be made directly and continuously without reducing the capacity of the expressway lanes. Simplified as much as possible, all turning movements are started in the direction drivers plan to take.

• **Design**—Divided by a 12-ft center mall, the proposed expressway will have 6-lane roadways—3 in each direction—with the exception of the 44th Street Expressway, which will have only 4 lanes. Each of these 12-ft lanes has been designed to carry the traffic of 3 or 4 normal city street lanes at 50 mph.

In residential and most commercial areas the recommended expressways are depressed and completely landscaped. Viaduct sections are used only in cases of necessity, at river and valley crossings, and in the downtown area where large volumes of traffic could not conceivably be handled in any other way.

Access has been limited to ramps at about half-mile intervals where specially designed lanes enable cars to enter or leave the moving streams of expressway traffic safely. Parking on the expressways will be prohibited. Extra outside lanes will be provided

for disabled cars and for snow removal purposes.

• **Results**—The expressway will benefit the community in many ways. Experience in other urban areas indicates that expressway systems reduce accidents considerably.

Fringe parks in redeveloped areas along the right routes can be used for recreational purposes.

Heavy traffic which has been blighting residential areas will be removed. Large tractor-trailer combinations and other trucks which at present travel residential and arterial streets will be removed.

Expressway routes will be of considerable value to the city's many defense industries.

To promote the development of express bus routes, complete access to surface streets will be provided at most bus transfer points. This will allow buses to leave the expressway, discharge passengers and return to the expressway.

Expressway ramps have been located so as to be of maximum benefit to both the downtown business area and the civic center.

The expressways will remove 60% of the downtown traffic having origin or destination there. Further reduction will be effected by removing from the streets 86% of the through traffic which would traverse the downtown area without destination there.

Property values and business volumes will increase substantially under these conditions.

• **Costs**—The cost of 20.5 mi of this proposed expressway system within the city is estimated at approximately $158 million—$100 million for construction, $58 million for real estate. A finance program could be carried out by utilization of current funds and bond issues within the present bonded debt limit supported by a county-wide vehicle or property tax.

No estimates have been developed for the suggested routes outside the city. They can probably be provided at a fraction of the cost of the inner routes.

The cost of protecting the $3 billion in city property will be completely justified by increase in property values and savings in vehicle operation that will result.

Wisconsin's State Highway Commission last week announced that $6 million will be spent on Milwaukee city and county projects. The largest item of this sum being $1 million for structures and grading for the East-West Expressway.



"Cruising Down the River" in Minnesota as . . .

Four houses are moved by barge

The turbulent Mississippi, whose floods bring nothing but grief, served last month as an avenue of escape for four property owners in Lily Dale, a suburb of St. Paul, Minn.

The four owners, tired of having their houses buffeted about by the recurrent spring floods each year, sent their homes "cruising down the river" for about five miles to new locations on high ground.

Movement of the four homes was a joint project of H. W. Prodger, St. Paul house mover, and the Twin City Barge and Towing Co., headed by Gordon Miller.

House-moving is no new art for Prodger, but shipment of the four homes by barge isn't exactly an ordinary undertaking, even though he did it once before, about a dozen years ago.

• **How it was done**—Prodger's crew of four men spent about three weeks lifting the four houses off their foundations. Then they built a ramp 26 ft wide and 80 ft long.

Prodger used pneumatic tires on dollies, 112 wheels under each building to move the first two houses onto the barge—each shipment made up of two homes. However, he discovered pneumatic tires don't operate as well on timber as do steel dollies, which he used for the second pair of buildings.

Once the two houses were secured to the barge—the owners and their families remained in them—the barge line brought in its 250-hp towboat, Tom Thumb, to take the load down river to the outskirts of St. Paul.

Building another ramp, Prodger removed the first two houses and returned for the remaining pair.

• **Costs**—Prodger said his charge for moving was about $1,000 for each house, plus about $200 for barge charges.

The four owners each flood year had suffered $500 to $1,500 damages per house.

Next spring, even if the Mississippi should flood its banks, the four families expect to be left high and dry in their new location.

The frame houses moved were: a seven-room, a six-room and two four-room homes. Their weight was estimated at 30 to 35 tons each, according to Prodger.

Prodger now has several others in Lily Dale who are considering making similar "cruises down the river" with their homes.

Public works department reorganized in Chicago

Reorganization of the public works department in Chicago has been approved by the city council, by adoption of 12 ordinances to legalize the new setup. Streamlining of the operations is expected to place them on a more businesslike basis and to save the city money.

The new alignment, which goes into effect Jan. 1, 1953—

Combines the Department of Subways and Superhighways with the Department of Public Works, with Virgil E. Gunlock, former commissioner of subways and superhighways, heading it as Commissioner of Public Works;

Creates a new Department of Water and Sewers, headed by James W. Jardine, who now is public vehicle commissioner;

Establishes a new bureau of engineering in the Department of Public Works to design and construct all major projects; Gunlock told the city council that engineers were hard to get and that this setup would give the city the best use of the engineers that it has;

Changes the name of the Department of Street and Electricity to the Department of Streets and Sanitation, with Lloyd M. Johnson remaining as its head;

Establishes a new Bureau of Parking in the Department of Streets and Sanitation which will maintain and supervise municipally-owned parking facilities.

Noxious odor fills valley, is traced to pipeline test

An obnoxious odor that filled the Mahopac Valley near Peekskill, N. Y., on election eve has been traced to an odorant, which was used in the testing of a gas line, police officials reported last week.

Williams Testing Co., Shreveport, La., was hydrostatically testing a line installed by Algonquin Gas Transmission Co. The line is the latest of three natural gas pipelines running into New England.

Eight days of search for a break that had been causing pressure losses on a four-mile stretch between Somers, N. Y. and Lincolndale, N. Y., had ended in failure.

The Williams Co. then decided to test the line by using an illuminating gas odorant, which found the break and settled into the valley. The odor was so strong residents notified state police.

Police asked the N. Y. C. Department of Water Supply, Gas & Electricity to test it in its laboratories. Police said chemists found that a very small amount of this gas could pollute a large volume of water and that the odor was almost inseparable from the water it polluted. No one ventured an opinion, however, as to how much of the odorant would constitute a real water supply danger.

• **New York City enters case**—The state police had notified John H. Kelley, district engineer of DWSG&E, because the area of pollution is in the heart of the city's watershed area.

Commissioner Dominick F. Papuano of New York City's Water Department wrote to Algonquin instructing that company the department must be warned of any future tests. He pointed out also that the odorant used is said to be highly volatile and inflammable.



Timber Towers Constructed by Sofarell at N. Y. International Airport

—Personalized Carpentry Service—

Our varied and broad experience of over four generations gives us an unusual background which is outstanding. Our knowledge and know-how creates harmony and a tempo which stimulates progress. Our ability to organize and schedule projects for fast production has proven most satisfactory to Owners, Contractors, Engineers, U.S.A.



Raising 64' Two Story Wall Section—Ferry-Grider—Buffalo, N. Y.

Corp Engrs., Bureau of Yards and Docks, Federal Works Agency and Municipal Authorities. We maintain one of the largest forces of carpenters. Work is detailed and supervised by our personnel. Consultants to Architects and Engineers on the Design, Practice and Theory of Wood Frame Construction.

SOFARELL BROS.

BUILDING COMPANY, INC.

161-19 JAMAICA AVE., JAMAICA, N. Y.

CARPENTRY SINCE 1905

"John, this building of mine holds a cost-cutting *Tip-Off* from ONE BUSINESSMAN TO ANOTHER"

"What is it?" asked John, a prominent appliance manufacturer.

The contractor answered, *"Simply this: don't take your fasteners for granted!*

"An RB&W man showed me how a switch in fasteners could help me make field connections much more economically.

"He suggested switching from rivets to high strength bolts. They cost more than rivets initially, but the assembled cost is much lower. My men work faster than with rivets. The building goes up faster."

You, too, can find a cost-cutting lesson from this story, whether you're in construction* or any other industry.

MORAL: Look to your fasteners for an often overlooked opportunity to reduce costs, and strengthen your competitive position. New inventions, like RB&W's SPIN-LOCK Screw, may prove more efficient than the fasteners you're now using. Or you may save by the stepped-up production you get from using the finest fasteners . . . RB&W bolts, screws, nuts and rivets of uniform accuracy, dependability and physical properties.

Let RB&W help you make the most efficient use of fasteners on your assembly line. Address RB&W at Port Chester.

RB&W—The Complete Quality line. Plants: Port Chester, N. Y., Coraopolis, Pa., Rock Falls, Ill., Los Angeles, Calif. Additional sales offices: Philadelphia, Pittsburgh, Detroit, Chicago, Dallas, Oakland. Sales agents: Portland, Seattle. Distributors from coast to coast.

RUSSELL, BURDSALL & WARD BOLT AND NUT COMPANY

*If you're interested in construction, write RB&W at Port Chester for a free reprint of the recent article, "No More Riveting."

RB&W 107 YEARS MAKING STRONG THE THINGS THAT MAKE AMERICA STRONG

Dallas takes more steps to alleviate water lack

The Dallas, Tex., city council last week let contracts for three deep wells to be sunk to the Trinity Sands in an effort to alleviate the city's critical water shortage (ENR Nov 13, p. 54).

The wells are expected to produce 9 mgd—about an eighth of the city's normal consumption.

Dallas went into action to boost its water sources after a recent Army Engineer report showed that only four month's supply remained in Lake Dallas, the city's sole basin on the Elm Fork of the Trinity River.

Well drilling contracts went to Texas Water Wells, Inc., at $100,800; the Layne Texas Co. at $106,400; and J. L. Myers & Sons at $102,000. Two of the contracts call for completion in 100 days, and the third in 110 days. All will be drilled near the Trinity River course.

• **Cloud seeding**—The council also approved a contract with Irving P. Krick (ENR Jan. 20, 1949, p. 57) of Denver, whose Water Resources Development Corp. will try to increase rains in the Trinity watershed by cloud seeding. The city will pay the cloud-seeding company $5,500 a month for six months, plus $3,500 the first month to cover equipment and supplies.

Meanwhile plans go ahead to dam up the junction of the Elm Fork and West Fork branches of the Trinity in order to back up West Fork flow to the city's Bachman treating plant on Elm Fork.

Problems of purifying the West Fork flow, which includes sewage from Fort Worth and Grand Prairie, are being studied. The council has yet to give approval to the projects. Cooperation evidently is necessary to pond off stockyard wastes in Fort Worth during dry spells. Large quantities of ammonia have been found in the West Fork water coming from Fort Worth.

In another water shortage prevention move, the city under the direction of Water Superintendent Karl Hoefle will start tapping White Rock Lake in about a week. This will add 8 mgd to the city's dwindling water supply.

Test showed the water is relatively pure as it comes from the lake, but chlorine will be added.

From previous efforts, the city is getting 5.4 mgd from 13 wells and 4.7 mgd from Bachman Lake and Willow Lake near Carrollton to add to the water supply.

MAXI-MOUNTED

WITH THESE MAXIMUM ADVANTAGES

one-man control
operation stability through 360°
close quarter maneuverability
fast travel—either direction



Adaptable for all makes of cranes from 5 to 50-ton capacity.

Write for additional information.

MAXI® CRANE CARRIERS



MANUFACTURED BY SIX WHEELS, INC. • LOS ANGELES 54, CALIF.

NEW FRONT MOUNT INDUSTRIAL 2-WAY RADIO

Speaker and antenna can be mounted in any position to meet your requirements.

WITH the cost of materials today changing radically in a few months time, you've got to make maximum use of equipment or lose out on your construction bid. This means loading the job with trucks, dozers, shovels and making that equipment work for you every minute. Control with G-E two-way radio gives you instant supervision—works your vehicles efficiently.

1. Improve supervision—your foreman can be anywhere on the job site—direct earth moving operations miles away via General Electric 2-way radio.

2. Cut "deadheading." Vehicles need not run empty when in-motion orders can be transmitted by radio. Ten trucks with radio often do work of 30 without it.

3. Control "down time." Trucks out of service can report breakdowns in seconds, be back on the job quickly.

4. Reduce "lead time." Foremen need only a few minutes to anticipate requirements when vehicles are "on call" instantly through a radio dispatcher. Idle trucks waste your money.

The CAS* man at the G-E office near you has studies on typical construction job savings made possible by G-E radio. These facts are eye-openers. Why not call him today?

*Communications Advisory Service

GENERAL ELECTRIC

Joint venture bids low on $4-million sewage job

The city of Sacramento, Calif., received a low bid of $4 million for the construction of a 54mgd primary sewage treatment plant. Bids were opened Oct. 30.

There were 12 bids on various phases of the job. Stolte, Inc., of Oakland and Fred J. Early Construction Co., of San Francisco, a joint venture, offered a low bid of $3.6 million for the erection of the main plant and the Stockton Construction Co. of Stockton, Calif., submitted a bid of $712,000 for the installation of connecting lines. The city had reserved the right to accept bids on the best combination. City Engineer E. A. Fairbairn's estimate for the work was $50,000 greater than the combined low bid.

The sewage plant is designed to take care of the Sacramento metropolitan area needs for the next 20 years. It is scheduled to be ready to go into operation in Aug. 1954.

Included in the plant will be a headwork structure, five sedimentation units, a sludge-pump building, five digestion tanks, digestion central building, elutriation tanks, filter building, office and laboratory, garage and machine shop, effluent pumping structure and chlorination unit.

In addition to the city of Sacramento, five other public agencies will use the facilities. At present raw sewage is being dumped into the Sacramento River and the State Health Department has warned the city that it must stop.

Voters of Sacramento approved a $4.4-million bond issue for construction of the plant.

Contract plans and specifications were drawn by Clyde C. Kennedy, San Francisco, engineer.

Shopping center

A giant shopping center, estimated to cost between $25-$35 million, will be built on the outskirts of Wilmington, Del.

The project will be known as the "Five States Wonder Mile." It includes: Sixty-eight stores along a 4,900-ft strip; at least four department stores among these units with floor space ranging from 36,000 to 150,000 sq ft; a 136-room hotel; parking space for 6,500 automobiles.

The shopping center it is expected will draw trade from five states near Wilmington.

All lifts are easier with a

CRANEMOBILE

for instance . . .
LONG BOOM for reach—
SHORT BOOM for heavy loads—



Whether your next contract calls for handling heavy lifts or long reach, the sturdy stability and the flexible performance of the CraneMobile makes all lifts easier. The CraneMobile is available in a number of sizes . . . crane capacities up to 25 tons . . . a selection of BAY CITY built carriers to meet job requirements. Here is a rubber-tire-mounted crane that will speed to scattered jobs. A crane packed with refinements and operating advantages to give you bigger value.

Let's consider just a few of the advantages . . .

- A collapsible high-gantry which permits lifting maximum recommended boom lengths from horizontal without outside assistance.
- An accurate, fast, independent boom hoist which raises or lowers boom or boom and load by power only.
- A power load lowering device that may be quickly engaged or disengaged to handle lowering of heavy loads smoothly and with precision.

But that's only part of the story. Why not get complete information from your nearest BAY CITY dealer.

BAY CITY SHOVELS, INC., Bay City, Michigan

WRITE FOR THIS BOOKLET

Get this handy pocket-sized booklet of facts and features showing why "all lifts are easier with a CraneMobile". It's loaded with information, it's neatly illustrated and it's yours for the asking . . . Write us.

213

BAY CITY

SHOVELS • CRANES • HOES • DRAGLINES • CLAMSHELLS

53





THEY'LL CONTROL PARAIBA AND PIRAI WATERS FOR ONE OF THE WORLD'S LARGEST UNDERGROUND POWER STATIONS

BALDWIN

Schematic profile of the hydro-electric developments on the Paraiba, Pirai and Lages Rivers showing Forcacava Valve Chamber and Fontes and Forcacava Power Stations.



FIVE 17-FOOT BALDWIN VALVES

to control river diversions for Rio

Soon a big, new project on the Serra do Mar plateau behind Rio will make the waters of both the Paraiba and Pirai rivers available to that power-hungry city. Once completed, it will raise the production of Rio de Janeiro Tramway Power and Light to over 4-billion kwhr a year.

Key control point will be the Forcacava Valve Chamber. From here the waters will be directed to Fontes or Forcacava No. 1 or No. 2 power stations.

Five 17-foot butterfly valves designed and manufactured by Baldwin-Lima-Hamilton Corporation are now being installed at the Forcacava Valve Chamber. Each is designed for a normal operating head of 212-feet—a maximum surge head of 280-feet. To provide the 1,700,000-ft. lbs. of torque for opening and closing these valves, operating pressures of 1500 to 2500 psi will actuate two servo-motor cylinders on each valve.

Whenever you are in the market for hydro-electric valves or turbines, our engineers will be glad to put their experience at your service. Because they can offer all basic types of turbines, they will give you unbiased opinions on the designs best suited to your flow or head conditions.

This type of equipment is also manufactured by our subsidiary the Pelton Water Wheel Company, 2929 Nineteenth Street, San Francisco 10, California.

-LIMA-HAMILTON

BALDWIN BLH LIMA-HAMILTON

General Offices: Philadelphia 42, Pa. • Offices in Principal Cities

Specify

TAPECOAT

The Original Coal Tar Tape Protection for Pipe, Pipe Joints, Couplings and Tanks



TAPECOAT provides time-tested protection against severe corrosion on gas, oil, water and air piping and on pipe joints, couplings and tanks. It is resistant to moisture, acids and alkalis underground, and is equally dependable against moisture, chemical fumes and other severe conditions above ground. It reduces maintenance, cuts pipe replacement cost—as proved in 11 years of service to industry.

TAPECOAT is easily, quickly applied with use of a torch to bleed the coating, for a perfect bond. It is wrapped spirally or "cigarette-wrapped."

TAPECOAT is sized to the job. It comes in widths of 2", 3", 4", 6", 18" and 24".

Write for details and prices.

*Reg. U. S. Pat. Off.

The TAPECOAT Company

Originators of Coal Tar Tape Protection

1551 Lyons Street
Evanston, Illinois

European sanitary engineers call for greater cooperation among specialists

The need for greater cooperation between engineers and other specialists who make up the team of public health workers, was one of the factors stressed at the Third Seminar for European Sanitary Engineers, held from Oct. 27 to Nov. 1 at the Institution of Civil Engineers, London.

More than 70 participants from 18 European countries, comprising sanitary engineers, chemists, health officers, bacteriologists, soil scientists, biologists and others, heard Dr. J. A. Scott, Chief Medical Officer of Health, London County Council, define the nature of this cooperation in the field of sanitation. It was the medical officer's task, he said, to establish the minimum standards of hygiene which would ensure the health of the community through the harmless disposal of infective and dangerous organisms, while the other specialists should find the methods to achieve this and to provide practical solutions to each problem as it arises, within the financial means of the community.

The general theme for the seminar was small sewage treatment works. One of the problems referred to by Harold Macmillan, British Minister of Housing and Local Government, in his opening address to the seminar, was the need to provide so far as possible the same standards of sanitation for rural communities as exist for advanced urban areas. A solution of this problem, he said, would help to stop the drift from the land which constitutes a serious social problem in the United Kingdom. Sanitary engineers have taken up this challenge and developed minor sewage treatment works for small groups of houses. Research continues to perfect the design of such works.

M.F.B. Sentenac, director-general of the technical services of the Prefecture of the Seine, Paris, raised the problem of large scattered populations such as are to be found in rural France. The seminar reached the conclusion that "group sanitation" was always to be preferred to individual plants for each house, because the former method was more economical and more efficient, particularly from the point of view of operation and maintenance. It was felt that small works providing tank and possibly filter treatment represented a justifiable compromise between the individual tanks serving one property and a main sewage system which, for small or scattered communities, was often prohibitive in cost.

The delegates visited the new sewage treatment works at Maple Lodge, Colne Valley (ENR, Oct. 2, p. 52). In operation for less than a year, this is one of the most modern sewage disposal works in Europe.

Earlier seminars for European sanitary engineers, held at The Hague and in Rome, have roused widespread interest in other parts of the world.

• **Baity attends**—Prof. H. G. Baity, director, Division of Environmental Sanitation, World Health Organization (on leave from the University of North Carolina), attended the greater part of the seminar before leaving for Buenos Aires, and the Inter-American Association of Sanitary Engineering conference. Still another meeting of sanitary engineers and allied experts from the Eastern Mediterranean Region of WHO is planned for Pakistan early in 1954.

The seminar which was sponsored jointly by the World Health Organization, The Rockefeller Foundation, and the British government, was presided over by G. M. McNaughton, chief engineer, Ministry of Housing and Local Government. A ten-member advisory panel was selected to continue the work and absorb the members of the previous 6-member Ad Hoc Committee which had carried on the coordination between seminars.

At the closing session it was decided to hold the fourth Seminar for European Sanitary Engineers in the spring of 1954.

All-water route planned Atlantic to Black Sea

A $250-million project that is expected to provide an all-water route from the North Atlantic to the Black Sea is now under study by the International Bank for Reconstruction and Development. Pushed by a group of Austrian industrialists, the plan would involve construction of a canal linking the Danube and Main rivers. The bank has been asked to lend 45% of the capital necessary to complete the project.

("International continued on p. 56)

man-sized LOADS ARE child's play FOR MACK SIX-WHEELERS

Man-sized loads over bruising terrain are child's play for Mack six-wheel trucks because they have the unique advantage of Mack's Balanced Bogie with exclusive Power Divider.

You save time and money with the Mack Power Divider because it distributes power to the wheels having traction under the toughest conditions—hub-deep mud, slippery sand or rock-strewn ground. Acting as a true differential, the Power Divider delivers torque between the two bogie axles and between the four driving wheels in proportion to wheel traction—thus eliminating useless wheel slippage and spinning.

Why not find out what Mack six-wheel trucks can do to save money and boost profits on your job through bigger payloads and faster, uninterrupted schedules. Your nearest Mack branch or distributor will be glad to make a factual study of your particular operation. Call them in and get the full story.

Mack TRUCKS

. . . outlast them all

Mack Trucks, Empire State Bldg., N. Y. 1, N. Y. Factory branches and distributors in all principal cities for service and parts. In Canada: Mack Trucks of Canada, Ltd.

WOOD TIMBERS

...offer strength plus endurance when they're penta*

PROTECTED

In the history of bridge building and other heavy construction, wood has long been the choice of materials because of its strength and toughness, its workability and economy. Today you specify PENTA treated wood timbers with the assurance that this modern wood preservative will protect the good structural qualities of these timbers for longer and more durable service without sacrificing workability.

Pressure treating with PENTA provides wood with clean protection against termites and decay . . . protects permanently, too, since PENTA will not leach or evaporate. Over 40 commercial treating plants located all over the country supply PENTA pressure treated wood to your specifications.

THE DOW CHEMICAL COMPANY
MIDLAND, MICHIGAN

The Dow Chemical Company
Dept. PE 42A • Midland, Michigan
Please send me: ☐ Plant wood treating specifications
☐ Valuable booklet, "Pointers on Penta" ☐ Sources of posts and treated wood

Name_____ Title_____

Company_____

Address_____

City_____ State_____

DOW *penta CHLOROPHENOL

Permanent staff planned for Pan-American roads

Plans for a permanent secretariat for the Pan-American Highway Congress were approved at a special meeting of the congress held in Mexico City Oct. 24-Nov. 2. Also approved was a program for financing the work of completing the Pan-American Highway and improving sections of the highway.

Lack of continuity in the work of the congress between its big meetings has been one of its major weaknesses. Resolutions were adopted, although there was no agency to press for action, on those resolutions by the countries most directly concerned. Nor was there any continuing study of subjects that should be brought forward for action by the congress.

At the Mexico City meeting a temporary executive committee was appointed to serve as the central organization until the next meeting of the Pan-American Congress which is set for Caracas, Venezuela, in 1954. On this committee are representatives from Argentina, Brazil, Mexico, Peru and the United States.

Secretarial services are to be provided by the Organization of American States.

Within the proposed permanent set-up are continuing committees on organization, highway recommendations, finance and coordination.

• **Highway financing plan**—Under the financing plan approved by the congress, governments of the countries in which the work is to be done would issue bonds to cover the cost, which would be supported by specified taxes or other income. These bonds then would be delivered to the International Bank for Reconstruction and Development as security for its own bonds in like amount to cover a loan to the country doing the work.

It is believed that these bonds can be sold in world markets much more easily than could the bonds of the individual countries. This plan, it is understood, has not yet been approved by the International Bank for Reconstruction and Development.

• **Honored by ARBA**—At the closing session of the congress the American Road Builders Association presented a plaque to Romulo O'Farrill, president of the Associacion Mexicana de Caminos and a director of the International Road Federation, in recognition of his leadership in highway development in Latin American countries. Eugene Reybold, vice president of the association, made the award.

Pioneer packs in power with WAUKESHA



for U.S. ARMY rock plants



Gasoline

WAUKESHA Super-Duty Six Gasoline Unit (6-WAKU)— 6-cyl., 6¼-in. bore x 6½-in. stroke, 1197 cu. in. displacement powers the plant shown. Get Bulletin 1555.

WAUKESHA

Diesel



WAUKESHA Super-Duty Six DIESEL Unit (6-WAKDU)— 6-cyl., 6¼-in. bore x 6½-in. stroke, 1197 cu. in. displacement. Get Bulletin 1418.

The U. S. ARMY uses portable rock crushing, screening, and washing plants to produce aggregate for air bases, roads, and concrete structures. Shown is a 56-A Primary Crushing Unit, typical of these plants, which Pioneer Engineering Works of Minneapolis, Minnesota, build to U. S. Army Engineers' Specifications with a Waukesha Super-Duty Six Power Unit to drive the crusher, feeders and conveyor. Capacity is 300 to 400 tons per hour with crusher set at 6-inch discharge.

Waukesha Super-Duty Sixes... gasoline or Diesel... are the choice of power equipment makers, operators and owners alike —for lively acceleration, shock-free operation, and low upkeep with high fuel economy.

187

WAUKESHA MOTOR COMPANY, WAUKESHA, WIS.
NEW YORK • TULSA • LOS ANGELES

Save time and money on construction jobs

The reference aid that helps you solve your toughest construction problems

With the construction work that lies ahead for every engineer, it is only up to you to assure yourself of superior workmanship—ensure your work of the finest structural qualities—by providing yourself with this revision of the famous Hool and Kinne Library—the books which for years have been providing structural engineers with the facts they need on every problem concerned with the design and construction of civil engineering structures.

HOOL AND KINNE'S

Structural Engineers' Handbook Library

Revised by R. R. ZIPPRODT,

And prepared by a staff of sixty-three well-known engineers, each a specialist in his field.

6 volumes; 3763 pages; 2719 illustrations; 63 contributors

Each one of these six volumes is a complete reference in itself on some aspect of structural engineering. The library

▶**COVERS** the how and why of foundation and substructure design and construction, the general theory of structural members, the detailed design of such members and the design of their connection with other members.

▶**EXPLAINS** the principles of statics, reactions, moments and shears in beams and trusses, influence lines, methods of computing stresses in lateral trusses and portable bracing.

▶**GIVES** details of design and construction of steel, timber and concrete structures of all types.

EXAMINE IT FREE!

We invite you to inspect these books for yourself, because we know that that is the one way you can realize their true value to you, and to the jobs that you do. You want to back up your own knowledge with sure, easy-to-get facts, and you want to make your workmanship worthy of your best time and effort. Therefore, the best investment you can make is to add to your own experience the tested working aids given in this dependable reference library.

Send for all six books, and allow them to go to work for you on your toughest problems.

10-DAY TRIAL EXAMINATION

McGraw-Hill Book Co., Inc., 330 W. 42 St., N.Y. 36

Send me Hool and Kinne's STRUCTURAL ENGINEERS' HANDBOOK LIBRARY, 6 volumes for 10 days' examination on approval. If the books prove satisfactory, I will remit $4.00 in 10 days, and $7.00 monthly until $39.00 is paid. Otherwise I will return books postpaid.

(PRINT)
Name .....
Address .....
City ..... Zone..... State.....
Company .....
Position NR-12-4

This offer applies to U. S. only.

Mexico opens Obregon hydro project

The Mexican Government has started operation of a new $17-million hydroelectric station in the northwestern state of Sonora.

The new plant, under construction for five years, is to be be known as Alvaro Obregon Dam, for a former president of the country. Mexican engineers claim it is one of the largest two dams in Latin America, with a capacity of 3,000 million cubic meters and provisions to install generating equipment for annual production of 96 million KWH.

The installation will ease a critical power shortage in the area, and provide irrigation for some 73,500 square kilometers of Yaqui Valley cotton and vegetable producing land. A main canal 124 kilometers long will feed irrigation works.

The dam is an earthfill structure 1,457 meters long and 97 meters high from the foundation, or 60 meters above water level. It is 10 meters wide at the crown of the curtain wall and 360 meters wide at the base. Construction of the curtain wall alone involved the movement of 8,590,000 cubic meters of earth, which is the largest volume ever placed in a single dam in Mexico and, engineers believe, the largest in Latin America also.

Storage capacity of the dam will be 2.4 million acre-feet of water of which enginers count on 2 million for irrigation and power generation and 400,000 for removal of sediment. The artificial lake, already formed in part, will have a surface area of 76,000 acres.

Included in construction is a concrete spillway, of the free flow type, which will have a discharge of 11,000 cubic meters per second with a flow of 6.70 meters high over the 315-ft length of the spillway.

For power generation, an upper intake located on the right bank consists of three concrete-lined tunnels six meters in dia and some 500 meters in length. It is equipped with butterfly emergency valves and jet cone service valves of 2.54 meters in diameter, which are said to be the largest in the world.

The main distribution canal cost $17 million in addition to the cost of the dam itself, financed by a loan from the U. S. Export-Import Bank. With a capacity of 110 cubic meters per second, the main canal is lined part of the way with concrete to prevent loss of water. A number of siphons and other works were constructed in connection with the canal.

In inaugurating Obregon Dam, the Mexican Minister of Hydraulic Resources noted that 43 major irrigation projects have been completed in Mexico during the last six years. Eighteen other projects are still in construction including Falcon Dam on the Rio Grande and Presidente Miguel Aleman Dam of the Papaloapan project in Vera Cruz state (ENR Oct. 9, '52, p. 34). The latter, when completed next year, will be the largest dam in Latin America. Another major project still under construction is the Miguel Hidalgo Dam, on the Rio Fuerte, for irrigation of 670,000 acres.

During the last six years the following important projects were completed in Mexico:

Morelos Dam, on the Colorado River, irrigating 500,000 acres.

Madero Dam, in Chihuahua state, irrigating 80,000 acres.

Solis Dam, in Guanajuato, for 340,000 acres.

Vallsequillo canals, in Puebla, for 70,000 acres.

Sanalona Dam, in Sinaloa state, irrigating 240,000 acres.

Guasave canal readaptation, in Sinaloa, for 75,000 acres.

Marte Gomez canals added to that dam, for 180,000 acres.

Anzalduas canal system, for 550,000 acres.

Technical research service is offered

A new, complete technical research service is being offered British Columbia industry. It will be provided by British Columbia Research Council through the new Division of Technical Services, headed by D. S. Smith, assistant director of the B. C. Council. The division will combine the technical information service of the National Research Council with that operated at present by the British Columbia Council.

In the new agency, staffs of both councils will be available to provide scientific assistance on technical problems for industry. The service will be free, and where answers cannot be provided from existing knowledge, the team of experts will assist in planning research investigations.

A program of visits to industrial plants will be an important feature of Smith's work. In making these contacts he will work with the field representatives of the British Columbia Provincial Department of Trade and Industry.

You'll find them in the best quarries —

GARDNER-DENVER

Portables

Dependable in any weather —at high altitudes as well as low—because of their two-stage design and their completely water-cooled compressor cylinders.

Wagon Drills

For spotting and drilling holes at a fast pace—thanks to their high maneuverability—their powerful drilling, rotation and blowing, all under finger-tip control.

Sinkers

For sinking block holes or blast holes in any kind of rock—there's a size and weight that's right for fast, efficient drilling in any type of ground.

Send today for bulletins on Gardner-Denver quarry equipment.

Since 1859

GARDNER-DENVER

Gardner-Denver Company, Quincy, Illinois
In Canada: Gardner-Denver Company (Canada), Ltd., Toronto, Ontario

THE QUALITY LEADER IN COMPRESSORS, PUMPS AND ROCK DRILLS

TWO GREAT VIBRATORS
FOR GENERAL CONCRETE CONSTRUCTION!

Model FS-6A. Now furnished with a 6 H.P. engine, providing plenty of reserve power under all conditions, and vastly improved power take-off. Vibrator frequency (up to 7500 VPM) and amplitude are carefully balanced for maximum progress and thorough consolidation. It is available with 3 vibrator heads, for thick or thin sections. Shafting is furnished in 7′ and 14′ lengths up to 28′. Quickly adaptable to concrete rubbing, wet or dry, and drilling. Built to stand severe usage. By any comparison, it's the finest engine-driven vibrator on the market and the best buy! Complete details on request.

The POWERFUL, LIGHTWEIGHT
JACKSON
ELECTRIC VIBRATOR

2¼ H.P. MOTOR. FAST — RELIABLE
Has more than ample power for uninterrupted placing of the stiffest mixes, even when using the maximum length of shaft (28′). Provides 8,000 to 10,000 VPM. Built for trouble-free service.

PLUGS INTO LAMP SOCKET
Wherever 115 volt, 60 cycle, single-phase AC or DC is available.

EXTREMELY HANDY
May be had with any length of shaft up to 28′ and choice of 3 vibrator heads. And since it weighs but 50 lbs. it is ideal for thin or thick sections, high places and reaching those otherwise difficult-to-get-to spots. Also ideal for incasing structural members and similar applications.

QUICKLY ADAPTABLE TO CONCRETE RUBBING
Wet or dry, and drilling. A relatively inexpensive vibrator that will do a whale of a job.

SEE OUR CATALOG IN GILLETT'S HEAVY CONSTRUCTION PRE-FILED CATALOGS

VIBRATORS FOR ALL PURPOSES — FOR SALE OR RENT
at your Jackson Distributor. Mass concrete placement, highway, airport, and municipal paving. Asphalt and Soil Compaction. Power Plants.

ELECTRIC TAMPER & EQUIPMENT CO., Ludington, Mich.

FIELD AND OFFICE



Combine drawings, specs

Much valuable office time can be saved if specifications for a building are made part and parcel of the drawings. This is easily done by typing the specs on tracing paper, having the latter blueprinted, then binding them with the drawings, as illustrated in the accompanying sketch. In one handy package, the two can be referred to in almost the same motion.—R. B. Cutler, Consulting Engineer, Greyledge, Manchester, Mass.

RANGE POLE HOLDER—This rig may be the best answer when he shouts "Plumb your rod!" The 42-in. tripod, mostly of aluminum, has stainless steel shoes. A sliding plumb bar attached to the tripod head pivots around the tripod bolt. The plumb bar is rigidly held in the desired position by the tripod bolt, and is designed to provide radial and laterial movement for plumbing the range-pole over the desired point. Set-up time is one minute. Winds up to 40 mph do not impair accuracy for pointing. (Courtesy of Engineering Research and Development Laboratories, Ft. Belvoir, Va.)





The American Brass Company, Waterbury, Conn., reports

Plant layout speeded

with Kodagraph Autopositive Paper

THE engineering and drawing reproduction departments of The American Brass Company must keep pace with the constant plant-layout demands of ten manufacturing divisions. *And here's how Autopositive Paper saves time and dollars in this work.*

First, paper cutouts of machines and equipment are pasted in position on a whiteprint of the proposed layout. From this opaque pasteup, a positive reproduction on Autopositive Paper is made *directly*. There's no negative step, no darkroom handling with this revolutionary photographic intermediate material. Just exposure in a standard whiteprint machine . . . processing in standard photographic solutions.

Then, the Autopositive intermediate—with dense photographic black lines on a durable, evenly translucent base—is used to produce the desired number of prints. These are sent to the branch involved to be studied and returned with comments.

This procedure may be repeated half a dozen times until complete agreement is reached on the final layout. And *every time* revolutionary Autopositive Paper saves time and dollars!

Other important uses of Kodagraph Autopositive Paper at American Brass

. . . to reproduce the blueprints and direct-process prints which the various divisions receive from vendors. The Autopositive intermediates are then used to produce any number of shop prints.



. . . to reclaim old, soiled, or worn drawings. Autopositive Paper intensifies line details . . . drops out smudges, creases—delivers intermediates which produce clean whiteprints and blueprints.



. . . to speed print service to all departments. Autopositive reproduces production reports, parts lists, documents of every type. And opaque originals can be copied as readily as translucent ones.

Kodagraph Autopositive Paper

"THE BIG NEW PLUS" in engineering drawing reproduction

Learn how Kodagraph Autopositive Paper is simplifying routines in thousands of concerns. Write today for a free copy of "New Short Cuts and Savings" for interesting facts about companies you know . . . and a revolutionary new product *you should know.*

MAIL COUPON FOR FREE BOOKLET

EASTMAN KODAK COMPANY, Industrial Photographic Division, Rochester 4, N. Y.

Gentlemen: Please send me a free copy of your new illustrated booklet, "New Short Cuts and Savings."

Name _____ Position _____

Company _____

Street _____

City _____ Zone ____ State _____

67

Kodak
TRADE-MARK

GET HIGH EARLY STRENGTH CONCRETE with *Standard Cement plus SOLVAY Calcium Chloride*

- √ Lowers Your Costs
- √ Permits Positive Control at All Temperatures
- √ Avoids the Stocking of Special Cement
- √ Assures High Ultimate Strength
- √ Provides Additional Cold Weather Protection
- √ Includes "Built-in" Curing

To speed up operations, increase output and permit use of concrete in shorter time — especially in cold weather — add Solvay Calcium Chloride to your Portland Cement concrete mixes. Works equally well with all Portland Cements, including standard, high early, air entrained and low heat cements.

WRITE TODAY FOR FREE BOOK CONTAINING FULL DETAILS

Filled with valuable information, as well as answers to all your questions about the use of Calcium Chloride in concrete, "The Effects of Calcium Chloride on Portland Cement" is available on request from Solvay. Contractors, engineers, architects — everyone who works with concrete — will find this book extremely useful. For your free copy, write today on your business letterhead.

SOLVAY Calcium Chloride

SOLVAY PROCESS DIVISION
Allied Chemical & Dye Corporation
61 Broadway New York 6, N. Y.

THOMAS CARR FORREST, JR., consultant on water and reclamation projects is nominated as president of the National Society of Professional Engineers.

Texas engineer nominated NSPE head

When Dallas, Tex., recently found itself faced with a desperate water shortage, the city turned, almost with a reflex action, to get the advice of a hard-working, soft-spoken engineer named Thomas Carr Forrest, Jr. (ENR Nov. 6, p. 51).

At one time in his crowded career, he had drawn up a complete water plan for the city—from source development to sewage treatment—and his experience was needed in a hurry.

Last week, one of engineering's highest honors was virtually assured for Carr Forrest.

Wallace M. Driskell, Jr., of Austin, executive secretary of the Texas Society of Professional Engineers, nominated him for the presidency of the National Society of Professional Engineers. Forrest at present is vice-president of the national society.

• **Believes in broad education**—If Forrest becomes NSPE head next June, the 28,000-member society will be led by a man intensely aware of engineering needs today. He is especially interested in the problem of training engineers for a more rounded view of their communities and responsibilities as citizens and leaders.

"There's no getting around it," he says. "Engineers are running this country. We are living in an engineering age, and the public is starting to realize it."

As a result, Forrest believes engineering colleges should offer more courses in economics and the humanities. He calls for a five-year college

(Continued on page 67)

Now CLIPPER Gives You A NEW CONVERTIBLE MASONRY SAW !

Here's How . . .

FIRST YOU BUY A **CLIPPER** MASONRY SAW



and

THEN YOU ADD . . . the "CONVERTIBLE" CART

THEN USE YOUR CLIPPER "4" WAYS

① Use as a DUSTLESS Masonry Saw
② Use as a DRY Masonry Saw

③ Slip the head from your Clipper Masonry Saw into the "CONVERTIBLE" CART and you have a Handy Concrete Saw.

④ Place it in tracks and you can cut large stone slabs or transite sheets

MODEL HD
9 models from $265

GREATER JOB PROFITS THAN EVER BEFORE!

. . . at any time the cutting head of your Model HD Clipper Masonry Saw can be placed on the "CONVERTIBLE" CART (that's all you do)—you're then ready to saw concrete or asphalt patches or trenches! Imagine...switching from cutting glazed tile, concrete, face brick to sewer, water or gas lines or floor patches. No more fractures beyond removal lines—no more spalling!

But there's more . . . just set the "CONVERTIBLE" CART on Tracks and operate as a TRACK SAW. Stone slabs, Transite sheets, Plywood, Masonite, Pre-Cast Stone and large Refractories can at last be easily cut.

Try This Combination on FREE TRIAL

Order TODAY . . . on FREE TRIAL. Discover for yourself how Clipper will increase production . . . cut costs . . . increase profits. Only through the Clipper FREE TRIAL ARE you guaranteed . . . ACTUAL TEST on the JOB . . . FULL SATISFACTION . . . NO OBLIGATION! . . . If you prefer, order your Clipper Masonry Saw now . . . and the Clipper "Convertible" Cart when the need arises.



SELECT-A-NOTCH

One man easily adjusts Cutting Head to desired height . . . Whether cutting 12" or 1" material. Operator's hands merely guide. Weight supported by rear Bar.

PRESSURE EQUALIZER

Makes your blades last longer . . . Because Equalizer Spring automatically cushions blade pressure whether cutting HARD or SOFT materials. Outstanding for blade economy.

ADJUST-A-CUT CONTROL

Pull the knob—and the Cutting Head is free for finger-tip setting at any desired angle. Release the Knob—and Head is locked in the desired position.

SAVE-A-BLADE DIAL

Just turn the Save-A-Blade Dial to the material hardness and the Pressure Equalizer Spring automatically sets the tension — guarantees faster cutting and longer blade life.

Clipper

KANSAS CITY 8, MISSOURI

PITTSBURGH
ST. LOUIS
CLEVELAND
INDIANAPOLIS
DETROIT
HOUSTON
AUSTIN, TEX.
CHICAGO
LOS ANGELES
PHILADELPHIA
SAN FRANCISCO
CINCINNATI
NEW YORK
ATLANTA
WASHINGTON, D. C.
BOSTON
BIRMINGHAM
KANSAS CITY

"COAST-TO-COAST"

MAIL THE COUPON TODAY!

Serving the World as the World's Largest Manufacturer of Masonry Saws

CLIPPER MANUFACTURING COMPANY
2812 S.W. WARWICK • KANSAS CITY 8, MO.

Send FREE Information and Literature on:

☐ NEW CLIPPER MASONRY SAWS ☐ CLIPPER CONCRETE SAW
☐ DUSTLESS Model HD ☐ FREE TRIAL 89

NAME _____

ADDRESS _____

CITY _____ STATE _____

SOLD ONLY DIRECT FROM FACTORY

SERVICE TO THE HIGHLY INDUSTRIALIZED GREAT LAKES REGION is the main purpose of Lock Joint's permanent manufacturing plant on the outskirts of Detroit. Specializing in pipe 24" in diameter and larger for water supply lines, distribution feeder mains, cooling water or process water lines, subaqueous intakes and outfalls, the Detroit plant is ideally situated to serve such nearby industrial centers as Chicago, Cleveland, Gary, Akron and Toledo. Because of this convenient location, pipe from the Detroit plant can be economically shipped to other parts of the country, as well.

AUGMENTING THE DETROIT OPERATION are our three other modern permanent pipe manufacturing plants. Each of these plants is strategically located to serve the rest of the country East of the Rockies. The Wharton, N. J., plant covers the East; Columbia, S. C., the South; and Turner, Kansas, the Great Plains. No matter how large or small your contracts may be, if your pipe requirements are 16" in diameter or larger, you can rest assured that the efficient and economical answer to your pipe problem can be supplied from one of these four Lock Joint Plants.

SCOPE OF SERVICES—*Lock Joint Pipe Company specializes in the manufacture and installation of Reinforced Concrete Pressure Pipe for Water Supply and Distribution Mains in a wide range of diameters as well as Concrete Pipes of all types for Sanitary Sewers, Storm Drains, Culverts and Subaqueous Lines.*

LOCK JOINT PIPE COMPANY

Established 1905

P. O. Box 269, East Orange, N. J.

PRESSURE PIPE PLANTS: Wharton, N. J., Turner, Kan., Detroit, Mich., Columbia, S. C.

BRANCH OFFICES: Casper, Wyo. • Cheyenne, Wyo. • Denver, Col. • Kansas City, Mo. • Valley Park, Mo. • Chicago, Ill. • Rock Island, Ill. • Wichita, Kan. Kenilworth, N. J. • Hartford, Conn. • Tucumcari, N. Mex. • Oklahoma City, Okla. • Tulsa, Okla. • Beloit, Wis. • Hato Rey, P. R. • Caracas, Venezuela



program in which junior colleges would weed out the "poor risks." If engineering minds are going to run this country, he reasons, they must be trained beyond mere technicalities.

And he also believes there is plenty of room for improvement in engineering techniques, especially where an engineer can save his client money.

In his own specialty—water—Forrest calls for more regional and watershed cooperation among cities competing for water supplies. He hopes small towns will band together to form water districts, rather than to overpumping underground water supplies.

• **Early training**—The man with these ideas—and he is a persuasive advocate of them—was born 56 years ago in Forreston, a small town between Dallas and Waco.

In the summers while he was going through high school, Forrest worked for the Waxahachie city engineer, J. D. Kirven, who today is a prominent earth-moving contractor.

Upon graduation from high school, Forrest entered Trinity University, Waxahachie, for a year, then went back to work for Kirven as inspector of the city's first sewage treatment plant. Forrest then returned to college for a year—this time at Texas A. & M. World War I interrupted his career for a year.

Then came an important move: Kirven, who had become chief engineer for Trinity Farms Co., a firm reclaiming 55,000 acres of Trinity River Valley land, hired his protege.

Under the direction of Kirven and the company's vice-president, T. H. Harbin, Forrest was soon deep in reclamation and drainage work on the Trinity—and he has been at it ever since.

Two years later, when Trinity Farms changed its set-up, the engineering department was wiped out and Forrest was out of a job.

But this was not for long. He had experience in the limited field at a time when demand for water control and reclamation work was booming. His first client was Ellis County Drainage District No. 1, and five years later he was working with about 20 levee districts.

The lure that drew Forrest to Dallas eventually was a partnership in the firm of E. L. Myers and E. W. Noves, prominent municipal engineers. Forrest went to work on a vast project—construction of the $6.5-million Dallas levee system. He was spreading out, too, from strictly reclamation work and was engaging in water supply, distribution and treatment.

H&B
ESTABLISHED 1887

PA-20 HOT MIX ASPHALT PLANT



Easily Portable by Truck . . . Efficient on Small as well as Big Jobs

H & B PA type plants are designed especially for the contractor who moves frequently, and who must be able to get efficient production on small as well as large jobs, under a wide variety of operating conditions.

PA plants are particularly adapted for moving by truck and trailer. If desired, the dryer and the mixing-weigh unit can be furnished with tandem axle and fifth wheel. These plants may be driven with individual electric motors or from one main power unit for the tower and one for the dryer. Gasoline, diesel, diesel electric or electric power may be used.

All PA plants are completely assembled and checked before shipment. See your local H & B distributor, or write for Bulletin P-46.

MOTO-PAVER

does the complete mixing and paving job—in one continuous operation. Ideal equipment for resurfacing work. Ask for Bulletin MP-49.

HETHERINGTON & BERNER INC.

Engineers • Manufacturers

730 KENTUCKY AVENUE • INDIANAPOLIS 7, IND.

Core Drilling *by Contract*

Exploration for coal and other mineral deposits. Foundation test boring and grout hole drilling for bridges, dams and all heavy structures. ***Core Drill Contractors for more than 60 years.***

JOY MANUFACTURING CO.
Contract Core Drill Division • MICHIGAN CITY INDIANA

INDUSTRY'S ALL-TIME FAVORITE FOR LONG RANGE *Economy*

JENKINS
Fig. 106-A
Renewable
Composition Disc

BRONZE
GLOBE VALVE

150 lbs. Steam
200 lbs. O.W.G.

Take a Jenkins Fig. 106-A apart. It's easy to see why it is industry's all-time favorite. Note the liberal dimensions of body and bonnet casting — the heavy, manganese bronze spindle, with more strong threads in contact with the bonnet, regardless of spindle position. See how the slip-on, stay-on disc holder fully protects the edge of the disc, prevents creeping, flaking, or cracking.

Every part, from perfect grip, heatproof handwheel to pipe ends, reflects the designing skill of Jenkins valve *specialists.* There's a good reason. Jenkins Bros. introduced the *first* renewable composition disc valve, — is today the only manufacturer of both valves *and* discs.

Fig. 106-A not only looks better — it proves out better in performance. In any comparison, its long life, low upkeep record has never been surpassed. That is the true measure of valve cost — and it is the reason why industry's shrewdest buyers will settle for nothing less than Fig. 106-A quality.

JENKINS VALVES

LOOK FOR THE DIAMOND MARK

SINCE 1864 TRADE JENKINS MARK

Jenkins Bros

GET THIS FOLDER — Gives details of Fig. 106-A design, and "family" interchangeability. Ask your Jenkins Distributor for Form 189-A, or write Jenkins Bros., 100 Park Ave., New York 17.



Fig. 106-A "Family" Interchangeability meets 90% of your valve needs with a small inventory of parts. Start with the standard Fig. 106-A. Trimming is interchangeable in Globe or Angle body, screwed or flanged. With a few parts, quickly-assembled combinations provide a Lift Check, a Spring-loaded Check, and valves for Stop and Check, Quick-opening, or Throttling service.

Through the years, Forrest helped with the water problems of many Texas cities. He has branched out from his native section of Texas and today is consulting engineer with the Sabine, Guadalupe-Blanco, and Upper Colorado River authorities.

• **Accomplishments**—The following are his main projects during the past fifteen years.

• The Texas Centennial Exposition. Starting in 1935, Forrest worked steadily for 13 months as consulting engineer for the exposition. He planned underground utilities, paving, street construction, drainage and even demolition of structures on the site.

• The New York World's Fair. As a result of his centennial work, Forrest was called to New York to help with that city's extravaganza.

• World War II military construction. Forrest designed and supervised construction engineering phases of Camp Wolters, Mineral Wells; Camp Howze, Gainesville, and Camp Maxey, Paris. All of these multi-million-dollar projects included facilities for 40,000 men. They required paving, sewerage, water systems, etc.

• Airports. Forrest made studies on Love Field and Redbird Airport in Dallas, and planned construction phases of airfields in Greenville, Paris and Gainesville.

• Trinity Industrial District. The firm of Forrest & Cotton is consulting engineer for this booming industrial district that eventually will cover 700 acres near the heart of Dallas. Forrest has supervised drainage, water supply, utility planning and a successful plan of depressing streets and railroad tracks so that factory floors are on grade with the beds of trucks and railway cars (ENR Oct. 23, p. 47).

• Interceptor sewers. Forrest was retained by Dallas to plan the East Bank Interceptor Sewer, an 11-mi line that is one of the largest west of the Mississippi. Now he is designing the West Bank Interceptor Sewer that will give West Dallas modern drainage.

• West Dallas Housing Project. Forrest has been retained as consulting engineer for the $35-million housing project that will house 14,000 persons in 3,500 units.

Forrest's partner is James A. Cotton, a younger man who was active in the Trinity River dam building program before joining Forrest. Forrest & Cotton head a firm of 70 persons, including 35 engineers.

Finke resigns in sewerage squabble

Ralph W. Finke, who has been city engineer at Seattle for the past four and one-half years, submitted his resignation Nov. 17 to Mayor Allan Pomeroy, to take effect not later than Dec. 15. His term was due to expire Jan. 1, and Pomeroy, who took office June 1, had intimated the appointment would not be renewed.

Finke, who was appointed by Pomeroy's predecessor, has developed a proposed $25-million sewage disposal program which has been criticized as "inadequate" by Mayor Pomeroy. Although the first $650,000 unit of the program already is under construction, the entire program is still awaiting expected approval from the city council.

Finke's resignation clears the way for Pomeroy to appoint his own city engineer, subject to approval by a majority of the council. This appointment may set the stage for a knockdown, drag-out fight between the council and the mayor over the sewage disposal program, with the council unlikely to approve a candidate sharing the mayor's opinion.

Pomeroy contends that "complete" treatment of the city's sewage in a central plant is necessary to avoid pollution of Puget Sound; Finke's program called for comminution and dilution at several points.

David Levine, council president, and M. B. Mitchell, chairman of the council's Streets and Sewers Committee, indicated the council probably will withhold action on the sewage disposal program until after a new city engineer has been appointed. Mitchell expressed regret at Finke's resignation.

• **Breaking point**—Mayor Pomeroy brought the sewage disposal controversy to a head Oct. 14 in a sharply-worded letter to Finke.

"I have always been in favor of proper pollution abatement for the city," Pomeroy declared, "but your department's report outlining a program does not satisfy my contention that further comparison studies should be made as to the city's policy for location of sewage treatment plant sites and sewer outfalls as well as the type of treatment that should be provided." Finke had asked the mayor and city council to endorse the $25-million, ten-year sewerage construction program.

Pomeroy's immediate quarrel with the program is over its location of the

Compare the Brunson to any instrument you know. Brunson alone offers you all these advancements . . . the first major surveying instrument improvements during the past 50 years.

- Ball-Bearing Spindle Base
- Ball-Bearing Telescope Axis
- Permanently Lubricated Sealed Dustproof Bearings
- Tangent Adjustment Wobble Pin
- Completely Enclosed Leveling Screws

Precision surveying instruments
Transits, Levels, Rods, Tripods.

LASTING BRUNSON ACCURACY

BRUNSON INSTRUMENT COMPANY, INC.
1405 Walnut St. • Kansas City 6, Mo.

CONCRETE JOIST CONSTRUCTION

RENTAL and ERECTION SERVICE

Member of CONCRETE REINFORCING STEEL INSTITUTE C.R.S.I. founded 1924

Gateway PANS

Stocked in . . .
- CHICAGO
- NEW YORK
- BALTIMORE
- CINCINNATI
- KANSAS CITY



Ask for Catalog No. 3100

GATEWAY ERECTORS, INC.
3233 W. Grand Ave., Chicago 51, Illinois

Rigid frame structure for school gymnasium

International Steel has an impressive record of service for its customers. Delivery on schedule . . . fabrication to most exacting specifications . . . economy—all add up to performance that International customers count on.

If you have a problem of any kind, involving ingenious and economical fabrication of structural steel, you, likewise, may profit by taking advantage of the wide experience and complete facilities of International Steel. The more unusual the problem, the more we like the challenge.

We invite you to put us to the test of International service. Write, call or wire the Special Projects Director.

Steel structural framing for the Kentucky State Office Building



Framing to unusual specifications for Indianapolis Speedway grandstand



Heavy reinforced doors for jet engine testing

INTERNATIONAL Steel Co.

STRUCTURAL STEEL
INDUSTRIAL DOORS
REVOLVING DOORS
STEEL BUILDINGS

1907 EDGAR STREET
EVANSVILLE 7, INDIANA

first of four comminutor plants in an Alki Point residential area. A site has been purchased for this plant, houses cleared away and construction plans are near completion.

"I am convinced that further study would indicate other sites more appropriate," Pomeroy wrote to Finke.

Pomeroy further charges that "previous correspondence and records of conferences between the city and the State Pollution Control Commission, as well as publications by that body, have clearly indicated a definite policy on the part of your department of not desiring to provide adequate sewage treatment." He called the proposed sewage treatment "experimental," considered unsuccessful in other areas and declared it would "result in an eventual added expense to the city."

The mayor asked Finke to estimate the cost of primary sewage treatment in Seattle.

Robert R. Hubbard, principal engineer in charge of all construction work for the Seattle Municipal Engineering Dept. has been appointed acting city engineer for the month of December.

He will fill the month's gap between the resignation of City Engineer Ralph W. Finke, effective Dec. 1, and a new city engineer, yet to be appointed, whose four-year term normally will begin Jan. 1. There has been some speculation that Hubbard might be offered the permanent post.

Aid to Chief of Engineers retires after long service

After a half century in the Army Corps of Engineers, W. H. McAlpine has retired as special assistant to the Chief of Engineers at Washington. He is an authority on construction of dams, reservoirs and levees.

McAlpine was graduated from Massachusetts Institute of Technology in 1896. He was assigned to the Louisville District Engineer's Office in 1912 and had charge of construction and reconstruction of dams on the Kentucky River. He was largely responsible for design and construction of the system of navigation dams on the Ohio River, completed in 1929. During World War I he was Louisville District Engineer.

Lt. Gen. Lewis A. Pick, former Chief of Engineers, said of McAlpine, "I know of no employee in the Corps who has had a more distinguished career than Mr. McAlpine, nor of anyone who has made a greater contribution to our civil works program. He personally participated in the approval and design of nearly every major flood control structure in the country."

unmatched Flexibility of operation ...and of quick fuel change-over

See Cleaver-Brooks Exhibition — Booth 7-W, 20th National Power Show, New York — December 1-6



Combination burner for gas or oil. Oil burner shown in stand-by position for quick change-over.



The Modern **Cleaver-Brooks** Model LR Steam Boiler Equipped with the C-B Rotary Burner

✔ Quick Steaming — Fast, effortless response to fluctuating steam demands

✔ Equally high efficiency using heavy No. 6 oils (or lighter oils) and all types of industrial gas

IF the quantity of steam required in your plant fluctuates throughout the day, depending upon the amount of steam-using equipment in operation, you can cut your steam costs substantially with a Cleaver-Brooks Boiler. It operates at a full 80% guaranteed efficiency whether you require maximum load use of all steam-using equipment . . . or whether your equipment is not in use, requiring as little as 30% response — often just enough to heat the plant.

Install a Cleaver-Brooks Boiler — oil, gas, or combination — either fuel properly proportioned by the exclusive Cleaver-Brooks Burner to meet your fluctuating or constant steam demand. Fully automatic, clean, with a single source for all of its matched parts . . . you benefit with lower fuel bills, less maintenance, reduced operating costs, greater profits. Why not consider changing your present boiler plant and think of flexibility — remember Cleaver-Brooks and get the complete facts on boilers, 15 to 500 HP — 15 to 250 psi.

Write for latest, fully illustrated and descriptive Cleaver-Brooks Steam Boiler catalog.

Cleaver-Brooks
STEAM BOILERS
the first and finest of their class

CLEAVER-BROOKS COMPANY
Dept. P-342 E. Keefe Ave., Milwaukee 12, Wis., U. S. A.
Cable Address: Clebro-Milwaukeewis

Builders of Equipment for the Generation and Utilization of Heat • Steam Boilers • Oil and Bitumen Tank-Car Heaters • Distillation Equipment • Oil and Gas-Fired Conversion Burners



Now... the famous MOTOR SCRAPER joins the A-C ALLIS-CHALMERS line

In order to serve you more completely, Allis-Chalmers has extended the *Finest Line on Earth* by adding the famous MOTOR SCRAPERS and MOTOR WAGONS formerly manufactured by La Plant-Choate. This customer-accepted line meets A-C's 4-point quality requirements in every way.

These big self-propelled units are *designed for your job* . . . easy loading, high-speed hauling and quick, clean ejection. They're *built to take it* . . . job-tested, job-proved through years of use all over the world. Like Allis-Chalmers other earthmoving equipment, the MOTOR SCRAPER is *easy to operate . . . simple to service.*

Today's jobs require a more careful selection of equipment. That's why you'll be money ahead if you make your nearby industrial A-C dealer your headquarters for crawler tractors, motor graders, MOTOR SCRAPERS and MOTOR WAGONS. Stop in soon to discuss your job requirements and see his complete parts and service facilities.



ALLIS-CHALMERS

TRACTOR DIVISION • MILWAUKEE 1, U. S. A.



TW-300 MOTOR WAGON
Bottom Dump
14 cu. yd. struck capacity
280 hp.

TR-200 MOTOR WAGON
Rear Dump
11 cu. yd. struck capacity
176 hp.

TS-200 MOTOR SCRAPER
10 cu. yd. struck capacity
176 hp.

TS-300 MOTOR SCRAPER
14 cu. yd. struck capacity
280 hp.

the Finest Line on Earth

BLOOD BROTHERS
Universal Joints mean sure power delivery–

If a universal "goes out", you're *in* for expensive delays. So when you buy equipment — large or small — check the universal joints.

Chances are they'll be Blood Brothers — a "good omen of good quality". You can count on them to deliver the power, smoothly and dependably, through years of rugged use.



whatever the job!

whatever the equipment!

Universal Joints
and Drive Line Assemblies

BLOOD BROTHERS machine co.
Division of Standard Steel Spring Company
ALLEGAN, MICHIGAN
Chicago Office: 122 S. Michigan Ave.

The BELMONT IRON WORKS

Engineers — Fabricators — Erectors
Contractors — Exporters
Cable address—Beliron
STRUCTURAL STEEL
BUILDINGS & BRIDGES
RIVETED — ARC WELDED
Shops: Eddystone, Pa.—Philadelphia, Pa. Royersford, Pa.

Main Office
22nd St. & Washington Ave.
Philadelphia 46, Pa.

New York Office
44 Whitehall St.,
N. Y. 4, N. Y.

DRILLING CONTRACTORS

Diamond and Shot Core Borings
Dry Sample Borings
Grout Holes and Pressure Grouting
Foundation Testing for Bridges, Dams and other Heavy Structures

Manufacturers, also, of Diamond Core Drilling Machines and complete accessory equipment, including all types of Diamond Drilling Bits. Ask for Bulletin 320

SPRAGUE & HENWOOD, Inc.
Dept. E, Scranton 2, Penna.

OBITUARIES

Jacob L. Warner, 76, former executive of the E. I. du Pont de Nemours and Co. and an engineering consultant since his retirement in 1946, died Nov. 11 in Wilmington, Del. He was graduated from the University of Pennsylvania in 1899. He received his degree of civil engineering in 1902. He entered the engineering department of the DuPont Company in 1904. For many years, he was a plant engineer on location and visited practically every plant owned by the company. His work required extensive tours through all parts of the country, and also in Canada and Mexico.

John B. Robinson, 67, formerly general superintendent for the Panhandle Pipe Line Co., died in Cleveland, Ohio, Nov. 12.

Richard P. Reed, 76, Wilmington, Del., builder, died Nov. 15. He was president of A. S. Reed & Brothers, which constructed such Wilmington landmarks as Wilmington High School, Trinity Church and the old Post Office. He was graduated from the University of Delaware.

George H. Thomas, 88, Dover, Del., building contractor for nearly 40 years died on Nov. 14.

Baxter L. Brown, 88, retired consulting engineer and former president of the St. Louis Board of Public Service, died Nov. 9. He was a vice president of the American Institute of Consulting Engineers, a director of the American Society of Civil Engineers, president of the St. Louis Institute of Consulting Engineers and president of the St. Louis Engineers' Club. He retired in 1941 after serving eight years as head of the Board of Public Service. He entered private practice in 1905 after five years as assistant chief engineer of the Missouri Pacific Railroad. He was joint engineer of the Chain of Rocks Bridge across the Mississippi River at St. Louis.

Raymond H. Mitchell, 53, division engineer for the Boston & Maine Railroad since 1945, died at Boston Nov. 18. He was a member of the Board of Registration for Professional Engineers in Massachusetts.

Augustus M. Turner, 75, Chicago contractor, died in Evanston, Ill., Nov. 15. He was president of A. M. Turner Co., which specializes in municipal and railroad construction work.



American Bridge Protects New Jersey Turnpike's Hackensack River Bridge With

PITTSBURGH'S NEW XLO STRUCTURAL - STEEL - PRIMER

XLO Steel Primer Gives You These 5 Important Advantages:

1. Unexcelled wetting properties insure uniform protective coating of steel surface irregularities caused by mill scale.
2. Controlled and positive drying permits shipment of fabricated parts to the job site within 24 hours after priming, in all seasons of the year.
3. Standard shop practice for thorough cleaning of metal surfaces before priming may be followed without impractical or costly methods of surface preparation.
4. Provides optimum protection against metal corrosion during shipment and erection; also serves as the foundation coat for the field painting system.
5. In addition to meeting ASTM Specification D-234-48 and Federal Specification TT-O-369 covering Raw Linseed Oil, XLO Structural Steel Primer provides a plus in drying over specification requirements.

● **One of the vital links** of the 118-mile New Jersey Turnpike is the $9,500,000 Hackensack River Bridge opened earlier this year. This important portion of the new toll highway which connects the New York metropolitan area with points south, is 5,623 feet long. Spans for this viaduct were fabricated and erected by the American Bridge Division, United States Steel Company.

● **Pittsburgh is proud** that its new XLO Structural Steel Primer was used to safeguard these record-size girders during transit and erection. This new kind of primer is derived from linseed oil, combined with red lead and iron oxide pigments to provide protection for all kinds of fabricated structural shapes during transit, erection and before application of field coats. It is also furnished with 100% red lead, if desired. A variety of IRONHIDE coatings are also available in a range of colors suitable for field coat application.

● **For further information** write, wire or phone Pittsburgh Plate Glass Company, Industrial Sales Division, 2000 Grant Building, Pittsburgh, Pa., or any of the factories listed below.

PITTSBURGH PLATE GLASS CO., Industrial Paint Div., Pittsburgh, Pa. Factories: Milwaukee, Wis.; Newark, N. J.; Springdale, Pa.; Atlanta, Ga.; Houston, Texas; Los Angeles, Calif.; Portland, Ore. Ditzler Color Div., Detroit, Michigan The Thresher Paint & Varnish Co., Dayton, Ohio. Forbes Finishes Division, Cleveland, Ohio. M. B. Suydam Div., Pittsburgh, Pa.

PITTSBURGH PAINTS

PAINTS • GLASS • CHEMICALS • BRUSHES • PLASTICS

PITTSBURGH PLATE GLASS COMPANY

THE PILE FOR THE JOB

9900
COMPRESSED CONCRETE PILES SUPPORT THE BROOKLYN UNION GAS CO. PLANT

Another proof of the sound engineering of

THE MAC ARTHUR METHOD

•

There are 42 years of experience behind the MacArthur Organization

MacArthur
CONCRETE PILE CORP.
18 East 48th St., New York 17, N. Y.
New Orleans • Cincinnati • Boston

PLANNED FOR YOUR PROTECTION

CONTINENTAL Chain Link Fence provides better protection features—more value for your fence dollar. You get engineered erection; 12 fence styles; rigid framework secured by tough rods and wire; galvanized fabric, and welded gates. Get these plus features in Continental's "Planned-for-Protection" fence.

*Trade Mrks Reg. U.S. Pat. Off.

CONTINENTAL STEEL CORPORATION
Kokomo, Indiana
Please send FREE copy of "Planned Protection"—complete manual on property protection.
Name
Address
City State

CONTINENTAL STEEL CORPORATION

MEETINGS

New prestressed concrete ideas discussed at Western conference

Prestressed concrete—rapidly coming of age—is still suffering some growing pains. That was the impression given the 275 attending the Western Conference on Prestressed Concrete held Nov. 14 and 15 at Los Angeles. That this method of construction has passed the novelty stage was shown by the number and variety of jobs described in conference papers. Much emphasis is given now to further research on specific details as well as to polishing specifications and code provisions.

The latter subject was analyzed in a panel discussion on specifications and building code provisions as applied to prestressed concrete. The panel was chairmaned by Sam Hobbs, Portland Cement Association, and included Prof. C. P. Siess, University of Illinois, Prof. T. Y. Lin, University of California, W. J. Jurkovich, California Bridge Department, and F. M. Andrus, Los Angeles County Building Department.

Siess discussed design specifications. He strongly urged standards of recommended practice as opposed to fixed specifications at this stage, to promote development rather than to hinder progress and improvement. Jurkovich discussed job specifications with particular reference to bridge construction. He advocated specifications that encourage competition in the various methods available and suitable for the work. Such specifications should make definite requirements of materials and performance.

The entire panel endorsed the idea that leading codes should provide for approval of alternate methods without specific fixed code provisions. Pending further development, such means of approval could be based on recommended practice, experience record and analysis for safety.

A survey of research covering some 200 universities and organizations was reported on by R. K. Steele of the Naval Civil Engineering Research and Evaluation Laboratory at Port Hueneme, Calif. Included among the widespread investigations are a study of transverse or eccentric loading on slender prestressed columns (University of California), a study of prestressed rigid frames (Illinois Tech), and glass-fiber wire and cable study (Princeton University).

Prof. R. E. Davis, University of California, detailed the means for selecting concrete materials that will produce uniformity and strength as well as reduce drying shrinkage and creep. He reviewed methods of placing to prevent segregation and water gain.

Practicability of continuous design was discussed by Jean Muller of Freyssinnet Co. He diagrammed the means for analysis to determine and combine the stresses due to simple beam action, continuity and prestressing, and outlined how cables should be located in continuous members.

Among the recent jobs described was the Barrett-Lick garage in San Francisco (ENR Nov. 13, p. 38) where use was made of heavy girders—twice the size of those in the Walnut Lane Bridge. Another building just getting to the stressing stage is a warehouse for the Long Beach, Calif., harbor department that includes 82 prestressed girders. J. R. Bole, structural engineer, presented cost data on a warehouse that showed a slightly higher cost for prestressed concrete girders than for unprotected steel truss or rolled-beam roof construction. The prestressed concrete provided additional fire-resistance and lower maintenance for the structure.

The conference was sponsored by the California Institute of Technology, University of Southern California, University of California, and the Naval Civil Engineering Research and Evaluation Laboratory. Proceedings will be available in February for $5.00 from Dept. of Conferences, University Extension, University of California, Los Angeles 24, Calif.

Conference on resources planned for next March

Plans for a national conference on conservation and development of national resources are being made by Resources for the Future, Inc., a nonprofit organization set up recently under auspices of the Ford Foundation. President-elect Dwight D. Eisenhower has expressed his willingness to call such a conference to be held some time in March.

President of Resources for the Future, Inc., is Horace M. Albright, president of United States Potash Co. Charles W. Eliot, planning consultant, is executive director.

Rolling Steel DOORS

Manually, Mechanically, or Power Operated



The vertical, roll-up action of a rolling steel door makes it ideally suitable for use where, in many cases, no other type of door would adequately meet the requirements. Quick opening, quick closing Rolling Steel Doors occupy no usable space either inside or outside the opening . . . they create no overhead obstructions above the floor—cranes may be employed to handle materials adjacent to the door opening. All-metal construction of Rolling Steel Doors provides permanence, greater protection against intrusion and fire, and assures you a lifetime of trouble-free service. When you select a rolling steel door, it will pay you to compare the manufacturer's specifications as well as the price tags . . . you will find that the hot-dipped galvanized curtain slat material that goes into Mahon Rolling Steel Doors is chemically cleaned, phosphated, and treated with a chromic acid solution to provide paint bond, and that the protective coating of synthetic enamel is baked on at 350° F. prior to roll-forming. This is just one of the extra value features of Mahon Rolling Steel Doors. See Sweet's Files for complete information including Specifications, or write for Catalog G-53.

THE R. C. MAHON COMPANY

Detroit 34, Michigan • Chicago 4, Illinois • Representatives in all Principal Cities

Manufacturers of Rolling Steel Doors, Grilles, and Automatic Closing Underwriters' Labeled Rolling Steel Doors and Fire Shutters; Insulated Metal Walls and Wall Panels; Steel Deck for Roofs, Partitions, and Permanent Concrete Floor Forms.

ROLLING STEEL DOORS, SHUTTERS AND GRILLES TO MEET EVERY REQUIREMENT

MAHON

JENNITE J-16®

Surface Seal



IN SEPTEMBER 1949, the intersection of Highways U.S. 24 and U.S. 25 outside Detroit, Michigan, was sealed with J-16 for Michigan State Highway Department to stop asphalt pavement distortion through elimination of softening action of fuel and oil drippage from excessive vehicle stopping and starting.

IN OCTOBER 1952, Officials reported that the J-16 seal continues to serve its purpose after three years of traffic amounting to 3,000 to 3,500 trucks and automobiles per day.

Protective maintenance pays

For complete details on Jennite J-16— Write for Specifications and these two brochures.

MAINTENANCE INC.

WOOSTER·OHIO

CABLE ADDRESS "MINCO"

LEGAL

Occupancy as constituting acceptance of work

Where the owner by reason of circumstances was forced to move into a house, such occupancy did not necessarily constitute a waiver of defects in the work.[1]

In this instance, action was brought by the owner against the contractor to recover damages for breach of contract and to restrain the contractor from collecting on a promissory note that had been given him in payment for the work.

The owner sought to stop payment on the note on the ground that the contractor had not properly performed the work for which the note was given.

The contractor claimed that the occupancy of the building by the owner constituted a waiver of the defects in the work.

The court held that the owner was forced by circumstances to occupy the house and that under such circumstances occupancy did not constitute a waiver of defective construction. The court held further that since the defects in the work were trivial and could easily be remedied, that there was substantial performance of the contract and that the contractor was entitled to recover the balance due under the contract less the cost that was incurred for remedying the defects.

(1) Beeson et ux. v Oden, 58 So. 2d 221, Court of Appeals of Louisiana, March 28, 1952.

Time of performance

A contract for construction of a coal-loading chute contained no provision as to time of performance. When the contractor delayed completion beyond what the owner thought proper, the owner attempted to terminate the contract, holding that he was perfectly within his rights to do so.

The court held, however, that the right to terminate such contract at will ordinarily applies to contracts for personal services and does not apply to a contract calling for a definite amount of work. In the latter case the general rule is that the contract must be performed within a reasonable time.[1]

(1) Stephens et al. v Horn, 236 S.W. 2d 953, Court of Appeals of Kentucky, Dec. 8, 1950.

(These summaries of court decisions are prepared by I. Vernon Werbin, New York attorney and civil engineer.)

SAFE

SURE

FAST

EASY

VALVE OPERATION



Get all 4 with LIMITORQUE®

For remote or local control . . . positive, speedy, safe, dependable opening and closing of all types of valves up to 120" diameter . . . equip with Limitorque. *Just pushing a button sets them in operation.*

They provide complete safety in two ways: First, they protect the workmen by eliminating the need of climbing to high or hazardous locations for manual valve operation. Second, they protect the valve operating parts by assuring a tight valve closure without overload on disc, seating rings or valve stems . . . and by automatically shutting-off the motor if foreign obstructions are met during the closing cycle.

Limitorque is actuated by any available power source . . . electricity, air, water, gas or oil.

Your valve maker can supply Limitorque Controls.

For complete details about Limitorque, send for Catalog L-50.

Philadelphia Gear Works, INC.



ERIE AVE. AND G ST., PHILADELPHIA 34, PA.

NEW YORK • PITTSBURGH • CHICAGO • HOUSTON • LYNCHBURG, VA.

Industrial Gears and Speed Reducers
LimiTorque Valve Controls

every other MARION 151-M on the IRON RANGE is a REPEAT ORDER

A NOTABLE RECORD OF ACCEPTANCE

Many of the biggest companies on the Iron Range are owners of MARION 151-M shovels.

MORE THAN HALF of these MARION owners have two or more 151-M machines.

In these days of urgent demand for increased ore production —days of high operating costs—days in which it is perhaps more important than ever to make wise selections of equipment, MARION is humbly proud of this unusual record of acceptance.

Ask your nearest MARION representative about the jobs the 151-M is doing in quarrying, coal stripping, construction and mining.

MARION POWER SHOVEL CO.
MARION, OHIO, U. S. A.

OFFICES AND WAREHOUSES IN ALL PRINCIPAL CITIES

from ¾ cu. yd. to 45 cu. yds.

CONSTRUCTION REPORTS

Bids Asked—Low Bidders—Contracts Awarded—First Section

Compiled by Business News Department—Engineering News-Record, 330 W. 42nd St., New York 36, N. Y.

ELSIE EAVES, Manager — *J. A. MAHONEY, Reports* — *M. R. ROESSLER, Statistics*

NEW ENGLAND

BIDS ASKED—HEAVY CONSTRUCTION

▲ **Mass., Boston**—PIER—B.A. 12/17—Commonwealth of Mass., Port of Boston Auth., East Boston, Contr. 8, constr. Pier 1, $9,500,000. Plans deposit $100, refundable. Fay, Spofford & Thorndike, 11 Beacon St., Boston, engrs. CD 11/13.

Mass., Haverhill—SWIMMING POOL—Bids Asked—Young Men's Christian Assn., Winter St., swimming pool addn. $150,000.

BIDS ASKED—BUILDINGS

▲ **Mass., Dighton**—PLANT—B.A. 1/5—Arnold Hoffman & Co., Inc., 55 Canal St., Providence, R. I., plant addn. $1,000,000. Extended date. Jenks & Ballou, 2600 Industrial Trust Bldg., Providence, R. I., engrs. CD 11/13.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **John Bowen Co., Inc.**, 173 Boston St., Boston, Mass. CA. **$11,379,587.** Contr. 1-A P-H 8 chronic disease HOSPITAL and NURSES HOME, Forest Hills, BOSTON, MASS. State, Dpt. P. Health, State House, Boston, Mass. CD 9/16, under LB.

Rich Bros. Constr. Co., 410 Park Square Bldg., Boston, Mass., CA **$693,396.** Spaulding SCHOOL, NEWTON, MASS. City, Pub. Bldg. Comn. Office, Newton, Mass. CD 10/28, under LB.

Gil Wyner Co., Inc., 12 Newland St., Malden, Mass. LB **$319,800.** superstructure women's DINING HALL, South St., WALTHAM, MASS. Brandeis University, 415 South St., Waltham, Mass. Isidor Richmond & Carey Goldberg, 16 Arlington St., Boston, Mass., archts.

▲ **Harry Kay Assocs.**, Middletown, Conn. Owner Builds. $4,000,000, 204 HOMES, in 108 acres N. Main St. west to Mountain Road, WEST HARTFORD, CONN.

MIDDLE ATLANTIC

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ **NEW YORK**—Bureau of Contracts & Accounts, The Governor Alfred E. Smith State Office Bldg., Albany, **The Lane Constr. Corp.**, 37 Colony St., Meriden, Conn., LB. **$7,096,781,** est. $8,585,000. 11.56 mi. thruway and 5.31 mi. acc. mi., New York State Thruway-Catskill Section-Sub 5 (Greene Co. line-Normanskill Creek); Selkirk Interchange; Stylebarrck Rd.; Beaver Dam Rd.; Clapper Rd.-Weisheit Rd.; Vample Rd.; Coeymans-Indian Fields Pt. 1. SH 1468, River S.H. 193; Glenmont-Feure Bush, S.H. 367; Albany-Bethlehem S.H. 5499, C.T. 52-8P, R.C., 52-111, S.T. 52-29 Albany Co.

Leon Reynolds, R.D. No. 1, Northville, N. Y., LB. **$271,916,** est. $288,000, 4.53 mi. Amsterdam-Hagaman S.H. 298, Manny Corners-Blue Corners, S.H. 1498 FARC 52-112, Montgomery Co.;

John J. Harvey Inc., 38 Campion Rd., Utica, N. Y., LB. **$387,274,** est. $419,200, City of Little Falls, Erie Canal Lock 17, M-52-2, Herkimer Co.;

Max Di Fiore & Son, Inc., 204 Edgeland St., Rochester, 9, N. Y., LB. **$73,884,** est. $83,000. 0.21 mi. Rochester City-Brooks Ave., FAC 5-215, Monroe Co.;

Depew Paving Co., Inc. & McLain Constr. Corp., 4955 Broadway, Depew, N. Y., LB. **$2,913,183,** est. $3,510,000, 2.14 thruway and 0.94 mi. N. Y. State Thruway-Ontario Section-Sub. 13 Union Rd.-Transit Rd.; Cayuga Rd., Youngs Rd. and 2 marginal roads, O.T. 52-17, S.T. 53-30, Erie Co. Bids Nov. 20. CD 10/28.

Frank Mascali & Sons, Inc., 210 St. and 31 Ave., College Point, N. Y. LB. **$108,730,** grading, curbing, flagging, constr. receiving basins and mails, b. conc. paving (permanent pavement) 71 Ave. from Kissena to Parson Blvds. and in Parson Blvd. from 65 to 71 Aves., FLUSHING, N. Y. President Queens Boro, Boro Hall, 120-55 Queens Blvd., Kew Gardens, 24, N. Y. Bids Nov. 14. CD 11/6.

Marcam Constr. Co., Inc., 2427 W. Third St., Brooklyn 23, N. Y., LB. **$381,077,** uncovering of all work performed under the abandoned Cont. No. 163638 for construction of combined sewer and appurtenances in 133 Ave. from 223 St. to Francis Lewis Blvd.; 224 St. from 133 Ave. to 131 Ave.; 225 St. from 133 to 131 Aves.; 131 Ave. from 225 to 226 Sts., and from 230 to 227 Sts.; 226 St. from 133 to 131 Aves.; 227 St. from 133 to 130 Aves.; 228 St. from 133 to 130 Aves.; 229 St. from 133 to 130 Aves.; 230 St. from 133 to 131 Aves.; 131 Ave. from 225 to 226 Sts. and from 230 St. to 227 Sts.; 226 St. from 133 to 131 Aves.; 227 St. from 133 to 130 Aves.; 228 from 133 to 130 Aves.; 229 St. from 133 to 130 Aves.; 230 St. from 133 to 131 Aves.; 130 Ave. from Francis Lewis Blvd. to 227 St., NEW YORK; President Queens Boro, Queens Boro Hall, 120-55 Queens Blvd., Kew Gardens, 24, N. Y. Bids Nov. 13. CD 11/6.

▲† **Malan Plumbing Co., Inc.**, 25-09 42 Rd., Long Island City, N. Y. LB. **$1,413,000,** ground electronics storage and overall facilities, Griffiss Air Force Base, Eng. 30-075-53-127, ROME, N. Y. U. S. Eng., 80 Lafayette St., New York 13, N. Y. Bids Nov. 18. CD 10/16.

▲ **NEW JERSEY**—N. J. Hy. Auth., State Office Bldg., 1035 Parkway Ave., Trenton,

Frederick Snare Corp., 233 Broadway, New York, N. Y., CA, **$2,445,635,** river piers for Raritan River bridge on Garden State Parkway (Contract 5) Woodbridge Twp. and Sayreville, Middlesex Co. Bids Nov. 6, awarded Nov. 20. CD 11/11, under LB.

▲† **Ole Hansen & Sons, Inc.**, Pleasantville, N. J., LB, **$1,369,928,** airfield pavements, Naval Air Station, NOY 70170, Spec. 31805, ATLANTIC CITY, N. J. Dpt. Navy, Phila. Naval Base, Phila., Pa. Bids Oct. 30.

▲† **Daniel J. Cronin, Inc.**, 717 S. Orange Ave., Newark, N. J. LB, **$1,644,000,** extension to altitude exhauster wing at Naval Air Turbine Test Station, West Trenton, TRENTON, N. J. Officer in Charge of Construction, Dist. P. Wks. Office, Navy Yard, Phila., Pa. Bids Nov. 6, Montgomery Co. Bids Oct. 30, awarded Nov. 14. CD 11/3, under LB.

▲ **James N. Driscoll Co., Inc.**, 1121 Frankford Ave., Phila., Pa., LB, **$3,417,435.** interceptor sewer, Lower Delaware Collecting System, PHILA., PA. Dpt. Procurement, City Hall Annex, Phila., Pa. Bids Nov. 17. CD 10/20.

MARYLAND—State Rds. Comn., 108 E. Lexington St., Baltimore,

McLean Contg. Co., 1301 Fidelity Bldg., Baltimore, Md. LB. **$482,030** slag, **$481,957** stone, constr. 2 dual multiple span steel beam bridges to carry Annapolis By-Pass over Admiral Dr. and cowhide branch, adjacent road work, Contr. 263-21-515, Anne Arundel Co. Bids Dec. 2. CD 11/12.

† **J. H. Lawrence Co.**, 2600 Huntington Ave., Baltimore, Md. LB. **$358,864.** steam distr. sys. addn., Eng. 18-020-53-24, EDGEWOOD, MD. U. S. Eng., 24 St. and Maryland Ave., Baltimore, Md. Bids Nov. 18. CD 10/22.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **Webb & Knapp, Inc.**, 270 Park Ave., New York 17, N. Y. Owner Builds. **$12,000,000.** 18 story OFFICE, STORE and SHOWROOM BLDG. 110 W. 34 St., NEW YORK, N. Y. Kahn & Jacobs, 2 Park Ave., New York 16, N. Y., and Rudolph C. P. Boeller, c/o owner, archts.

▲ **Webb & Knapp, Inc.**, 270 Park Ave., New York 17, N. Y. abandoned project, for 4 story OFFICE, on block between 6 and 7 Ave. running from 34 to 33 Sts. NEW YORK, N. Y. Est. **$5,000,000.** CD 7/18/51 under CA.

▲† **Carl Buhr, Inc.**, Grand Central Terminal Bldg., New York 17, N. Y., CA, **$1,453,768,** 200x1200 ft. WAREHOUSE, Raritan Arsenal, RARITAN, N. J. U. S. Eng., 80 Lafayette St., New York, 13, N. Y. Bids Oct. 22. CD 9/24.

▲ **Welsh Grant Corp.**, St. Davids Rd., Phila., Pa., Separate Contracts. **$2,000,000.** RESIDENTIAL DEVELOPMENT, Krewstown Rd., PHILA., PA.

▲ **McCloskey & Co.**, 1620 W. Thompson St., Phila. Pa., LB **$4,936,000.** Wilson Park Low Rent HOUSING, PHILA., PA. Housing Auth., 42 S. 15 St., Phila. Pa., Louis Doane, Penna R. R. Bldg., Wilmington, Del. engr. Bids Nov. 13. CD 10/14.

† **Wm. T. Lyons Co.**, 1700 Friendship St., Baltimore, Md. CA. **$631,980.** low temperature test chamber LABORATORY OFFICES, REPAIR SHOP, outside utilities, Eng. 18-020-53-6, EDGEWOOD, MD. U. S. Eng., 24 St. and Maryland Ave., Baltimore, Md. CD 11/12, under LB.

▲ **Morris Cafritz**, 1404 K St. N. W., and **Charles H. Tompkins**, 907 16 St. N. W., Wash., D. C. Own Forces, **$26,000,000,** community of OFFICES, APARTMENTS, SHOPS AND HOTELS, Florida and Connecticut Aves. 19 St. and Columbia Rd. N. W., 1st unit, Park at Your Desk Office Bldg. **$8,000,000;** 2nd unit office, **$4,000,000;** 3rd unit hotel, **$9,000,000;** 4th unit apartment, **$5,000,000** WASH., D. C. Roy L. Werner, 1404 K St., N. W., Wash., D. C. archt.

SOUTH

BIDS ASKED—HEAVY CONSTRUCTION

La., **New Orleans**—B.A. 12/19—City, City Hall, Palmetto Street Overpass, $750,000. Extended date. David W. Godat & Assoc., Terminal Station Bldg., engrs. CD 11/18.

▲ **Fla., Coral Gables**—B.A. 3/1—City, M. B. Garris, city engr., City Hall, sewage treatment plant and sewer lines. $2,850,000. CD 11/11.

BIDS ASKED—BUILDINGS

Ala., **Birmingham**—CHURCH—B.A. 12/16—West End Baptist Church, c/o Lawrence S. Whitten, archt., Brown-Marx Bldg., church. $450,000. CD 2/6.

Ala., **Eufala**—HOSPITAL—B.A. 12/16—Barbour Co., Eufala, hospital. $700,000. Sherlock, Smith & Adams, 303 Washington Ave., Montgomery, archts. CD 3/18.

Ala., **Huntsville**—SCHOOL—B.A. 12/16—City, high school. $875,000. Plans deposit $50. Van Keuren, Davis & Co., 3004 7 Ave. S., Birmingham, archts. Extended date. CD 8/5.

Fla., **Tallahassee**—POWER PLANT—B.A. 12/16—City, City Hall, power plant addn. Approx. $500,000. Plans deposit $50. Reynolds, Smith & Hills, P.O. Box 4817, Jacksonville, engrs.

Ga., **Warrenton**—HOUSING—B.A. 12/16—Warrenton Housing Auth., Warrenton, housing Projects GA 127-2 and GA 127-2. $325,000. CD 4/1.

Ga., **Arlington**—HOUSING—B.A. 12/18—Arlington Housing Auth., Arlington, housing Project GA111-1. Plans deposit $50. H. L. Holman, Jr., Ozark, Ala., archts.

Ga., **Statesboro**—HOUSING—B.A. 12/18—Statesboro Housing Auth., Statesboro, 88 unit housing Projects GA-132-1 and GA-132-2. $800,000. Abreu & Robeson, Walton St. N.W., Atlanta, archts. CD 4/1.

Ga., **Waynesboro**—HOUSING—B.A. 12/18—Waynesboro Housing Auth., Waynesboro, housing Projects GA 86-7, GA 86-8, GA 86-9, GA 86-10, and GA 86-11. $300,000.

† Tenn., **Murfreesboro**—LAUNDRY—B.A. 12/23—Veterans Admin., Munitions Bldg., Wash., D. C., Laundry Bldg. 12 addn., Veterans Admin. Hospital.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

† **T. F. Scholes, Inc.**, P. O. Box 4598, Berkley Station, Norfolk, Va., LB **$449,971,** training railway addn., ENG 44-110-53-7; Spec. 771, FORT EUSTIS, VA. U. S. Eng., foot of Front St., Norfolk, Va. Bids Nov. 18. CD 10/23.

† **A. H. Ewing's Sons**, 3 W. Cary St., Richmond, Va., LB **$333,383,** operations bldg., control tower, utilities

PROJECTS COVERED

Projects—By Size

Construction projects here reported cover the United States and Canada, are of these minimum sizes or larger: water supply, earthwork, waterways $34,000; other public works $60,000; industrial buildings $82,000; other buildings $300,000.

Classes of Construction

(Name in order of Listing)

Water Supply	Latin America
Sewers, Waste Disposal	Public Buildings
Bridges	Commercial Buildings
Streets & Roads	Industrial Buildings
Earthwork, Waterways	Unclassified

Stages Reported

PROPOSED WORK: Including appointment of engineers or architects.

BIDS ASKED (new announcements only). For full calendar, see also preceding issues of ENR.

LOW BIDDERS: On jobs below $500,000 value all low bidder news will be the final reports published on the projects invloved except where award is not made to the low bidder. In this case, a supplementary contract award report will be published.

CONTRACTS AWARDED: Except awards to low bidders previously reported in low bidder stage.

Dates shown are of issue in which last previous report was published.

Symbols and Abbreviations Include:

†	Federal Government
▲	Project of $1,000,000 or over.
B.A.	Bids Asked
ENR	Engineering News-Record
CD	Engineering News-Record Construction Daily

Manufacturers Of Reliable Pile Driving Hammers

1852 *1952*

VULCAN IRON WORKS
CHICAGO·U·S·A

and Pile Extractors

Manufacturers of Pile Driving Hammers and Pile Extractors

VULCAN IRON WORKS • 329 NORTH BELL AVENUE • CHICAGO 12, ILL.

RENT
these cost-reducing forms for concrete

Cost records from job after job prove that Economy's system of Form Engineering and Rental Service means substantial savings in TIME—MATERIAL—MONEY for GREATER PROFITS.

ECONOMY FORMS CORP.
HOME OFFICE • DES MOINES, IOWA

DISTRICT SALES OFFICES: Kansas City, Mo.; Omaha, Neb.; Minneapolis, Minn.; Ft. Wayne, Ind.; Cincinnati, Ohio; Pittsburgh, Pa.; Springfield, Mass.; Metuchen, N. J.; Decatur, Ga.; Dallas, Texas; Los Angeles, Calif.; Oakland, Calif.; Denver, Colo.

ECONOMY METAL FORMS

dewater the Complete way

Wherever there's ground water, only "Complete" gives COMPLETE assurance of COMPLETE elimination of the hazard. These patented fluted tube wellpoints remove more water faster . . . more easily, more efficiently, most economically!

Write today for "Complete" catalog Dept. ER

COMPLETE MACHINERY & EQUIPMENT COMPANY, INC.
36-40 11th STREET
LONG ISLAND CITY, N. Y.

COMPLETE WELLPOINT SYSTEMS
FOR SALE OR RENT

for Readiness Hangar, ENG 44-110-53-5, Spec. 751. LANGLEY AIR FORCE BASE, VA. U. S. Eng., foot of Front St., Norfolk, Va. Williams, Coile & Blanchard, 3415 Virginia Ave., Newport News, Va., engrs.-archts. Bids Nov. 13.

† **Jack Stone Co.**, 55 "K" St. S. E., Wash., D. C. LB $948,960, radio transmitter antenna sys. at Monogram and radio receiver antenna sys. at Northwest, NOY 74887, Spec. 35790, MONOGRAM and NORTHWEST, VA. P. Wks. Office, Fifth Naval Dist., U. S. Naval Base, Norfolk, Va. Bids Nov. 17. CD 11/6.

† **Horne Bros., Inc.**, 25 and River Rd., Newport News, Va. LB $334,000. 5 structural steel radiators (towers) one at 800 ft. four at 300 ft. high, NOY 28492. Spec. 30127, MONOGRAM, VA. P. Wks. Office, Fifth Naval Dist., U. S. Naval Base, Norfolk, Va. Bids Nov. 18. CD 11/6.

▲ † **McKoy-Helgerson Co.**, P. O. Box 57, Greenville, S. C. LB $1,536,000. addnl. facilities, Naval Mine Depot, NOY 26917, Spec. 28932, YORKTOWN, VA. P. Wks. Office, Fifth Naval Dist., U. S. Naval Base, Norfolk, Va. Baskervill & Son, 2313 W. Cary St., Richmond, Va. engrs.-archts. Bids Nov. 13. CD 10/7.

▲ **NORTH CAROLINA**—State Hy. & P. Wks. Comn., Raleigh:

Barnus Constr. Co., Box 561, Kinston, N. C. LB $89,825, Est. $75,000-$100,000, sand asph. base, surf. 6.6 mi. U. S. 70, Proj. BS 2-6-16-127, Carteret Co.;

Macon Constr. Co., Franklin, N. C., LB $202,599, est. $225,000-$250,000, grading 5.79 mi. Proj. 7200, S.F. 186, (6), Caldwell Co.;

A. R. Thompson Constr., Inc., Rutherfordton, N. C. LB $129,196, est. $200,000-$225,000, traffic bound macad. bit. surf. tr., Proj. 9-451, McDowell Co.;

Ben B. Propst, Box 526, Concord, N. C. LB $781,793, est. over $400,000. traffic bound macad., stabil. aggregate, bit. surf. tr. 25.03 mi. Proj. 5845, F-645 (9), Davidson and Randolph Counties;

H. F. Ramsey Co., Inc., Asheville, N. C. LB $323,123, est. $400,000-$500,000 traffic bound macad., bit. surf. tr. 6.59 mi. U. S. 19 and 23, Proj. 9701, F-392 (4), F-635 (2), F-543 (7), Yancey and Madison Counties;

Sloan Constr. Co., Inc., Box 747, Greenville, S. C. LB $142,157, est. $175,000-$200,000, sand asph. or b. conc. base and surf. 14.38 mi. Proj. 3-9-32-219, 3-9-33-230. New Hanover and Pender Counties;

H. R. Stewart & Co., 5 Westchester Dr., Asheville, N. C. LB $180,780, est. $150,000-$175,000, traffic bound macad., bit. surf. tr. 4.49 mi. N. C. 105, Proj. 8135, S-450 (1), McDowell and Burke Counties;

Taylor Constr. Co., Inc., Johnson City, Tenn., LB $124,656, est. $125,000-$150,000. b. conc. binder and surf. 10.4 mi. U. S. 52 and 21, N. C. 67, Proj. BS 8-6-72-155, BS 8-6-76-149, Code 5900-805, Code 5900-813, Stokes and Yadkin Counties. Bids Nov. 18. CD 11/10.

Ivy H. Smith Co., 1525 San Marco Blvd., Jacksonville, Fla., CA, $141,375, piping only municipal water softening plant addn., HOLLYWOOD, FLA. City, Joseph W. Watson, city mgr., City Hall, Hollywood Fla. Eugene C. Hedges, Hollywood, Fla., city engr.

Boh Bros. Constr. Co., 2400 Cypress St., New Orleans, La. CA $732,398. Proposal No. 2652, constr. St. Bernard Underpass, Gentilly Blvd. at Florida Ave., New Orleans, LA. City, Purchasing Div., 302 City Hall, New Orleans, La. Bids Oct. 24, awarded Oct. 31. CD 11/6 under CA.

Volz Constr. Co., Ripley, Tenn., CA $261,000. WW imprvs., east part of JACKSON, TENN. City, Jackson, Tenn. CD 11/27/51.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **Duke Constr. Co.**, Military Hy. and Bells Rd., Norfolk, Va., Owner Builds. Approx. $2,400,000. 285 frame, masonry HOUSES; $750,000, 1 story masonry shopping center, approx. 15 stores, NORFOLK, VA. CD 8/8.

Fred J. Wiggins, 130 E. 4 St., Charlotte, N. C. Owner Builds. $600,000. 65 RESIDENCES, 3rd addn. to Lakeview Sub-division, CHARLOTTE, N. C.

▲ **Fiske-Carter Constr. Co.**, Spartanburg, S. C. CA. Approx. $1,000,000. MILL 2, CLINTON, S. C. Clinton Cotton Mills, Clinton, S. C. CD 10/31, under CA.

L. A. Nelson & Co., Main St., Greenville, S. C. CA $90,000. shirt PLANT addn., GREER, S. C. Greer Shirt Corp. Greer, S. C.

George L. Fuller Constr. Co., Fuller Bldg., Augusta, Ga., CA. $558,000. HIGH SCHOOL, NORTH AUGUSTA, S. C. Aiken County School Dist., Aiken, S. C. Bids Oct. 29. CD 11/6, under LB.

De Give, Dunham & O'Neill, Grand Theatre Bldg., Atlanta, Ga., CA. $981,000, TWIN BLDG. addn., at State Hospital, MILLEDGEVILLE, GA. State Dpt. P. Welfare, State Office Atlanta, Ga. Bids Oct. 21. CD 10/28, under LB.

Lakewood Homes, Shorter Ave., Rome, Ga., Owner Builds $600,000, 125 RESIDENCES, ROME, GA.

Gill Constr. Co., 113 S.E. 2 St., Ft. Lauderdale, Fla., Owner Builds, $350,000. MOTEL, FORT LAUDERDALE, FLA.

Cowart Bros., 217 W. Church St., Jacksonville, Fla., Owner Builds, $750,000, 74 RESIDENCES, JACKSONVILLE, FLA.

Clutter Constr. Co., 20 S.W. 27 Ave., Miami, Fla., Owner Builds, $400,000, HOTEL, MIAMI BEACH, FLA.

Ray Childs, Decatur, Ala., CA, $360,000, CHURCH addns., DECATUR, ALA. First Presbyterian Church, Decatur, Ala.

(Continued on page 85)

Where the *other* services also count – it's always BAYLEY WINDOWS



Ask For Copy of These Catalogs
– or see them in Sweet's

PIVOTED WINDOWS (STEEL ONLY)

PROJECTED WINDOWS (ALUMINUM OR STEEL)



PROJECTED RIBBON WINDOWS (ALUMINUM)



SAF-T-GARD WINDOWS (FOR MENTAL HOSPITALS)



GUARD AND DETENTION WINDOWS (FOR CORRECTIONAL INSTITUTIONS)

For Factory and Power Plants
- Office Buildings
- Commercial Buildings
- Monumental Buildings
- School Buildings
- Hospitals and Sanitariums
- Prisons and Institutions.

Steel or Aluminum Windows of
Time-tested Design for Modern or Traditional Buildings of all Types

Through 73 years of serving the construction industry Bayley has never been satisfied to build for quality *alone*. They also recognized the need for a fully cooperative relationship from the time of a building's inception to its occupancy. With that sense of responsibility, they pioneered during those years many of the most worthwhile developments in the design of metal windows.

The objectives of Bayley Window design have always been to improve natural daylighting, vision and ventilation with an enduring window, and to constantly develop products in harmony with advancing architectural trends.

The efficiency, quality and all-around economy of Bayley Windows — in either steel or aluminum — is evidenced by their use in outstanding buildings throughout the world. The nationwide Bayley Organization — through District Offices and local representatives — places on ready call a trained Window Engineer to work with you on any window requirement, from inception to completion of a project. Write or phone.

See Bayley in Sweet's. Complete catalogs on aluminum windows, 17 a/BA; steel windows, 17 b/BAL; Saf-T-Gard Hospital Detention Window, 17b/BAY.

The William **BAYLEY** *Company*
Springfield, Ohio

District Sales Offices: Springfield, Chicago 2, New York 17, Washington 16

73 *Years of* **RELIABILITY**

- ⅜ cu. yd. Bucket
- 1700 lb. Capacity
- 9½' Lifting Height
- Hydraulic Lift and Dump
- ¾ cu. yd. Snow Bucket
- Handles 42" Sod Fork
- Operation of Lift-Loader does not interfere with use of Maintainer blade

HUBER LIFT-LOADER

Give your jobs a REAL lift with the bigger, better HUBER lift-loader.

It travels around like a pick-up truck, and converts easily from a ⅜ cubic yard material handling loader to a ¾ cubic yard snow bucket or a 42" sod fork.

Its 1700-lb. lifting capacity makes short work of big jobs. The HUBER's ability to dump 45 inches ahead of the front wheels makes it easy for the operator to spot his loads. And it is operated hydraulically, including control of the bucket.

There's a BIG BONUS in other HUBER attachments which make the Maintainer a bulldozer, highway mower, berm leveler, road planer, snow-plow, broom or patch roller.

Get the details on this versatile 6,000-lb., 42½ H.P. machine from your nearest HUBER Distributor.

HUBER MANUFACTURING CO. • Marion, Ohio, U. S. A.
Manufacturers of Huber Maintainers, Graders and Complete Line of Rollers

HUBER

(Continued from page 82)

Inwood Constr. Co., Trinity Universal Bldg., Dallas, Tex. CA Est. **$550,000.** Department STORE, ALEXANDRIA, LA. Haas Investment Co., c/o contractor.

Winchester Bros., 5900 S. Front St., New Orleans, La. CA Est. **$300,000.** CHURCH, NEW ORLEANS, LA. Oak Park Presbyterian Church, c/o contractor.

† **Sheet Metal Fabricating Co.,** Kankakee, Ill. LB **$658,963.** general contract utilities SHOPS, DINING HALL bldg. addns., alterations, Veterans Admin. Hospital, LEXINGTON, KY. Veterans Admin., Munitions Bldg., Wash., D. C. Bids Nov. 18. CD 11/3.

▲ **Crawford Corp.,** 2019 N.E. Third St., Baton Rouge, La. Owner Builds. **$6,000,000.** 1,000 RESIDENCES, LOUISVILLE, KY.

▲ **J. A. Jones Constr. Co.,** 209 W. 4 St., Charlotte, N.C. CA **$1,214,500.** ADMINISTRATION and STUDENT UNION BLDGS., OWENSBORO, KY. Kentucky Wesleyan College, Owensboro, Ky. Bids Nov. 18, awarded Nov. 20.

MIDDLE WEST

BIDS ASKED—BUILDINGS

Mich., Adrian—SCHOOL—B.A. 12/10—Bd. Educ. Madison School Dist., 2 story, brick, steel Madison Rural School addn., Treat Rd. $300,000. Plans deposit $20, refundable, Francis A. Faulhaber, 128 E. Maumee St., archt. CD 8/29.

▲ **Mich., East Lansing**—DORMITORY—B.A. 12/11—State, A. N. Langius, dir. State Bldg. Dpt., Lansing, brick, steel, concrete dormitory incl. food service bldg. and 3 bldgs., Michigan State College, Michigan Ave. and Harrison Rd. $7,500,000. Extended date. Ralph R. Calder, 1212 Kales Bldg., Detroit, archt. Snyder & McLean, 2214 Penobscot Bldg., Detroit, engrs. CD 10/31.

Ill., Alton—HOUSING—B.A. 12/17—Madison County Housing Auth., D. F. Braner, exec. dir., 3 and Haller Sts., East Alton. Proj. Ill. 15-4, incl. 58 two story bldgs., 115 dwelling units, 17 one story buildings, 34 dwelling units and 1 story management and maintenance bldg. Friedman, Alschuler & Sincere and Ernest A. Grunsfeld Associated Architects and Engineers, 223 W. Jackson Blvd. Chicago, 6, Ill., archts. CD 3/27/51.

Mich., Marquette — HOSPITAL — Bids Asked — Morgan Heights Sanatorium, Dr. James R. Acockes, supt., brick, masonry tuberculosis hospital addn., alterations. $350,000. Plans deposit $50, refundable, Harry W. Gjelsteen, 212 First St., Menominee, archt. CD 1/28/52.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ **OHIO**—State Hy. Dpt., State Office Bldg., Columbus, **The Baker & Hickey Co.,** P.O. Box 5008-Tri-Village Station, Columbus, O., CA. **$1,649,240,** est. $1,593,000, Type T-50 on B-71 and structures 0.711 mi. SR 46-(3.35)-3.65), S.R. 169 (2.14-2.74), U-UG-635 (4), U-1098 (1), City of Niles, Proj. No. 323, Trumbull Co. Bids Nov. 14. CD 11/19, under LB.

National Constr. Co., 23500 Lakeland Blvd., Euclid, O., CA. **$776,940,** est. $600,000. storm relief sewer in Lloyd Rd. from Lake Erie south to county line, 10-ft. brick in tunnel, EUCLID, O. City, City Hall, 585 E. 222 St., Euclid, O. Bids Oct. 13, awarded Nov. 12. CD 10/27 under LB.

WISCONSIN—State Hy. Comn., Madison, Wis.

La Crosse Dredging Corp., 310 S. Michigan Ave. Chicago, Ill., LB, **$229,224,** Contract 3, structures, The Old U.S.H. 4-S.T.H. 23 (Sonn and Boland Subways) Road, U.S. Hy. 41, Proj. FG 03-1 (31) (32) Fond du Lac Co; LB, **$146,487,** Contract 2, structures, The Old U.S.H. 41-S.T.H. 23 (Corum Subway) Road, Proj. FG 03-1 (30) U.S. Hy. 41, Fond du Lac Co. Bids Nov. 18. CD 10/31.

▲ **WISCONSIN**—State Hy. Comn., Madison,

Phillip C. Kaiser, Portage, Wis., LB, **$96,267** Contract 1, grading, draining 5.561 mi. U.S.H. 51-C.T.H. "B" Rd., S.T. Hy 22, S 0294 (4), Columbia Co.;

John F. Bloomer Co., Appleton, Wis., LB, **$249,018** Contract 1, base course 1.583 mi. USH 41-Appleton Road (College Ave. Extension) S. Hy. 125, Proj. S 0730 (1) and SG 0730 (3) and T 0730 (1), Outagamie Co.;

H. Turner & Son, Boscobel, Wis., LB, **$198,062,** Contract 1 grading, draining 2.051 mi. Ellsworth-Durand Rd., U.S. Hy. 10, Proj. F 019-1 (32), Pierce Co.

I. H. Pertzsch, N. 2 St., Onalaska, Wis., LB, $149,354 Contract 1, c. conc. 0.712 mi. La Crosse-Holmen Rd., U.S. Hy. 53, U 5101 (7), La Crosse Co.;

Murphy Constr. Co., Black Creek, Wis., LB, **$168,832** Contract 1, b. conc. surf. Seymour-East County Line and West County Line-Green Bay Rd., S.T. Hy. 54, Proj. 038-2 (18) and (20), Outagamie and Brown Counties;

Jay W. Craig Co., 1814 N. E. California St., Minneapolis, Minn., LB, **$166,272,** Contract 1, single aggregate bit. 13.25 mi. West County Line-Bloomer Rd., S.T. Hy. 40, Proj. T 058 (3), Chippewa Co.;

Mathy Constr. Co., 508 Hoeschler Bldg., La Crosse, Wis., LB, **$125,100,** Contract 3, single aggregate bit. 8.006 mi. The U.S.H. 63-East County Line and West County Line-Connorsville Rd., Proj. T 059 (5), (3), S.T. Hy. 64 St. Croix and Dunn Counties;

Rein & Schultz, 119 E. Washington Ave., Madison, Wis., LB, **$126,564,** Contract 1, single aggregate bit. 6.966 mi. Hager City-U.S.H. 10 Road, U.S. Hy. 63 Proj. F 028-1 (35), Pierce Co. Bids Nov. 18 CD 10/31.

G. H. Sargent Co., West Branch, Mich. CA Est. **$200,000.** sewage treatment plant, interceptor sewers, force

"DUMPCRETES WERE A NATURAL FOR THE FORT KNOX HOUSING PROJECT"
says S. D. Zenor, New Albany (Ind.), concrete sub-contractor
Butler plant with 2-yd CMC Mixer set up 2 miles from job

"32,000 yards is a lot of concrete," says Mr. Zenor, "especially when you make your pours in close quarters."

"We liked our four Dumpcretes for these tight spots, because they are light and easy-to-maneuver. With the high discharge and long chute we placed concrete direct . . . for foundations, porches, steps, sidewalks and parking areas. They were fast, too, and maintenance was nil."

Algernon Blair and Fort Knox Construction were contractors on the 1500-unit projects.

Dumpcretes charge fast, travel fast and place fast. Get the facts today.

MAXON DUMPCRETE

Fastest from plant to pour

Manufacturing Division
MAXON CONSTRUCTION CO., INC.
631 Talbott Bldg., Dayton 2, Ohio

Please send the following

☐ "Dumpcrete High-production Method"

☐ "12 Ways to Set Up for Central Mixing"

Name_____
Firm_____
Street_____
City_____ State_____

WELDING CONNECTORS

Saxe Welding Connection Units position and secure structural parts to be welded.

Clip K3A permits an adjustable connection.

These widely used units eliminate all hole punching and, with welding, produce the most economical, safe and quickly erected structural frame.

Write for 1951 edition, Structural Welding Practice Manual.

J. H. WILLIAMS & CO.
Buffalo 7, New York
Air Reduction Canada, Ltd. Montreal 2, Canada

GUNITE
PNEUMATICALLY PLACED CONCRETE
DENSE · DURABLE · HIGH STRENGTH
for
Restoring Disintegrated Concrete
Dam, Dock and Bridge Repairs
Steel Encasement and Fireproofing
Sewer, Water Pipe and Penstock Linings
Stack and Bunker Linings
Wood Pile Casings—Pressure Grouting
Prestressed Tanks and Silos

Get in touch with us for engineering data and estimates

GUNITE CONSTRUCTION CORPORATION
420 LEXINGTON AVE., NEW YORK 17, N.Y.
MURRAY HILL 3-7699

soil sampling made easy!



Acker Soil Sampling Kit gives you accurate sub-surface information *Quickly— Easily— Inexpensively*

Write today for prices and bulletin 26 ENR

ACKER DRILL CO., INC., SCRANTON 3, PA.

Over 30 years of experience in the manufacture and development of drilling equipment

Send For This New Water Filtration Data



BULLETIN B-12 on general filtration principles; BULLETIN B-12-W details information on filtering potable and waste water.

DICALITE DIVISION

GREAT LAKES CARBON CORPORATION

612 S. Flower St., Los Angeles 17, Calif.

WET JOBS

Whether it's

HEAVY CONSTRUCTION



BUILDINGS



SEWERAGE

or any other type of wet work

For "quick-dry" . . . specify . . .

GRIFFIN

WELLPOINT CORP.

881 East 141st Street, New York 54, N. Y.
Hammond, Ind. Houston, Tex. Jacksonville, Fla.

In Canada: Construction Equipment Co., Ltd.
Toronto Montreal Halifax

main, pump station, ELK RAPIDS, MICH. Village, Elk Rapids, Mich. Bids Oct. 6. CD 9/24.

BUILDINGS

LOW BIDS AND CONTRACTS

▲† **George Sheaf & Co.**, 449 Neilston St., Columbus 3, O., CA. $1,048,856, 2 WAREHOUSES and washracks, Lima Ordnance Depot, Serial No. ENG 46-022-53-6, LIMA, O. U.S. Eng., 237 Fourth Ave., Huntington 18, W. Va. Bids Oct. 3. CD 9/10.

Kaiser-Ducett Co., 80 E. Jackson Blvd., Chicago 4, Ill. CA. $400,000. FACTORY, CO2 and dry ice, URBANA, O. Liquid Carbonic Co., 31st and Kedzie Sts., Chicago, Ill. Awarded Nov. 12.

Harvey A. Hanson, 1851 Elston Ave., Chicago, 14, Ill., CA, $300,000 Saugonash SCHOOL, CHICAGO, ILL. Bd. Educ., 228 N. LaSalle St., Chicago, Ill. Bids Oct. 24. CD 10/17.

Mercury Builders, 5412 W. North Ave., Chicago, 39, Ill., CA, $414,371, 2 story, brick Abraham Lincoln SCHOOL CICERO, ILL. School District 99, 5110 W. 24 St., Cicero, Ill. Awarded Nov. 14. CD 10/2, under LB.

Erik A. Borg Co., 6649 N. Ridge Ave., Chicago, Ill., LB, $306,700, 3 story, bsmnt., 45x170 ft. GIRLS DORMITORY, RIVER FRONT, ILL. Concordia Teachers College 7400 Augusta Blvd., River Front, Ill. Perkins & Will, 309 Jackson Blvd., Chicago, Zone 6, archts. CD 11/13.

▲ **Darin & Armstrong, Inc.**, 2041 Fenkel St., Detroit, Mich. CA Est. $5,000,000. 1 story, 450,000 sq. ft. mfg. hydraulic steering gears, PLANT and 100x750 ft. MAIN BLDG., M-46 and Towerline Rd., SAGINAW, MICH. Saginaw Steering Gear Div., General Motors Corp., 628 N. Hamilton St., Saginaw, Mich. Bids Nov. 3. CD 10/21.

WEST OF MISSISSIPPI

BIDS ASKED—HEAVY CONSTRUCTION

▲ **Tex., Anahuac**—B.A. 12/25—Trinity Bay Conservation Dist., Anahuac, Cont. 48D02, imprv. 9.08 mi. Spindletop Bayou, Jefferson Co., involving 2,162,000 cu. yd. ditch excav., $575,000; Cont. 48D03, rein.-con. pier on treated timber pile, $75,000; Contr. D48D04, imprv. 13.67 mi. Spingle Top Bayou in Chambers and Jefferson Counties, 1,377,000 cu. yd. dragline ditch excav., $382,000. Plans deposit $15. Freese, Nichols & Turner, 2111 C & I Bldg., Houston, engrs. Extended date. CD 11/6.

Tex., Houston—TELEVISION STATION—Bids Asked—University of Houston, 3801 Cullen Blvd., and Houston Independent School Dist., 1600 Washington St., television station. $225,000. CD 8/28.

BIDS ASKED—BUILDINGS

Mo., St. Louis—HOSPITAL—B.A. 12/10—Barnard Free Skin & Cancer Hospital, John R. Shepley, pres., 3427 Washington Ave., Zone 3, 4 story, ground floor, 45x128 ft., brick, rein.-con., 40-bed cancer hospital, Barnes Hospital Group vicinity of Kingshighway and Euclid Ave. Russell, Mulligardt, Schwartz & Van Haefen, 1620 Chemical Bldg., 721 Olive St., Zone 1, archts. Brussel & Viterbo, Arcade Bldg., 812 Olive St., Zone 1, engrs. CD 10/14.

N. D. Williston—COURT HOUSE—B.A. 12/11—Williams Co., Williston, court house, $600,000. W. F. Kurke & Assoc., 1117 13 Ave. N., Fargo, archts. CD 8/28.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ **Dravo Corp.**, Dravo Bldg., Pittsburgh, Pa. CA. Est. $1,000,000. 887 ft. dock in Mississippi River adjacent to plant, consisting of 8 barge-mooring piers each 20 ft. in diam., ST. LOUIS, MO. Great Lakes Carbon Corp., 526 E. Catalan St., St. Louis 11, Mo.

† **Rorick Constr. Co.**, 905 S. 20 St., Omaha, Neb. CA. $850,184. WAF dormitories, mess and admin. bldg. at Offutt Air Force Base, Inv. 25-066-53-130, FORT CROOK, NEB. U. S. Eng., 1709 Jackson St., Omaha, Neb. Bids Nov 13. CD 11/18, under LB.

KANSAS—State Hy. Comm., Wichita.

Stannard Constr. Co., 428 N. Rock Island St., Wichita, Kan. CA. $239,168. c. conc. 1.585 mi. Proj. AD-2 (1), Part I, Sedgwick Co. Bids Nov. 13. CD 11/5.

▲ **Southwestern Bell Telephone Co.**, Auditorium Circle, San Antonio, Tex., Own Forces. Approx. $2,500,000. 153 mi. underground coaxial cable line from San Antonio to Corpus Christi for telephone and TV reception, TEXAS. CD 11/09.

† **Cage Bros.**, Rte. 10, Box 46, San Antonio, Tex. CA $593,246, addnl. embankment slope protection, Dam "B," Inv. No. CIVENG 41-443-53-10, TEXAS. U. S. Eng., 100 W. Vickery St., Fort Worth, Tex. Bids Oct. 24. CD 10/29 under LB.

† **Worth Constr. Co.**, Box 531, Fort Worth, Tex. CA. $506,291, maintenance apron, Carswell Air Force Base, ENG 41-443-53-14, FORT WORTH, TEX. U. S. Eng., 100 W. Vickery St., Fort Worth, Tex. Bids Oct. 21. CD 10/29 under LB.

† **Edward Morgan & Jones Gillis**, Box 4327, Fondren Station, Jackson, Miss., CA. $618,225, runway extens., $203,513, parking apron, Gray Air Force Base, Inv. No. Eng 41-443-53-18, KILLEEN, TEX. U. S. Eng., 100 W. Vickery St., Fort Worth, Tex. Bid Nov. 7. CD 11/12 under LB.

▲ **Continental Pipe Line Co.**, subsidiary of Continental Oil Co., W. L. Kyger, pres., Ponca City, Okla. Owner Builds. $5,000,000. 600 mi. oil pipe line from Billings, Mont. to Spokane, Wash., MONTANA-IDAHO-WASHINGTON. CD 11/7.

▲† **Lease & Leigland**, 1501 N. 35 St., Seattle 3, Wash. CA $1,664,700, est. $1,592,241. dormitories,

(Continued on page 88)



To this old factory . . .



they simply did this . . .



to get this . . .

Fenestra acoustical-structural panel ceiling changes old factory into modern office . . . OVERNIGHT!

Out of a sow's ear . . . !

A big Michigan concern needed office space in a hurry and the only available building was an old one-story factory.

Steel beams (the bottom chords of the roof trusses) ran clear across the building . . . every 20 feet.

So they simply laid 20-foot Fenestra* Acoustical-Structural Steel Panels side by side, from one beam to the next. Quickly, inexpensively, the long, strong panels interlocked into a flat, handsome acoustical ceiling . . . and acted as a load-carrying storage floor for ducts, air conditioning, electrical services and such.

While they were doing all this, the company employees went right on working below. Using the first few panels laid as a storage and working platform the installation crew stayed up above. And, of course, there was neither dirt nor dust to shower down below.

They can clean their Fenestra acoustical ceiling with soap and water, or paint it without hurting its acoustical efficiency. And, of course this acoustical ceiling is noncombustible.

Cost?

Less than $1.25 per square foot . . . installed!

If you would like to know more, write to the Detroit Steel Products Company, Department ER-12, 2286 East Grand Boulevard, Detroit 11, Michigan. Also ask about the other money-savers you see illustrated below. *®

Fenestra METAL BUILDING PANELS

. . . engineered to cut the waste out of building



Acoustical "D" Panels for roofs, floors, ceilings. Width 16". Depth 1½" to 7½".



"C" Insulated Wall Panels. Width 16". Depth is 3". Steel or aluminum.



Acoustical Holorib for acoustical-structural roof. Width 18". Depth 1½".



Acoustical "AD" Panels for ceiling-silencer-roof. Width 16". Depth up to 7½".

CONTINENTAL



Builds for Defense

MANUFACTURE OF ENGINES for the use of our Armed Forces is a major phase of Continental Motors' operations, of course. Yet it by no means sums up the company's activities with a bearing on the national well-being, for Continental is also a major source of power for hundreds of civilian jobs vital to our economic strength . . . You find it in leading makes of specialized equipment in construction and industry, and on highway and farm. You find it also in the air. In fact, the majority of all utility planes serving industry and business today—speeding executive travel and getting more things done—fly with dependable, time-proven Continental power.

ESTABLISHED SERVICE FROM COAST TO COAST

Continental Motors Corporation
MUSKEGON, MICHIGAN

(Continued from page 86)

mess-admin. bldg., Great Falls Air Force Base, Inv. 53-21, GREAT FALLS, MONT. U. S. Eng., 4735 E. Marginal Way, Seattle 4, Wash. CD 10/21, under LB.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **A. H. Neumann & Bros.**, 514 Hubbell Bldg., Des Moines, Ia., LB, $3,339,000, general contract;

Allen Plumbing & Heating Co., 623 6 St., Des Moines, Ia., LB, $328,250, plumbing and heating for Veterans Memorial AUDITORIUM, DES MOINES, IA. City, City Hall, Des Moines, Ia. Bids Nov. 6. CD 9/19.

▲ **Jones-Hettelsater Constr. Co.**, 1911 Baltimore St., Kansas City, Mo. and **Davey & Moen**, Mason City, Ia., CA, $1,000,000. three feed mixing PLANT bldgs. MASON CITY, IA. Allied Mills, Bd. of Trade Bldg., Chicago, Ill.

▲ **Lippert Bros.**, 2800 N. Santa Fe St., Oklahoma City 5, Okla., LB $1,143,343. Negro HIGH SCHOOL, 10 and Eastern Sts., OKLAHOMA CITY, OKLA. Bd. Educ., 400 N. Walnut St., Oklahoma City, Okla. Bids Nov. 18. CD 10/28.

▲ **Carpenter Bros.**, 1335 Plowman St., Dallas, Tex., CA $1,305,000. Item 1, structures of test LABORATORIES BLDG., DALLAS, TEX. Chance Vought, Div. of United Aircraft Corp., Box 5907, Dallas, Tex. Bids Nov. 7, awarded Nov. 17. CD 11/19, under LB.

Brace & Carruth, 706 Garden Oaks St., Houston, Tex. Owner Builds. $450,000. Unit 1, SHOPPING CENTER off N. Shepherd and W. 11 Sts., HOUSTON, TEX. CD 10/21.

Schneider Constr. Co., Box 13157, Houston, Tex. LB $379,424. CHURCH, HOUSTON, TEX. River Oaks Baptist Church Congregation, c/o Hamilton Brown, archt., 2019 W. Gray St., Houston, Tex. Bids Nov. 17. CD 11/19, under LB.

† **J. A. Sharrock**, Box 268, Marshall, Tex. CA, $980,000, construct Facilities "A", Plant No. 2, Longhorn ORDNANCE WORKS, Inv. No. Eng 34-066-53-54, MARSHALL, TEX. U. S. Eng., Box 61, Tulsa 2, Okla. Bids Nov. 13. CD 11/10.

Ross Smith & Assoc., Mesquite, Tex., Owner Builds. $370,000. 37 DWELLINGS, MESQUITE, TEX. CD 9/17.

J. B. Andrews & Assoc., Mesquite, Tex., Own Forces. Approx. $340,000. 40 DWELLINGS, MESQUITE, TEX. CD 9/17.

Bd. Educ., Riverton, Wyo., rejected bids Oct. 8, Ashgrove Elementary SCHOOL, RIVERTON, WYO. Will re-advertise.

† **Campbell & Kay**, Box 4091, Station A, Albuquerque, N. M. LB $963,833, est. $950,000. BUILDING 880 addn., Inv. No. 293-53-18, ALBUQUERQUE, N. M. U. S. Atomic Energy Comn., Box 5900, Albuquerque, N. M. Bids Nov. 14. CD 10/14.

FAR WEST

BIDS ASKED—HEAVY CONSTRUCTION

† **Calif., Travis Air Force Base**—SHOPS—B.A. 12/12—U. S. Eng., Wright Bldg., Sacramento, squadron shops, ENG 53-34, Spec. 1689.

† **Calif., Travis Air Force base**—HEADQUARTERS—B.A. 12/17—U. S. Eng., Wright Bldg., Sacramento, air base group headquarters, Spec. 1679.

† **Washington**—B.A. 12/30—Bureau Reclamation, Dpt. Interior, Ephrata, Wash., earthwork, pipe lines and structures for Area P-8 laterals, sublaterals and wasteways, Potholes East Canal Laterals, Columbia Basin Proj., west of Eltopia, Spec. DC 3845; adv. ENR 12/4.

Calif., Bakersfield—Bids Asked—City, 2101 "H" St., sanitary sewers in Planz Rd., $141,943. Extended date. R. E. White, 1716 Oak St., engr.

BIDS ASKED—BUILDINGS

Calif., Stockton—SCHOOL—B.A. 12/9—Stockton City Unified School Dist., 324 N. San Joaquin St. Grover Cleveland Elementary School. Plans deposit $50. Victor Galbraith, 312 Exchange Bldg., archt. CD 6/14/51.

Ore., Portland—SCHOOL—B.A. 12/10—School Dist. 1, 631 N. E. Clackamas St., 8-room rein.-con. addn. to Highland School, Roald, Schmeer & Harrington, Portland Trust Bldg., archts.

Calif., Sonoma—SCHOOL—B.A. 12/17—Sonoma Valley Union High School Dist., Sonoma, Sonoma Valley Union High School addn. Plans deposit $25. John Lyon Reid, 1069 Market St., San Francisco, archt. CD 10/29/51.

Calif., Miranda—SCHOOL—B.A. 1/7—Southern Humboldt Unified School Dist., Miranda, school site development, sewers, $500,000. Ernest Frederick Winkler, Harold M. Hansen, 251 Post St., San Francisco, archts. CD 8/21.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

† **U. S. Eng.**, 4735 Marginal Way, Seattle 4, Wash. received no bids Nov. 5, 2 battery-charging motor-generator sets for Ableni Falls Dam, Newport, Inv. 53-28, IDAHO. CD 10/14.

▲† **Utah Constr. Co.**, 144 E. Broadway, Salt Lake City, Utah, LB $2,486,613, est. $3,202,207, constr. 3.3 mi. Gateway Tunnel, 9 ft. diam., concrete lined, Weber Basin Proj., UTAH. Bureaun Reclamation, Dpt. Interior, Ogden, Utah. Bids Nov. 13. CD 10/17.

† **Anderson Constr. Co.**, Route 1, Box 210—A, Vancouver, Wash., LB, $257,600, 36 raceways ponds, 2 holding ponds Carson Fish Station, Skamania Co., WASHINGTON U. S. Fish & Wildlife Service, Swan Island, Portland, Ore. Bids Nov. 17. CD 11/6.

(Continued on page 91)

HERE'S YOUR PROOF OF . . . .

DRAVO *Counterflo* HEATER VERSATILITY!

get these FREE case studies now!

Detailed information and photographs show how heaters can be adapted for temporary heating . . . or how large open spaces in commercial, industrial or educational buildings can be comfortably, easily and quickly heated with Dravo Heaters. These case studies give you proof of Dravo Heater versatility, and they're yours for the asking.

DRAVO HEATERS OFFER YOU:

LOW INITIAL COST—Users report 30% to 60% savings over "wet-type" systems.

EASY INSTALLATION—Need only fuel, exhaust and electrical connections . . . no ductwork.

LOW OPERATING COST—Direct-fired . . . burn gas or oil . . . readily converted . . . minimum efficiency 80%.

AUTOMATIC OPERATION—On-off or modulating controls . . . no constant attention needed.

LONG SERVICE LIFE, LOW MAINTENANCE—Stainless steel combustion chamber eliminates refractory lining.

SAFETY—Approved by American Gas Association, listed by Underwriters' Laboratories, Inc.; Dravo standardized safety control circuit accepted by Factory Mutual Engineering Division.

MOBILITY—Can be moved to any location.

FLEXIBILITY—When floor space is limited, can be wall-hung or suspended from trusses in any position.

DRAVO HEATERS SOLVE HEATING PROBLEMS IN THESE INSTALLATIONS, TOO:

- **TEMPERING MAKE-UP AIR**—where removal of noxious fumes makes comfort heating normally difficult.
- **PROCESS DRYING AND HEAT CURING**—where moisture content must be controlled or removed from air, and temperature regulated to meet production needs.
- **HEATING AND VENTILATING STORES, SCHOOLS AND AUDITORIUMS**—where quick, automatically controlled, low-cost heating is desired.

FOR FREE CASE STUDIES OF INTEREST TO YOU

MAIL THIS COUPON TODAY . . .

(Case Study sheets are 8½" x 11", punched for binder or convenient filing.)

HEATING DEPARTMENT, DRAVO CORPORATION
Dravo Building, Fifth and Liberty Avenues
Pittsburgh 22, Pa.

Please send me the following case studies FREE:

- ☐ Process drying and heat curing
- ☐ Temporary heating
- ☐ Space heating large buildings
- ☐ Stores, schools and auditoriums
- ☐ Tempering make-up air
- ☐ Please have a representative call.

Name _____ Title _____

Company _____

Address _____

City _____ Zone _____ State _____

When writing ask for Bulletin DE-523-1

DRAVO
CORPORATION

PITTSBURGH • ATLANTA • BOSTON • CHICAGO • CINCINNATI
CLEVELAND • DETROIT • NEW YORK • ST. LOUIS • PHILADELPHIA
WASHINGTON

Sales Representatives in Principal Cities

Manufactured and sold in Canada by Marine Industries, Ltd., Sorel, Quebec. Export Associates: Lynch, Wilde & Co., Washington 9, D.C.



. . . it's the *tight* RING-TITE JOINT used with TRANSITE SEWER PIPE

HERE'S HOW THE RING-TITE JOINT WORKS:



◀ **Start of assembly.** Two rubber rings and a Transite sleeve (cut away to show position of the rings) are placed on one of the two pipe ends to be joined.



▶ **Final position.** Sleeve centered over both pipe ends, with the rubber rings tightly compressed between sleeve and pipe.



◀ **Checking joint** for proper assembly. This is done with a simple gauge immediately after the joint is made . . . *before backfilling.*

*Transite is a registered Johns-Manville trade mark

NOT ONLY IS IT POSSIBLE to assemble the new Ring-Tite Coupling in a fraction of the time required for making ordinary sewer pipe joints—but, with the use of a simple feeler gauge, you can check this joint for proper assembly as soon as it is made, *and backfill immediately!*

This "packaged" joint—furnished with Transite* Pipe and ready for assembly—has still other important practical advantages. Not only are there fewer joints to make due to long thirteen-foot lengths, but time is saved also by eliminating the use of poured compounds. Just a simple assembly operation with a mechanical coupling puller, and the Ring-Tite Joint is ready for service.

Its tightness means less infiltration in the sewerage system and this effects savings in treatment costs. Transite's high-flow capacity (Manning's n = .010) often results in substantial installation savings by permitting flatter grades and shallower trenches—an important economy where pipe is laid at or below the ground water table or in rock excavation.

For further data about this corrosion-resistant asbestos-cement pipe and how it can save money for you, write for Folder TR-103A. Address your inquiry to Johns-Manville, Box 60, New York 16, N. Y.

JOHNS MANVILLE JM PRODUCTS

Johns-Manville TRANSITE SEWER PIPE

(Continued from page 88)

▲† **Morrison-Knudsen, Macco Corp. & Peter Kiewit Sons Co.,** Box 450, Boise, Idaho, CA. $2,987,374 power house, Lookout Point Dam, Lane Co., Civeng 35-026-53-20, OREGON. U. S. Eng., Pittock Block, Portland, Ore., Bids Oct. 15, awarded Nov. 18, under LB.

† **OREGON**—Bureau P. Rds., Dpt. Commerce, Morgan Bldg., Portland,

Peter Kiewit Sons Co., Longview, Wash., CA. $241,463, constr. 7.4 mi. Thomas Creek Rd., Fremont Forest, Lake Co. Awarded Nov. 18.

▲† **Cascade Constructors,** Box 774, Pasco, Wash., LB, $3,270,925, installing equipment at McNary Dam, Schedules A and D, Inv. 53-17, OREGON. U. S. Eng., City-County Airport, Walla Walla, Wash. Bids Oct. 20. CD 10/24, under LB.

† **Morrison-Knudsen Co., Inc.,** 411 W. Fifth St., Los Angeles, Calif., LB, $288,600, riprap upstream slope at Mormon Island Dam, Spec. 1701, Folsom, CALIFORNIA, U. S. Eng., Wright Bldg., Sacramento, Calif. Bids Nov. 13. CD 10/17.

Guy F. Atkinson Co., Box 259, Long Beach, Calif., LB, $223,500, est. $227,000, Santa Cruz By-Pass Bridge demolish Ocean Blvd. Bridge, LONG BEACH, CALIF. Long Beach Harbor Dept., 1333 El Embarkadero, Long Beach, Calif. Bids Nov. 13. CD 11/5.

A. Teichert & Son, Inc., 1931 Stockton Blvd., Sacramento, Calif. LB $505,338, East Storm Water Separation Project, SACRAMENTO, CALIF. City Hall, Sacramento, Calif. Bids Nov. 13. CD 10/30.

† **Erickson & Campbell,** 800 R St., Sacramento, Calif., LB, $209,213 "K" system trainer bldg., human relations and resources center, Mather Air Force Base, Spec. 1646, SACRAMENTO, CALIF. U. S. Eng., Wright Bldg., Sacramento, Calif. Bids Nov. 14. CD 10/17.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **Robert E. McKee, Inc.,** 4700 San Fernando Rd., Los Angeles, Calif., LB, $2,307,700, general contract;

A. S. Schulman Electric Co., 641 Imperial St., Los Angeles, Calif., LB, $582,324, electrical work;

E. Willardson, Inc., 2880 Rowena Ave., Los Angeles, Calif., LB, $339,000, plumbing work, for 8 story, rein.-con. communicable diseases unit GENERAL HOSPITAL, LOS ANGELES, CALIF. Los Angeles Co., Hall of Records, Los Angeles, Calif. Bids Nov. 13. CD 10/9.

▲ **Bechtel Corp.,** 3750 Wilshire Blvd., Los Angeles, 5, Calif., CA, $10,000,000, thermofor catalytic reformer at refinery, TORRENCE, CALIF. General Petroleum Corp. (affiliated Socony-Vacuum Oil Co., Inc.), 612 S. Flower St., Los Angeles, 17, Calif.

T. A. Stanfield, 986 E. Base Line, San Bernardino, Calif., LB, $862,963, rein.-con., stucco, frame HIGH SCHOOL VICTORVILLE, CALIF. Victor Valley Union High School Dist., Victorville, Calif. Bids Nov. 12. CD 10/22.

CANADA

BIDS ASKED—HEAVY CONSTRUCTION

Que., Lac des Loups (Postal Dist., Mont Laurier)—STAFF DWELLINGS—B.A. 12/8—F. T. Collins, Dpt. Transport, Ottawa, Ont. staff dwellings, garage power house and related work at airport. Plans deposit $25.

Que., Howick—B.A. 12/13—Municipality, water system, $115,000. Y. Verzina, Ormstown, Que., engr. CD 10/2.

Ont., Toronto—Bids Asked—Don Mills Development Co., c/o John Layng, archt., 170 Bloor St. W., sewage disposal, plant for housing. King, Coons, Phelan & Porter, 8 Bedford Rd., engrs.

SOON LETS CONTRACT—BUILDINGS

Ont., Mount Dennis—WAREHOUSE—Canadian Admiral Corp., Ltd., 501 Lakeshore Rd., Port Credit, soon lets contract 1 and 2 story, 25,000 sq. ft. steel, concrete block, brick warehouse, Jane St. $100,000. N. A. Armstrong, 19 Melinda St., Toronto, archt.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

Winnipeg Supply & Fuel Co. Ltd., Boyd Bldg., Winnipeg, Man., CA, $728,669, air navigation school at Royal Canadian Air Force Base, WINNIPEG, MAN. Defence Constr. Ltd., Kensington Bldg., Winnipeg, Man. Awarded Oct. 31. CD 9/24.

Standard Paving Ltd., Harbor Commission Bldg., Toronto, Ont., CA, $261,282, exten., roads and services incl. storm sewer, conduit for steam heating, electric, grading and excavation Canadian Army Ordnance Depot, LONG BRANCH, ONT. Defence Constr. Ltd., 40 Eglinton Ave. E., Toronto, Ont. Bids July 3, awarded Oct. 31. CD 6/18.

BUILDINGS

LOW BIDS AND CONTRACTS

E. R. Tremblay Co., Inc., 39 Goulburn Ave., Ottawa, Ont., CA, $393,000, 50 concrete, brick DWELLINGS, Prestland Rd., OTTAWA, ONT. Ottawa Lowren Housing Ltd., 95 Echo Dr., Ottawa, Ont. Bids Oct. 29. CD 10/20.

▲ **Barnett McQueen Co., Ltd.,** 460 Christian St., Fort William, Ont., CA, $1,233,000, two pavilions and connecting passages for Ontario HOSPITAL, PORT ARTHUR, ONT. Dpt. P. Wks., Parliament Bldg.,

For Many Digging Jobs, *Only* the Sherman *Power* Digger is Practical

Get the most out of the excavating equipment you already own or rent by keeping it on your big volume jobs.

For miscellaneous excavating and trenching jobs the Sherman Power Digger is *fully capable* and *far less expensive to operate*. You can buy Digger and Tractor complete for less than many automobiles cost.

The Sherman Power Digger is the answer where giant digging equipment and manual labor are both uneconomical. It reaches 8 feet below ground surface and swings in an arc of 140° with a radius of 10 feet behind the tractor.

For complete information on how the Sherman will cut your digging costs, write today for free literature C36.

Efficient performance of the Sherman Power Digger is assured by positive hydraulic action and patented actuated bucket.

The Sherman Power Digger is attached to a lightweight, rubber-tired tractor giving unmatched maneuverability and transportability.

Designed, Engineered and Manufactured Jointly by
SHERMAN PRODUCTS, Inc.
Royal Oak, Michigan
WAIN-ROY CORP.
Hubbardston, Mass.

Patent No. 2,303,825.
Other patents pending.

Sherman
PRODUCTS, INC.
ROYAL OAK, MICHIGAN

25 YEARS EXPERIENCE
for SATISFACTION
Foundation
WELLPOINT SYSTEMS
RENTAL • SALES
SEND FOR LITERATURE
Foundation Equipment
CORPORATION
Long Island City 1, N. Y. 38th Ave. & 10th St. EXeter 2-1100
Chicago, Illinois 2608 W. 111th St. Hilltop 5-8282

Full power behind both drills with Jaeger air-plus pressure

75 ft.
125 ft.
185 ft.
250 ft.
365 ft.
600 ft.

By using a "new standard" Jaeger 365 compressor instead of a 315 on this by-pass bridge approach at Shelton, Connecticut, Mariani Construction Co. was able to hold a 4" wagon drill at top efficiency, averaging 300' per day in shale, *and operate a hand-held drill at the same time.* All Jaeger sizes offer like advantages—more air per dollar, more production per hour.

THE JAEGER MACHINE COMPANY **200 Dublin Avenue Columbus 16, Ohio**

PUMPS • MIXERS • TRUCK MIXERS • PAVING SPREADERS and FINISHERS

TIMBERLOCK

Split-Ring

TIMBER CONNECTORS

Timberlock Split Rings comply with all Government specifications as to manufacture and material. Their excellent quality, favorable price, prompt service and acceptability have been proven by their satisfactory use in many projects under the jurisdiction of the Army, Navy, Maritime Commission, Defense Plant Corporation and various other governmental agencies.

Write for prices and delivery, Dept. ER-2.

THE MARSH COMPANY
HASTINGS, NEBRASKA

HOTTEST and CLEANEST

- GREATEST RADIANT HEAT
- LESS CLEANING THAN ANY OTHER SALAMANDER
- NO WICKS, JETS, VALVES OR PRESSURES
- EXCLUSIVE EXTINGUISHING DAMPER
- IDEAL FOR INDOOR OR OUTDOOR USE



Get complete HY-LO FACTS NOW!

Patent No. 2284157

HY-LO
Oil-burning Salamander

SCHEU PRODUCTS COMPANY
274 STOWELL STREET • UPLAND, CALIF.

Toronto, Ont. Bids Oct. 21, awarded Nov. 18. CD 9/26.

L. B. Magil Co., Ltd., 5275 Queen Mary Rd., Montreal, Que. CA, $200,000, 2 story, bsmnt., 118x166 ft., rein.-con., brick FACTORY, Iberville St., MONTREAL, QUE. H. M. Steinberg, 4151 W. Sherbrooke St., Montreal, Que. Greenspoon & Assocs., 4151 W. Sherbrooke St., Montreal, Que., archts.

Proposed Projects

WATER SUPPLY

▲ Calif., Hayward—City, City Hall, voted bonds water system, $1,750,000.

Ga., Elderton—City, City Hall, WW imprvs., $400,000.

Ind., Gas City—City, Theodore Strichler, city engr., wells, equipment, installing 34,200 ft. new mains, iron removal plant and aeration process, rehabilitation of tank, new service meters, $250,000. Clyde E. Williams, 312 W. Colfax St., South Bend, consult. engr.

Minn., St. Paul Park—Village, W. J. Fastener, clk., defeated $390,000 bonds Nov. 4, water extensions. (Correction-status). CD 11/7.

▲ Va., Richmond—City, City Hall, 1953 WW imprvs. $1,107,000.

SEWERS, WASTE DISPOSAL

Calif., Hayward—City, City Hall, voted bonds sewerage system, $300,000.

▲ Calif., Santa Clara—City, City Hall, voted $1,900,000 bond sewerage system. CD 2/7.

Ind., Rochester—City, City Hall, remodeling sewage plant. Approx. $250,000. Clyde Williams Assoc., South Bend, consult. engrs.

Kan., Hays—City, voted $300,000 bonds Nov. 4, sewerage works imprvs., extens. Serwis & Van Doren, Crawford Bldg., Topeka, consult. engrs. CD 10/22.

Kan., Junction City—City, c/o V. A. Basgall & J. Russell Calde, voted $500,000 bonds Nov. 4, sewage disposal plant, $650,000, Wilson & Co., 223 N. Santa Fe St., Salina, consult. engrs. CD 10/3.

Kan., Parsons—City, voted $475,000 bonds Nov. 4, sewerage sys. expansion.

▲ Minn., Edina and Richfield—Village of Edina, B. Hawthorne, clk., and Village of Richfield, J. A. Klein, clk., (joint project), interceptors 12- to 54-in. joint sanitary sewerage sys. connecting with Minneapolis sewerage sys. $2,490,000. G. M. Orr Eng. Co., 1004 Marquette Ave., Minneapolis, consult. engr. CD 7/16/52, under Minn., Richfield.

▲ N. Y., West Seneca—Town, sewerage sys. and treatment plant. $3,800,000. CD 7/9/47.

Wis., Sheboygan—City, City Hall, storm sewers in Erie and Mead Aves. $245,000. R. E. Fleischer, c/o owner, engr. CD 2/6.

▲ B. C., Vancouver—Vancouver & Districts Joint Sewerage & Drainage Bd., Sun Bldg., sewerage project, $30,000,000. A. M. Rawn, Charles G. Hyde & John Oliver, city engr., c/o owner, are Bd. of Consulting Engineers. CD 11/14.

Ont., Barrie—Municipality, ratepayers to vote Dec. 8, sewage disposal plant. $510,000. R. Campbell, Town Hall, town engr. CD 7/23.

BRIDGES

▲ ALABAMA—State Hy. Dpt., Montgomery, Etowah Co.—bridge over Coosa River Gadsden, $2,000,000. Troy E. Watford & Assocs., Gadsden, consult. engrs. CD 2/9/50.

▲ Ill., Cicero—Town, 4936 25 Pl., bridge at Laramie Ave. (52 Ave.) over yard and main line R/W of Chicago, Burlington & Quincy R. R. $1,750,000. De Leuw Cather & Co., 150 N. Wacker Dr., Chicago 6, Ill., consult. engrs. CD 1/3/50.

▲ La., Covington—St. Tammany and Jefferson Parishes Police Jury, Court House, causeway across Lake Pontchartrain, Gretna. $40,000,000. Palmer & Baker, Inc., Staples Pake Bldg., Mobile, Ala., consult. engr. CD 9-26/51.

▲ MASSACHUSETTS—Commonwealth of Mass., Metropolitan Dist. Comn., Parks Div., 20 Somerset St., Boston,

Somerville—Squires Bridge, $1,000,000. Duffill Assoc., 80 Boylston St., Boston, consult. engrs. CD 4/18/52.

UTAH—State Road Comn., State Capitol, Salt Lake City,

Salt Lake Co.—constr. Becks Hot Springs overpass for North-South Freeway through West Salt Lake City. $500,000. E. G. Johnson, c/o owner, state road engr.

Va., Norfolk—State Hy. Dpt., Richmond, underpass Norfolk & Western Ry. at Brambleton Ave. $750,000.

▲ Wis., Kenosha—City, City Hall, underpass on 30 Ave. $2,000,000. Consoer, Townsend & Assocs., 451 E. Ohio Ave., Chicago, Ill., consult. engrs.

STREETS AND ROADS

Ill., Park Ridge—City, 102 N. West Highway, street rehabilitation program. $600,000.

(Continued on page 95)

Tough jobs made easy

with Dressers

Every pipeline job has its tough spots. Maybe it's a complicated valve setting, or a gallery where space is cramped. Perhaps there's a steep grade or subsurface structures to be circumvented. From penstocks to filter galleries, wherever pipe is joined, Dresser Couplings simplify installation—pay *double* dividends when the going gets tough.

The versatility on the job of these factory-made joints eliminates such problems as exact pipe fitting, slight misalignment of pipe ends and expansion-contraction stresses. Dresser flexibility provides the give-and-take necessary to protect the piping in service, assuring low maintenance.

With Dresser Couplings, ordinary workmen can make bottle-tight joints every time—the only tool required is a wrench. Available in steel and CIP sizes from $\frac{3}{4}''$ to 72" and larger.

Make your next tough job easier with time-tested Dresser Couplings.



Construction time was cut from months to weeks by using Dresser Couplings on this 75" penstock in British Columbia. Penstocks remain bottle-tight despite high pressures and severe weather conditions.

Existing pipe networks often seriously complicate installation of new lines. Dressers supply the simplest, fastest way to get under or around underground obstacles. Line is completed easier, quicker.

This valve setting and tie-in was greatly simplified and stress on the valve body reduced by Dresser Couplings on *both* sides of the valve. Workmen installed Dressers quickly, even in this cramped space.

Air and water supply lines used in the construction of Brooklyn Battery Tunnel were connected with Dressers. Proved *dependable*, Dressers provided the fast, simple answer to this pipeline problem.

DRESSER®

COUPLINGS

Dresser Manufacturing Division,
319 Fisher Avenue, Bradford, Pennsylvania
(One of the Dresser Industries)

FREE ENGINEERING DATA

Mail this coupon for interesting and informative engineering data on diversified Dresser installations. It's file material that will be a big help next time you're designing a pipeline.



DRESSER MANUFACTURING DIVISION
319 Fisher Ave., Bradford, Pa.

Please send me your "Report of Dresser Coupled Lines", your "Bridge River" reprint, and copies of your Expansion Joint and Style 38 Catalogs.

Name_____
Title_____
Company_____
Street_____
City_____ Zone____ State_____

MANITOWOC

versatility pays off for MORRISON-KNUDSEN

it's a **DRAGLINE** with a 5½ yd. bucket and 140' boom relocating a railroad at Tomar, Wash.

On the C. J. Strike Dam, Grandview, Idaho, the versatility of the big 5 yd. Manitowoc 4500 is really paying dividends for Morrison-Knudsen Co., Inc.; like it is for other contractors throughout the nation. One of these husky Manitowocs is handling a variety of jobs — alternating from dragline, to crane, to concrete setting as the situations arise—handling each job quickly, efficiently, economically.

Relocating a railroad at Tomar, Washington called for dragline work for a second 4500; then came a quick switch to shovel for the next job and a fast move to Kemmerer, Wyoming.

Not only are these large excavators "quick change" artists, but they can be shifted from location to location almost as fast as the ordinary small shovel. Ships on standard flat cars or trailers — erection time 3-5 days.

A Manitowoc 4500 will cut your costs too, give you small machine mobility and versatility plus big, low cost capacity. Get complete details. Manitowoc Engineering Works, Manitowoc, Wisconsin.

then it's a **SHOVEL** with a 5 yd. dipper and 50' boom transported to Kemmerer, Wyoming.



now it's a **CRANE** along with another Model 4500, erecting steel, turbines and pouring concrete.

MANITOWOC

SHOVELS 1-5 YD. — Speed Crane — CRANES 18-100 TON

(Continued from page 92)

Ill., **Rantoul**—Village, Village Hall, street paving program of unpaved streets, bit. surf. $350,000. Tracy & Pitzen, Paxton, consult. engrs. CD 4/2/51.

O., **Cleveland**—City, City Hall, Zone 14, widen E. 9 St. 5 ft. on each side from Lakeside Ave. to St. Clair Ave. and from Prospect to Woodland Aves. $200,000. John C. Wenrick, c/o owner, city comr. of Engr. CD 11/7.

▲ **UTAH**—State Road Comn., State Capitol, Salt Lake City.

Iron Co.—imprvt. 3.9 mi. State Rd. between Paragonah and Orton. $120,000.

Salt Lake Co.—imprvt. Redwood Rd. between 33 and 78 South Sts. $400,000.

Salt Lake and Davis Counties—constr. industrial road from Beck's Crossing westerly to Redwood Rd. and north to Cudahy Lane. $200,000.

San Juan Co.—imprvt. State Rd. from Monticello to Blanding 11½ mi. $300,000.

Sanpete Co.—imprvt. 10.6 mi. State Rd. between Salina and Millard County line. $230,000.

Summit Co.—6-mi. realignment of U.S. 40 from Kimball's Junction to Summit County line. $800,000.

6-mi. imprvt. U.S. 30, between Echo Junction and Emory. $500,000.

imprvt. 3.5 mi. State Rd. in Chalk Creek Canyon. $200,000.

Uintah Co.—imprv. 22 mi. State Rd. from Bonanza to U.S. 40. $400,000.

Imprv. 13.3 mi. of State Rd. between Frisco and Wah Wah Mountains. $220,000.

Imprv. 6.2 mi. U.S. 91 between Hot Springs and Five Points. $500,000. E. G. Johnson, c/o owner, state road engr.

▲ **ONTARIO**—Dpt. Highways, Toronto, Ont. (Prov. Govt.), **Prescott**—rebuilding No. 2 Highway into 4-lane controlled access road for Johnston 2 mi. east of Prescott to Quebec border about 70 miles. $5,000,000.

EARTHWORK, WATERWAYS

▲† **Kansas**—Bureau Reclamation, Dpt. Interior, Bldg. 53, Denver Federal Center, Denver, Colo., 9,160 ft. crest, 97 ft. high Webster Dam and reservoir, on South Fork Solomon River near Webster, Rocks Co. $14,037,000. CD 5/25/44.

▲† **Tennessee**—U. S. Eng., 303 Federal Office Bldg., Nashville, Zone 1, furnish 4 main unit turbines with nominal rating of 32,000 hp. at 40 ft. head, adjustable blade propeller type, Approx. $2,000,000; furnishing 4 main unit generators with 25,555 kva. full power rating, vertical shaft type, $2,000,000; for Old Hickory Lock and Dam, Cumberland River, near Carthage. CD 5/1/51.

AIRPORTS

▲† **Ala., Montgomery**—BUILDINGS—U. S. Eng., P. O. Box 1169, Mobile, Zone 7, plans by Pearson, Tittle & Narrows, First National Bank Bldg., additional buildings at Gunter Air Force Base, $1,000,000.

▲ † **Tex., Ellington Air Force Base**—BUILDINGS—U. S. Eng., 606 Santa Fe Bldg., Galveston, dining halls, $350,000; 3 story training and administrative headquarters structures, $500,000; warehousing, $750,000; hangar, $[illegible],000; barracks, $1,750,000.

LATIN AMERICA

▲ **Brazil, Santos**—Port of Santos, Santos, plans hydroelectric plant expansion $10,000,000; warehousing and misc. constr. $4,000,000; modernization and enlargement of parts telephone services, $6,000,000; new docks, $5,500,000; new rail lines and shops, $12,000,000.

PUBLIC BUILDINGS

Ala., Bessemer—SCHOOL—City, City Hall, plans by Wilmot C. Douglas, 2922 7 Ave. Birmingham, Negro Elementary and Junior High School $750,000.

Calif., Bakersfield—CITY HALL—City, City Hall voted $950,000 bonds, city hall. CD 9/11.

▲ **Calif., Centerville**—HOSPITAL—Washington Township Hospital, Centerville, voted $1,250,000 bonds community hospital, Santos Rd., near here. Sorensen & Ellsworth, P. O. Box 1304, Carmel, archts. CD 8/20.

▲ **Calif., Corona**—SCHOOL—Corona Unified School Dist., Corona, defeated $1,532,062 bonds, schools. CD 9/4.

Calif., Riverside—JUVENILE HALL—Riverside Co., Court House, voted $774,000 bonds, Juvenile Hall, Milton H. Caughey, 9304 Santa Monica Blvd., Beverly Hills, archt. CD 11/26/51.

▲ **Calif., San Diego**—HALL OF JUSTICE—San Diego Co., Civil Center, defeated $10,000,000 bonds, Hall of Justice. CD 9/12.

▲ **Calif., San Francisco**—HOUSING—San Francisco Housing Auth., 440 Turk St., low-rent housing on Harbor Slope near Hunters Point. $1,800,000. CD 4/18/46.

Conn., Mansfield—SCHOOL—Town, Town Hall, plans by Russell F. Hills, 130 Washington St., brick, steel, concrete high school, $500,000.

Fla., Sanford—HOSPITAL—Seminole Co., voted bonds, hospital, $500,000.

Ind., Richmond—LIGHT PLANT—City of Richmond Electric Plant, new light plant, $750,000. Eral Beck, Richmond, plant mgr. CD 4/30/51.

The Central Maintenance Building, Division of Highways, State of California, was only recently constructed . . . using Alcoa Aluminum Building Sheet exclusively for roofing and siding. Contractor-Erector: Geo. D. Widman, Inc.

THE STATE ARCHITECTS SPECIFIED

ALCOA

BUILDING SHEET

DIVISION OF HIGHWAYS STATE OF CALIFORNIA

Big, tough, easy-to-handle units of Alcoa Industrial Building Sheet helped speed the construction of this highway maintenance building. With the installation of the last fastener, the job was complete . . . ready for occupancy. Typical of the low-cost, low-upkeep buildings made possible by aluminum.

Light weight Alcoa Industrial Building Sheet (only 56 pounds per square) reduces dead load. Goes up faster, requires no finishing . . . no painting.

Compare the advantages offered by aluminum with those of any other material. Next time *you* figure a building job, figure it in aluminum . . . Alcoa Aluminum Building Sheet.

FACTS FOR ENGINEERS

Alcoa Industrial Building Sheet may be erected over steel or wood; and there is a fastener for every type of job.

Lengths: 5 to 12 feet.

Widths: Roofing, 35 inches—Siding, 33⅓ inches (32-inch coverage).

Thickness: .032 inches—equal to 22 U. S. Gauge.

For complete engineering and application details, write for booklet AD-167.

ALUMINUM COMPANY OF AMERICA

806-M Gulf Building • Pittsburgh 19, Pa.

ALCOA

INDUSTRIAL BUILDING SHEET

Old Equipment Gets NEW Lease on Life

. . . Repowered with S-N Gear!

SO EFFICIENT — S-N Reduction Gears transmit *full* power, from engine to load smoothly, quietly . . . at the most economical speed for the driven equipment. They deliver more heavy duty power per gallon of fuel than any other method of speed-reducing. Savings for you!

SO RELIABLE — S-N quality materials and precision engineered workmanship are world-renowned for providing dependable power transmission.

SO RUGGED — S-N heavy duty, herringbone Reduction Gears are built for years of use.

SO COMPACT — Mounted on the engine, they conserve space.

SO VERSATILE — Reduction ratios of 1.5:1 up to 4:1; range . . . 50 to 900 H.P.

Designed for original installation and repowering of construction equipment like cranes, shovels, rock crushers, pumps, etc., requiring slower shaft speeds than engine speed. Application shown is 12-year-old gravel quarry power shovel repowered with Cummins 165 H. P. diesel engine and S-N 2255/3055 1.5:1 Reduction Gear.

For your future needs, employ S-N transmission experience. Specify S-N, one of the world's principal suppliers of quality reduction gears and power cut-off clutches for changing speed and increasing torque. WRITE TODAY.

The

SNOW-NABSTEDT

GEAR CORPORATION

transmission engineers for 46 years

211 Welton St., Hamden, Conn.

THE SNOW-NABSTEDT GEAR CORP. REVERSE & REDUCTION S-N GEARS HAMDEN, CONN., U.S.A.

Gears specifically designed for industrial use.

CUSTOM DESIGNED

FIELD OFFICE TRAILERS

SOLD OR RENTED

Our Field Office Trailers (now in use in more than 19 countries throughout the world) are DESIGNED and CONSTRUCTED for use under all conditions. They are NOT converted House Trailers, but Heavy Duty trailers designed especially for the job of Field Office Trailers. Send for FREE BOOKLET of cut-away scale drawings, specifications and prices.

INFORMATION ON RENTAL CHARGES UPON REQUEST.



American Trailer Co., Inc.

4030 WISCONSIN AVE., N. W., WASHINGTON, D. C.

Mobile Homes Headquarters in our Nation's Capital since 1936

▲ **Kan., Hutchinson**—SCHOOLS—School Dist. 2, Reno Co., voted $1,450,000 bonds Nov. 4, school, imprvs.

Kan., Salina—SCHOOL—School Dist. 1, Saline Co., voted $750,000 bonds Nov. 4, school addn. J. W. Radotinsky, 1401 Fairfax Trafficway, Kansas City, Kan., archt.

▲ **Kan., Topeka**—OFFICE—State, c/o Sen. Riley W. MacGregor, chn. Bldg. Comn., State House, plans by John A. Brown, state archt., State House, and Chas. L. Marshall, consult. archt., Topeka, state office, $7,000,000. CD 12/31/48.

▲ **Ky., Fort Knox**—ARMORED SCHOOL—U. S. Eng., 830 W. Broadway, Louisville, plans by Otis & Grimes, Tyler Bldg., Louisville, Zone 2, 79,250 sq. ft. permanent non-combustible armored school, incl. utilities, site development, roads, walks, $2,000,000. CD CD 7/28/52.

▲ **Ky., Fort Knox**—ARMORED SCHOOL—U. S. Eng., 830 W. Broadway, Louisville, plans by Otis & Grimes, Tyler Bldg., Louisville, Zone 2, 79,250 sq. ft. permanent non-combustible armored school, incl. utilities, site development, roads, walks, $2,000,000. CD 7/28/52.

† **Md., Fort George C. Mead**—POST TELEPHONE EXCHANGE—U. S. Eng., 24 St. and Maryland Ave., Baltimore, plans by Fenton & Lichtig, 2023 Maryland Ave., Baltimore, post telephone exchange, $500,000. CD 5/26/52.

▲ **Mich., Alma**—HOSPITAL—R. B. Smith Memorial Hospital, Bd. Trustees Alma, memorial hospital, Wright Ave. $1,125,000.

Minn., Crookston—SCHOOL—Bd. Educ., I. Swanson, clk., voted $550,000 bonds Nov. 4, 1 story, grade school, Toltz, King & Day, 2509 Pioneer Bldg., St. Paul, archts.

Miss., Jackson—ARMORY—State Bldg. Comn., Woolfolk State Office Bldg., armory for Mississippi National Guard. $800,000.

Miss., Jackson—OFFICE—State Bldg. Comn., Woolfolk State Office Bldg., plans by J. T. Liddle, Barnett-Madden Bldg., office for Miss. State Highway Patrol, $600,000.

▲ **Mo., Jefferson City**—SCHOOLS—Bd. Educ. plans by Marshall & Brown, 1016 Baltimore St., Kansas City 6, Mo., schools, $1,000,000. CD 10/8.

▲ **Mo., St. Louis**—SCHOOLS—Bd. Educ., V. Harry Rhodes, comr., School Bldg., 911 Locust St., elementary school for negroes, Euclid Ave. near Fountain Ave. $1,000,000; elementary school for negroes in DeSoto-Carr Dist., $1,125,000; Ames Elementary School, $1,125,000; Dumas School, $800,000; Patrick Henry School, $1,250,000. CD 6/23/52.

Neb., Lincoln—HIGH SCHOOL—Bd. Educ., 720 S. 22 St., Northeast High School, $650,000. CD 5/7/51.

▲ **O., Columbus**—HOUSING—Columbus Metropolitan Housing Auth., 425 W. Rich St., housing, $15,000,000.

▲ **O., Columbus**—HOUSING—Columbus Metropolitan Housing Auth., 425 W. Rich St., plans by Wm. F. Bretenbach, 2143 Fairfax Rd., 500 unit East Side Housing, Woodward, Woodland, and Brentnell Aves. $5,000,000.

▲ **Tenn., Chattanooga**—CIVIC CENTER—City, City Hall, civic center, $2,000,000.

Tenn., Chattanooga—HOSPITAL WING—City, City Hall, plans by Bianculli & Palm, 501 Cherry St., West Wing Addn. to Baroness Erlanger Hospital, $750,000. CD 5/9/49.

▲ **Tex., Amarillo**—SCHOOLS—Amarillo Independent School Dist., Amarillo Elementary Schools No. 1, $450,000; No. 2, $375,000; No. 3, $550,000; high school addn. and remodeling, $750,000; new classrooms, existing elementary schools, $700,000; misc. classrooms to some existing schools, $450,000; Junior-High School, $2,000,000; gymnasium, $350,000; heating plant, $225,000. CD 3/10.

▲ **Tex., Austin**—HOSPITAL—Bd. for Texas State Hospitals & Special Schools, 45 and Lamar Sts., plans by Jessen, Jessen, Millhouse & Greeven, 2816 N. Guadalupe St., 5 story concrete, masonry general hospital bldg., partially air-conditioned, $1,250,000. Wilson & Cottingham, Littlefield Bldg., Austin, and Zumwalt & Vinther, Mercantile Securities Bldg., Dallas, consult. engrs. CD 12/19/51.

▲ **Tex., Harlingen**—HOSPITAL—Bd. for Texas State Hospitals & Special Schools, 45 and Lamar Sts., Austin, plans by R. Newall Waters, Weslaco, 400-600 bed tuberculosis hospital, $2,500,000. Walter C. Moore, c/o owner engr. CD 9/23.

▲ **Tex., Houston**—WAREHOUSING—Port Comn., Navigation Dist., Wharf 13, cancelled bond election Dec. 13, warehousing, $1,600,000. CD 11/14.

▲ **Tex., Lufkin**—HIGH SCHOOL, etc.—Lufkin Independent School Dist., Lufkin, voted bonds Nov. 1, high school, $750,000, Wilbur Kent, 404 Perry Blvd., archt.; stadium addn., playgrounds, athletic courts, $125,000; Junior School addn., $325,000; shops and gymnasium, $300,000. CD 1/23/50.

▲ **Tex., Orange**—HOSPITAL—Orange Co., Orange, plans by J. M. Morris, Orange, 200-bed county hospital, $2,500,000. CD 4/26/51.

▲ **Tex., San Antonio**—HOSPITAL—Bd. for Texas State Hospitals & Special Schools, 45 and Lamar Sts., Austin, plans by Phelps & DeWees & Simmons, 2501-6 Majestic Bldg., 500-bed tuberculosis Hospital to be known as South Texas Tuberculosis Hospital, $2,500,000. Walter C. Moore, c/o owner, superv. archt. CD 9/23.

† **Va., Warrenton**—OFFICERS' QUARTERS—U. S. Eng., 1st and Douglas Sts., Wash., D. C., non-commissioned officers' quarters, Vint Hill Farms, $100,000-$500,000.

(Continued on page 99)

Speed demolition and reconstruction

There is a CP DEMOLITION TOOL for every type of work, ranging from the lightweight CP-111 (25 lb. class), for lateral or overhead jobs, to the heavy-hitting, smooth handling CP-117 (80 lb. class), for which no job is too tough.

The only "one-man gun" of its kind — cutting *one-inch* rivets — CP-11X BOYER RIVET BUSTER has quick-change retainer for chisels and backing-out punches. Powerful 11″ stroke. With chisel, it is 31″ long and weighs 35 lbs.

Heavy-duty CP-365 AIR IMPACT WRENCH saves time in removing nuts or bolting-up structural members — takes the hard work out of equipment maintenance. Capacity to 1¼″ bolt size.

Rugged CP HI-SPEED ELECTRIC SAWS have plenty of reserve power for hard jobs. Available in three sizes: 7½″, 8¼″ and 9½″ blades. Special blades can be furnished for cutting non-ferrous metal, or for ceramic or concrete products.

CHICAGO PNEUMATIC TOOL COMPANY

General Offices: 8 East 44th Street, New York 17, N. Y.

PNEUMATIC TOOLS • AIR COMPRESSORS • ELECTRIC TOOLS • DIESEL ENGINES
ROCK DRILLS • HYDRAULIC TOOLS • VACUUM PUMPS • AVIATION ACCESSORIES

CONCRETE MASONRY
is the Ideal Building Material for ANY Type of Structure



NOTE THE BEAUTY of Vibrapac block. Made in a variety of pleasing designs, textures and colors.

One of many Miami Beach hotels built with Vibrapac block.

Resists Wind and Weather... Frost and Fire Adds *Beauty* and *Permanence* at Low Cost



More and more churches are being built with Vibrapac block.



School building with interior and exterior exposed Vibrapac block.

In the full range of building construction, from a small unit to a multi-story skyscraper, you'll find that concrete masonry excels as a building material. It is armored against age, climate, fire, weather, termites, rodents, tornadoes, hurricanes and floods. The dry, sound-conditioned walls and floors promote good health and restful quiet. Owners of concrete masonry structures are assured of a low initial cost . . . minimum of upkeep . . . easier financing . . . and lower insurance rates. Get all the facts. Write today for literature and names of Vibrapac-equipped plants in your area.

BESSER MANUFACTURING CO.
ALPENA, MICHIGAN, U. S. A.

Made on a Vibrapac

All sizes of high-quality masonry units of any desired texture or density are made on a Besser Vibrapac, using one set of Plain Pallets. The Vibrapac is fully automatic. No machine operator is required.



BESSER

BATCH MIXERS | SKIP LOADERS | BLOCK & BRICK CUBERS | SUPER VIBRAPAC | SINTERING PLANTS | ACROW CENTERS | ROOF TILE MACHINE

(Continued from page 96)

▲ **Va., Williamsburg**—DINING HALL—State Hospital Bd., State Capitol, Richmond, dining hall at Eastern State Hospital. $1,020,000.

Wash., Moses Lake—HOSPITAL—Moses Lake Hospital Dist., Moses Lake, voted bonds, hospital, $620,000. H. A. Hovind, 1500 Westlake Ave. N., Seattle, and C. Martell, Fernwell Bldg., Spokane, archts. CD 10/13.

▲ **Wash., Yakima**—SCHOOL—School District 7, voted special levy, Junior High School, $1,000,000. J. W. Maloney & J. M. Whitney, Larson Bldg., archts. CD 9/5.

▲ **Ont., Barriefield**—HOSPITAL—Defence Constr. Ltd., 56 Lyon St., Ottawa, 4 story, 325-bed military hospital. $4,500,000.

▲ **Ont., Brantford**—HOUSING—Province of Ontario, Dpt. Planning & Development, Tonorto, housing in Echo Place Area, $1,500,000.

▲ **Ont., Toronto**—HOUSING—City, A. A. Lamport, mayor, City Hall, 624 apartment addn., in south section of Regent Park Housing Auth., with 6 story units. $5,000,000.

COMMERCIAL BUILDINGS

▲ **Ala., Birmingham**—COLLEGE BUILDINGS—Howard College, 7725 2 Ave. South, plans by Van Kuren, Davis & Co., 3004 7 Ave. S., college group of buildings. $8,000,000. CD 11/9/51.

▲ **Calif., Compton**—DWELLINGS—Phoenix Constr. Co., 642 S. Western Ave., Los Angeles, plans by L. C. Major & Assocs., 511 N. La Cienega Blvd., Los Angeles, 150 frame, stucco dwellings, Olive and Avalon Blvds. $1,000,000.

▲ **D. C., Wash.**—STORE, etc.—John McShain, Inc., 1501 N. Arlington Ridge Rd., Arlington, Va., plans by Edwin Weihe, 927 15 St. N. W., 12 story, brick, stone, concrete store and office bldg., 13 and Pennsylvania Ave. N. W., $1,500,000. Jacob Feld, 60 E. 23 St., New York, N. Y., consult. engr.

▲ **D. C., Wash.**—DEPARTMENT STORE—Sears, Roebuck & Co., W. Arthington and S. Homan Sts., Chicago, Ill., plans by Ballenger & Co., 121 N. Broad St., Philadelphia, Pa., department store, Alabama and Naylor Sts. $2,700,000.

▲ **Ga., Macon**—LAW SCHOOL—Mercer University, Macon, law school, $2,700,000. CD 6/20.

▲ **Ill., Hinsdale**—DIAL EXCHANGE—Illinois Bell Telephone Co., 212 W. Washington St., Chicago, Zone 6, plans by Holabird Root & Burgee, 180 N. Wabash St., Chicago, Zone 1, dial exchange bldg., $1,000,000.

Me., Millinocket—HOSPITAL—Millinocket Community Hospital, Main Ave., plans by Crowell, Lancaster Higgins, 6 State St., Bangor, 1 story, masonry hospital, $600,000. CD 2/20/52.

▲ **Mo., St. Louis County**—SCHOOL—The Principia Lower & Upper Schools, c/o trustees of Principia Corp., 5539 Page Blvd., St. Louis, Zone 12, plans by W. L. Risley, 220 S. Westmoreland Ave., Los Angeles, Calif., 8 school bldgs. on 388 acre tract on Mason Rd. between Clayton Rd. and Daniel Boone Hy., $5,000,000. CD 3/27/47.

▲ **Neb., Omaha**—HOSPITAL—Clarkson Hospital 26 St. and Dewey Ave., hospital addn., imprvs. $1,000,000.

▲ **N. M., Albuquerque**—HOTEL—Homer G. Maxey & Assoc., Lubbock, Tex., plans by Charles E. Armstrong, Majestic Bldg., Fort Worth, Tex., 5 story, 260-room rein.-con. hotel, with patio and parking space, Oak and Central Sts. $2,000,000.

Tenn., Chattanooga—CHURCH—Lookout Mountain Presbyterian Church, 316 N. Bragg Ave., Lookout Mountain, Chattanooga, church addn. $500,000.

▲ **Tex., Fort Sam Houston**—HOUSING—Federal Housing Admin., 610 S. Flores St., San Antonio, construct, manage, finance, 400 Wherry Housing Units, near Bel Mead Addn. across Military Hy. $3,000,000. CD 8/11/50.

Tex., Fort Worth—YOUTH—First Methodist Church Congregation, S and Florence Sts., plans by A. C. McAdams, Majestic Bldg., youth bldg. $500,000.

▲ **Tex., Houston**—CHURCH BLDGS., etc.—Our Lady of Mt. Carmel, 1111 Pierce St., plans by Golemon & Rolfe, 5100 Travis St., parish hall, $400,000; elementary school, $575,000; church, $400,000; dormitory, $550,000; co-educational high school, $1,000,000; electric lighting sys. $75,000. CD 11/11.

▲ **Va., Alexandria**—HOUSES—Colonial Investment Corp., 201 S. Washington St., 631 row houses, $6,000,000. E. S. Holland, Jr., 527 King St., consult. engr.

Wash., Seattle—HOUSES—Lovell Constr. Co., 12510 15 Ave. N.E., plans by R. L. Durham & Assocs., 100 Denny Way 45 houses in Will Rogers Addn. at 15 Ave. N.E. and E. 135 St. $500,000.

▲ **B. C., Vancouver**—DEPARTMENT STORE—Simpson-Sears, Ltd., 196 Yonge St., Toronto, Ont. retail department store in Burnaby Suburb, $4,000,000. CD 8/12.

▲ **Man., Winnipeg**—SHOPPING CENTER—Greater Winnipeg Shopping Centre Ltd., Winnipeg, Man., D. B. Landers, genl. mgr., Edmonton, Alta., plans by C. Callebaut, Brussels, Belgium, shopping centre, incl. 135 retail stores, 1500 seat auditorium, 3 apartment blocks, 75 room hotel, community bldgs., in Old Kildonan District, Winnipeg suburb, $18,000,000.

▲ **Man., Winnipeg**—HOMES—Great West Development Co., Winnipeg, plans by Green, Blankstein-Russell & Assocs., 222 Osborne St. N., 350 homes, St. James Area of Greater Winnipeg, $3,600,000.

▲ **Ont., Toronto**—APARTMENT BLOCK—International Realty Co., 190 Church St., plans by P. Caspari, 496



WISCONSIN-Powered
CLYDE STEEL DERRICK

Clyde Iron Works, Inc., Duluth, Minn., builds the Model-W3 Whirlette. Here are the job facts: Hook work cap. 10,000 lbs. at 10 ft. radius, 2,000 lbs. at 40 ft. radius; hoist line speeds, 50 to 160 f.p.m.; boom lengths, 20, 30 or 40 ft. Whirlette requires no guy wires or stiff legs and revolves through 360°.

* **Power for the Whirlette is a single-cylinder Model AHH 9.2 hp. Wisconsin Heavy-Duty Air-Cooled Engine.** A logical choice and an easy one. There's a Wisconsin for every job, every machine, 3 to 30 hp. You choose from 11 different models, all of which can be supplied as standard engines or with clutch assembly, clutch reduction and electric starting. 2-cylinder and 4-cylinder models can be supplied as complete power units.

Write today for the complete "Wisconsin story", giving you detailed descriptive and engineering information.



WISCONSIN MOTOR CORPORATION
World's Largest Builders of Heavy-Duty Air-Cooled Engines
MILWAUKEE 46, WISCONSIN

A 7338-1½-I

Unique Trailer Design Provides Spacious LIVING and OFFICE Quarters.....
DOES THE JOB OF TWO ORDINARY TRAILERS

Plenty of room for your field office—and for living, too!

LIGHTHOUSE DUPLEX

NO STATE PERMITS NEEDED

Reg. U S Pat Off

Unusual privacy! Two bedrooms upstairs, living room, kitchen (with breakfast nook) and complete bathroom downstairs. Yet overall height is only 11½ feet, 6 inches shorter than a commercial trailer. Equivalent to a 48-foot trailer home—yet only 28 feet in length. Maximum comfort in all temperatures from the tropics to the coldest regions. Write for name of your nearest dealer.



Lighthouse Trailer Company
LIGHTHOUSE — YOUR GUIDE TO BETTER LIVING
5747 WEST TOUHY AVE. • CHICAGO 31, ILLINOIS

DIG and HAUL... faster... cheaper



Picture shows how scraper cuts into hill and moves gravel to crusher

with a SAUERMAN DRAG SCRAPER

Movement of almost any kind of material can be accomplished economically with a Sauerman Scraper Machine. It is used to excavate sand, gravel, clay, etc., and deliver to hopper or pile—to clean out sludge basins and handle all kinds of viscous materials—for stockpiling coal, ore and other bulk materials. Wherever used it saves time, money and manpower.

One easily trained man controls the operation and takes care of the small amount of maintenance. Only a few parts come in contact with the material being worked, so wear is slight. Installation cost is low and power consumption, Diesel, gasoline or electric, is moderate.

Write for interesting 24-page Catalog.

CRESCENT Scraper Buckets
⅓ to 15 cu. yd.

The streamlined Crescent bottomless scraper bucket is an important feature of Sauerman machines. Light in weight, but powerful in its digging action, it moves heaping loads with minimum line-pull. Made in several different designs for handling different classes of materials.

SAUERMAN BROS., Inc.
532 SOUTH CLINTON ST., CHICAGO 7, ILLINOIS

Cableway and Scraper Specialists Since 1909

Maximum Joint Filling WITH Servicised SELF-EXPANDING CORK

- Recovers 50% Beyond Original Thickness After Compression
- Fully Compressible
- Non-extruding, Resilient

Ideal for large concrete structures or masses where substantial initial contraction is anticipated before any considerable amount of expansion takes place. 50% expansion beyond original thickness after compression keeps joint space filled, regardless of concrete movement. Made in ½" to 1" thicknesses; 2" to 12" (Standard) widths; also made in 24" and 36" widths on special order.

Write for Catalog and Complete details on Servicised Joint Fillers and Sealers.

SERVICISED PRODUCTS CORP.
6051 W. 65TH ST. • CHICAGO 38, ILL.

EFFICIENCY PLUS PROTECTION with KINNEAR Steel Rolling Doors

Repel
RIOTERS, TRESPASSERS, FIRE, RAIN, SNOW, etc. . .

Safeguard all doorway entrances against harmful elements. For complete protection against fire specify "AKBAR" fire doors made to rigid specifications and approved by Underwriters' Laboratories, Inc. Fire insurance rates have been reduced up to ⅓ after the installation of "AKBAR" Firedoors. Write today for complete details.

The KINNEAR Manufacturing Company
1820-40 Fields Ave., Columbus 16, Ohio
1742 Yosemite Ave., San Francisco 24, Calif.
Offices and Agents in Principal Cities

SAVING WAYS WITH DOORWAYS
KINNEAR ROLLING DOORS

Church St., concrete, steel, brick, stone apartment block, Alexander and Church Sts. $5,000,000.

▲ Sask., Regina—HOUSING—Cairns Constr. Co., 2136 Queen St., Regina, housing in Lakeview subdivision. Approx. $1,000,000.

INDUSTRIAL BUILDINGS

▲ Ga., Atlanta—WAREHOUSES—Atlantic Coast Line R. R. Co., R. L. Groover, ch. engr., Wilmington, N. C., warehouses, $5,000,000.

▲ Ga., Savannah—WAREHOUSE—Georgia Refrigerated Warehouses, c/o Robert & Co. Assocs., archts., 96 Poplar St. N.W., Atlanta, cold storage warehouse $1,200,000.

▲ Ind., New Albany—SUB-STATION—Public Service Corp. of Indiana, Inc., 1000 Main St., Plainfield, sub-station, $1,500,000. Sargent & Lundy, 140 S. Dearborn St., Chicago, 3, Ill., consult. engrs.

Kan., Kansas City—PLANT—Swift & Co., 4115 S. Packers St., Chicago, Ill., branch meat packing plant addn. $590,000. J. P. McShane, c/o owner, gen. super. engr.

▲ Mo., Kansas City—PLANT, etc.—Hall Bros., c/o Joyce C. Hall, pres., 25 and Grand Sts., plans by Welton, Becket & Assoc., 1114 Grand Ave., plant and office for Hallmark Cards, on 7+a acre tract south 25, McGee to Locust Sts., bridge to present plant 25 acres. $6,000,000.

▲ O., Columbus—PLANTS—Kanna Paint Mfg. Co., 95 W. Long St., 1 and 3 story brick, concrete, steel plants, 100,000 sq. ft. floor space. $1,000,000.

O., Rocky River—SUB-STATION—Cleveland Electric Illuminating Co., Public Square, Cleveland, Zone 1, electric power sub-station, 20550 Center Ridge Rd. $500,000.

▲ Ore., The Dalles—PLANT—Harvey Machine Co., Inc., 19200 S. Western Ave., Torrance, Calif., Defence Production Admin. Authority sought for aluminum reduction plant. $45,000,000. Lawrence Harvey, c/o owner, engr.

▲ Tex., Dallas—GENERATOR PLANT—Dallas Power & Light Co., Dallas Power & Light Bldg., 165,000 kw. turbine generator plant unit, Mountain Creek area. $16,100,000.

▲ Tex., Orange—PLANT—Allied Chemical & Dye Corp., Orange, addnl. chemical plant units. $16,500,000.

▲ Va., Hopewell—PLANT—Allied Chemical & Dye Corp., (Nitrogen Div.), 61 Broadway, New York, N. Y., synthetic fibre plant. Company has option on site near here at confluence James and Appomattox Rivers. $23,000,000.

UNCLASSIFIED

Ark., Little Rock—TELEVISION STATION—Great Plains Television Properties, c/o U. S. Corp. of Illinois, 33 North La Salle St., Chicago, 2, Ill., television station, $247,000. Jansky & Bailey, National Press Bldg., Wash., D. C., consult. engrs.

Ark., Little Rock—TELEVISION STATION—Little Rock Telecasters, P.O. Box 420, Wichita Falls, Kan., television station, $211,500. William L. Foss, Inc., 927 15 St. N.W., Wash., D. C., consult. engr. CD 10/8.

Calif., Richmond—OFF STREET PARKING SITE—City, City Hall, voted $500,000 bonds, off street parking site. CD 9/10.

Calif., San Diego—TELEVISION STATION—Charles E. Salik (KCBQ), P.O. Box 1629, Hotel Manor, Zone 12, television station, $496,000. Robert M. Silliman, 1011 New Hampshire Ave., Wash., D. C., consult. engr.

Calif., San Jose—TELEVISION STATION—San Jose Television Broadcasting Co., P.O. Box 995, San Jose television station, $640,000. E. C. Page, Bond Bldg., Wash., D. C., consult. engrs.

Fla., Jacksonville—BASEBALL STADIUM—City, City Hall, baseball stadium, $950,000. CD 1/22/45.

Fla., Jacksonville — TELEVISION STATION — Florida-Georgia Television Co., 1746 E. Adams St., television station, $645,000. Weldon & Carr, 1405 Connecticut Ave. N.W., Wash., D. C., consult. engrs.

† Md., Aberdeen Proving Ground—AIRFIELD IMPRVS. —U. S. Eng., 24 St. and Maryland Ave., Baltimore, airfield improvs., etcters. $3,000,000. Whiteside, Foster, Damon & Deane, Inc., Pennsylvania R.R. Bldg., Wilmington, Del., engr.

Miss., Jackson — TELEVISION STATION — Mississippi Publishers Assoc., P.O. Box 427, television station, $404,000. Raymond M. Wilmotte, 1469 Church St. N.W., Wash., D. C., consult. engr.

Neb., Hastings—TELEVISION STATION—Strand Amusement Co., Strand Theatre Bldg., television station, $257,000. Vandivere Cohen & Wearn, 1420 New York Ave. N.W., Wash., D. C., consult. engr.

N. C., Raleigh—TELEVISION STATION—Sir Walter Television & Broadcasting Co., 204 W. 6 St., Erie, Pa., television station, $296,000. William L. Foss, Inc., 927 15 St., N. W. Wash., D. C., consult. engr.

O., Warren—TELEVISION STATION—The Warren Tribune Radio Station, Inc., (WHHH), 108 Main St., television station, $484,000. John Creutz, Bond Bldg., Wash., D. C., consult. engr.

Okla., Altus—ELECTRIC DISTRIBUTION SYSTEM—City, voted bonds Nov. 11, rebuilding electric distr. sys. $390,000. CD 10/14.

(Continued on page 103)



Right Now... More than Ever

YOU NEED A

HOMELITE

Carryable GENERATOR

There's always a real need . . . a good use . . . for a Homelite Carryable Generator. But right now . . . with the shorter days and longer nights . . . a Homelite is all the more useful. Because in addition to using it for operating electric tools you can also use it for brilliant floodlighting.

Light and carryable, a Homelite is quickly put into action any time and any place you need floodlighting. And you can easily regulate your floodlighting to cover both large or small areas according to your needs.

Dependable in operation under all kinds of weather and operating conditions, a Homelite needs no manual attention after starting.

It's the simplest, surest, most flexible, most practical means for providing power for floodlighting.

Write for our complete generator bulletin.

Manufacturers of Homelite Carryable Pumps • Generators Blowers • Chain Saws

PERFORMANCE · DEPENDABILITY · SERVICE

HOMELITE

CORPORATION

1112 RIVERDALE AVENUE • PORT CHESTER, N. Y.

For Watertight Walls in..... **DISPOSAL and FILTRATION PLANTS, RESERVOIRS, FLOOD WALLS, DAMS**



Use

SUPERIOR

Water-Seal COIL OR SNAP TIES



The form tie used for water tight walls must, of course, be leak proof. The type of tie which is truly leak proof is determined by the anticipated height of head, and the resultant pressure.

Superior Snap Ties, and standard and Cone-fast Coil Ties, give satisfactory results for low heads, but for high heads, the use of Superior Water Seal Ties provide a real and justifiable insurance against leakage.

Superior Water Seal Snap Ties, and Coil Ties, both standard and Cone-fast, are provided with a water stop in the form of a securely fixed washer near the middle of the tie as illustrated. This washer effectively breaks the continuity of the rods, preventing seepage along the tie.

On any forming job, use SUPERIOR Concrete Accessories and be assured of the best in material, design and workmanship . . . plus the services of our experienced engineers who are always available to help plan your form work.

SUPERIOR CONCRETE ACCESSORIES, INC.

4110 Wrightwood Avenue, Chicago 39, Illinois

New York Office
1775 Broadway, New York 19, N. Y.

Pacific Coast Plant
2100 Williams St., San Leandro, Calif.

(Continued from page 100)

Okla., Tulsa—TELEVISION STATION—All-Oklahoma Broadcasting Co., (KRMG), 311 S. Denver Ave., television station. $719,000. McIntosh & Inglis, Wyatt Bldg., Wash., D. C., consult. engrs.

Ore., Portland—TELEVISION STATION—Mount Hood Radio & Television Broadcasting Corp. (KOIN), New Heatman Hotel television station. $666,000. E. C. Page, Bond Bldg., Wash., D. C., consult. engr.

Pa., Hazleton—TELEVISION STATION—Hazleton Broadcasting Co., (WAZL), 708 Hazleton Natl. Bank Bldg., television station, $227,000. James C. McNary, Natl. Press Bldg., Wash., D. C., consult. engr.

R. I., Providence—TELEVISION STATION—New England Television Co. of Rhode Island, 514 Industrial Trust Bldg., Zone 3, television station, $291,000. J. Gordon Keyworth, Williamstown, Mass., consult. engr.

▲ **Tennessee**—NATURAL GAS LINE—East Tennessee Natural Gas Co., Kingston Pike, Knoxville, 100 mi. 16 in. natural gas lines, Knoxville to Bristol. $5,800,000.

Tenn., Chattanooga—TELEVISION STATION—Tom Potter, 1032 Life of America Bldg., Dallas, Tex., television station, $313,000. John H. Mullaney, 1757 K St., N.W., Wash., D. C., consult. engr.

Tenn., Knoxville—TELEVISION STATION—W. R. Tuley, 208 S. E. Riverside Dr., Evansville 8, Ind., television station, $235,000. Harold B. Rothrock, Redford, Ind. consult. engr.

Tenn., Knoxville—TELEVISION STATION—WKGN, Inc., Park Natl. Bank Bldg., television station, $414,000. Millard M. Garrison, 1519 Connecticut Ave. N.W., Wash., D. C., consult. engr.

Tenn., Nashville—TELEVISION STATION—Life & Casualty Insurance Co. of Tenn. (WLAC), 159 Fourth Ave. N., television station, $781,000. A. Earl Cullum, Jr., 4710 Lemmon Ave., Dallas, Tex., consult. engr.

▲ **Texas**—OIL PIPE LINE—Texas Gulf Pipe Line Co., Abilene, crude oil pipe line, Abilene area, $750,000; Blum area, $425,000; Trinity area, $486,000. 12/4/52.

Tex., Austin—TELEVISION STATION—Tom Potter, 1032 Life of America Bldg., Dallas, television station, $732,000. E. C. Page, Bond Bldg., Wash., D. C., consult. engr.

Tex., Beaumont—TELEVISION STATION—Tom Potter, 1032 Life of America Bldg., Dallas, television station, $300,000. E. C. Page, Bond Bldg., Wash., D. C., consult. engr.

Tex., Corpus Christi—TELEVISION STATION—H. L. Hunt, 4009 Lawther Dr., Dallas, television station, $254,000. Weldon & Carr, 1605 Connecticut Ave. N.W., Wash., D. C., consult. engrs.

Tex., Corpus Christi—TELEVISION STATION—Superior Television Co., 2727 Agnes St., television station, $496,000. George P. Adair, 1833 M St., Wash., D. C., consult. engr.

Tex., El Paso—TELEVISION STATION—Franklin Broadcasting Co., 14410 Valley Vista Dr., Sherman Oaks, Calif., television station, $247,000. Bernard Assoc., 5010 W. Sunset St., Los Angeles, Calif., consult. engrs.

▲ **Tex., Houston**—WHARVES, etc.—Port Comm., Navigation Dist., Wharf 13, cancelled bond election Dec. 13, constr. Wharf No. 1, $1,000,000; Wharf No. 2, $1,250,000; Wharf No. 3, $750,000; Wharf No. 4, $875,000; Wharf No. 5, $1,100,000; Wharf No. 6, $950,000; Wharf No. 7, $1,175,000; railway storage yards, $970,000; lighting sys. $75,000; gas lines, $65,000. CD 11/14.

Tex., McAllen—TELEVISION STATION—Texas State Network, Inc., (KRIO), 1201 W. Lancaster Ave., Fort Worth, television station, $297,000. Commercial Radio Equipment Co., 1319 F St. N.W., Wash., D. C. consult. engrs.

Tex., Waco—TELEVISION STATION—Central Texas Television Co., c/o R. K. Prescott, Life of America Bldg., Dallas, television station, $225,000. Weldon & Carr, 1605 Connecticut Ave. N.W., Wash., D. C., consult. engrs.

Wash., Seattle—TELEVISION STATION—Mount Rainier Radio & Television Broadcasting Corp. (KJR), Skinner Bldg., television station, $645,000. E. C. Page, Bond Bldg., Wash., D. C., consult. engr.

W. Va., Charleston—TELEVISION STATION—Joe L. Smith, Jr., Inc. (WKNA) WJLS Bldg., Main and Kanawha Sts., Beckley, television station, $326,000. A. D. Ring & Co., Munsey Bldg., Wash., D. C., consult. engrs.

Wis., Madison—TELEVISION STATION—Monona Broadcasting Co. (WKOW), 215 W. Wilmington Ave., Madison, Zone 3, television station, $319,000. Walter F. Kean, 1 Riverside Rd., Riverside, Ill., consult. engr.

Wis., Milwaukee—TELEVISION STATION—Milwaukee Area Telecasting Corp., 411 E. Mason St., television station, $658,000. Waldon & Carr, 1e0 Connecticut Ave. N.W., Wash., D. C., consult. engrs.

Wyo., Cheyenne—TELEVISION STATION—Frontier Broadcasting Co. (KFBC) Plains Hotel, Cheyenne, television station, $238,000. Robert C. Plumenschmid, c/o owner, consult. engr.

▲ **B. C., Vancouver**—TELEVISION ANTENNA, etc.—Famous Players Canadian Corp., Ltd., Royal Bank Bldg., Toronto, Ont., community television antenna and coaxial cable sys. for coin telemeter television service, $10,000,000.

▲ **Que., Montreal**—SUBWAY SYSTEM—Montreal Transportation Comm., 159 W. Craig St., subway system. $65,000,000. De Leuw, Cather & Co., 150 N. Wacker Dr., Chicago, Ill., U.S.A., engrs. CD 12/1/43.

▲ **Ont., Sarnia**—PIERS, etc.—Dpt. P. Wks., Hunter, Bldg., Ottawa, 3 piers, combined length 4,850 ft. into Sarnia Bay from govt. docks each pier 300 ft. wide with railway spur to serve 12 large or 33 small ships, $15,000,000.

PROTECTION

WEBB

FLAMEFOIL-TREATED WEBB TARPAULINS

keep out water and . . . much more

Webb Flamefoil canvas coverings keep out fire . . . keep out weather damage where you store equipment . . . keep out mildew and dust from machinery and tools. They're made from top quality canvas of any weight. Hems are double-lock stitched. Heavy reinforcements at all points of abrasion and strain. Sturdy grommets provide bulldog grip.

You can have this economy and protection in a Webb Flamefoil-treated tarp of any size, any specifications for every protective use. Also available—windbreakers with plastic windows for winter weather operations. Write for information and prices.

WEBB MANUFACTURING COMPANY
2938 N. 4th St., Philadelphia 33, Pa.

"Gunite" . . . . . the sand-cement product of the "CEMENT GUN," for Concrete and Masonry Repairs, Pre-Stressed Tanks, Steel Encasement and for lining Reservoirs, Sewers and Tunnels.

CEMENT GUN COMPANY
"GUNITE" CONTRACTORS
GENERAL OFFICES—ALLENTOWN, PENNA., U.S.A.
MANUFACTURERS OF THE "CEMENT GUN"

EVERETT — Hewitt Avenue was built in 1923. Photos taken in 1924 and 1951.

LONGVIEW — Main St. was built in 1924. Photos were taken 1924, 1951.

TACOMA — S. 38th St. at Fawcett Avenue was built in 1924. Photos were taken 1924, 1951.

Here today — *and still here tomorrow*

that's the story of CONCRETE streets in western Washington

Motorists and taxpayers in western Washington can be well satisfied with the long service records of their concrete streets. Many of the old concrete pavements in this area have served dependably, economically for a quarter of a century or longer and are still good for many more years of ***low-annual-cost*** service.

Outstanding service records like these are typical of concrete streets from coast to coast. These streets go or serving today despite weights and volumes of traffic .ar in excess of those for which they were designed originally. They are proof that concrete streets are truly "here today—*and still here tomorrow!*"

Today concrete streets can be built even better because of improvements in engineering design, in materials and in construction methods. Concrete pavements have moderate first cost, low maintenance cost and long life. This results in ***low-annual-cost*** service that cannot be matched by any other paving material.

Examples shown here do not include Seattle, which has more square yards of concrete streets per capita than any large city in America, and which has many quarter-century streets.

PORTLAND CEMENT ASSOCIATION
33 West Grand Avenue, Chicago 10, Illinois
A national organization to improve and extend the uses of portland cement and concrete through scientific research and engineering field work

MATERIALS AND LABOR PRICES

Market quotations on construction materials and wage rates reported monthly by ENR correspondents
January Materials, and Labor Prices will appear in January 8, 1953 issue

CEMENT, AGGREGATE, READY-MIXED CONCRETE—F. O. B. CITY

	PORTLAND CEMENT* Per bbl. C/L lots cash. dis. not deducted			SAND AND GRAVEL Per ton, carload lots			CRUSHED STONE Per ton, carload lots		CRUSHED SLAG Per ton, carload lots, f.o.b. plant		CONCRETE BLOCK 8 x 8 x 16-in.: truckload del.: per block		CONCRETE Ready Mixed 1:2:4, over.
	Paper	Bulk	Mortar	Gravel, 1½ in.	Gravel, ¾ in.	Sand	1½ in.	¾ in.	1½ in.	¾ in.	Sand grav.	Lt. wgt. agg.	50 c.y., del.
Atlanta	$3.81	$3.50	3.30	$2.00	$2.00	$1.75	$2.10	$2.10	$1.65	$1.85	$0.19	$0.19	$11.95
Baltimore	3.76	3.45	3.38	2.50‡a	2.50‡a	2.00‡a	2.70‡a	2.80‡a	2.60‡a	2.55‡a	.17	.17a	10.80
Birmingham	3.11	2.81	....	2.24n	2.24n	1.94n	2.50	2.50	1.10	1.30	.165	.168	9.85
Boston	4.01	3.69	3.81	2.50a	2.50a	2.50a	1.50a	1.60a	....	....	.20	.22a	11.50h
Chicago	3.33	3.02	....	3.00‡b	3.00‡b	3.40‡b	3.00‡b	3.00‡b	2.00‡	2.00‡	.22	.22b	11.44/11.94
Cincinnati	3.31	3.40	3.40	2.00‡c	2.14‡c	2.14‡c	2.44‡e	2.44‡e	....	....	.21	.225a	11.45
Cleveland	N. A. in C. L.		....	2.05ef	1.85f	1.65	3.81a	3.81a	2.95‡	2.95‡	....	.23	12.40d
Dallas	2.95	2.65	2.70	2.18	2.28	1.84	2.22	2.38	....	....	.128e	.215	9.30
Denver	3.89	3.59	3.89	1.85	2.00	1.20	....	....	....	....	.22	.255a	10.50
Detroit	3.27	3.00	3.05	4.25‡b	4.25‡b	3.75‡b	4.25‡	4.25‡	4.25‡	4.25‡	.19	.20a	10.75f
Kansas City	3.30	3.03	3.15	1.85‡	1.85‡	1.50‡a	2.00‡a	2.00‡a	....	....	.18ag	.23e	11.60b
Los Angeles	4.00a	3.60a	4.72	1.95a	2.20a	1.95a	1.95a	2.08a	....	....	.125/m	.23m	10.43kh
Minneapolis	3.80d	3.49d	3.41	2.30‡ag	2.30‡ag	1.35‡ag	2.50‡ag	2.50‡ag	....	....	.21ek	....	12.15fk
Montreal	3.01ae	2.86ae	....	3.00	3.00	2.25	1.55ej	1.85ij	....	....	.20	.20a	9.65eh
New Orleans	3.20	3.02	3.18	2.32	2.32	1.82	....	....	1.05	1.25	.25	....	12.90
New York	3.86	3.55	3.43	2.35bk	2.35bk	1.60bk	2.50bl	2.50bl	....	....	....	....	11.80am
Philadelphia	3.43/3.82‡	3.12/3.49‡	3.43/3.48‡	2.75‡	2.75‡	2.15‡	2.10‡	2.15‡	1.75	1.65	.22/.25	....	11.50
Pittsburgh	3.32	3.04	3.32	2.15‡	2.15‡	2.10‡	2.60‡	2.60‡	2.15	2.15	.23d	.23d	12.50
St. Louis	3.27/3.48b	2.84/3.10b	3.05/3.22	2.90am	2.70am	2.30/2.70am	1.70j	1.70j	1.50	1.50	.215	.215ci	10.75
San Francisco	3.36	2.96	....	1.92	1.92	2.02	2.02	2.02	....	....	....	.23cl	10.70e
Seattle	3.75a	3.25a	4.50n	3.00‡bm	3.00‡bm	3.00‡bm	3.50‡bm	3.50‡bm	....	....	24j	.3325j	11.40f

‡Delivered. * Prices incl. dealers comm. except as noted.
CEMENT: a Subj. to 10¢ dis. b Less 2% for cash. c CL price dealers comm. not incl. d Dealers sell only LCL. h LCL.
SAND, GRAVEL, STONE & SLAG: a Truck lots. b Per cu. yd. c 5 tons or more. e ¼". f Pea gravel. g Less 5% for cash. h Less than 5 tons. i Sales tax incl. j F.o.b. quarry. k Barge lots asd. l F.o.b. scow Hudson river. m Less 2% for cash. n F.o.b. cars.
CONCRETE BLOCK: a Cinder. b Waylite. c Haydite. d Celocrete. e 5⅛ x 8 x 12 in. f 8 x 4 x 16. g F.o.b. truck at job. i Less 2% for cash. j Less 1% for cash. k 8x8x18. l F.o.b. plant San Rafael. m F.o.b. yard.
READY MIXED CONCRETE: a 5 cu. yds. or over del. Man. b 25 cu. yds. or more. c 10–100 cu. brackets. d 1–3 mi. zone. e 2,000 lb concr. f 2500 lb. comp. h Less 50¢ for cash. i 5% off for cash. j 2% off for cash. k Sales tax included. l 1:2½:4. m F.o.b. yard. n Plus escalator clause.

CASH DISCOUNTS CEMENT to Contractors: Truck delivery, 2% for cash on 10th of month: on carload deliveries, no trucking, same as dealer cash discount 10c. per bbl. for payment within 15 days of date of invoice. Subject discount 10c. per bbl. 20 days in Montreal.

CURRENT MAXIMUM PRICES AT CEMENT MILLS

Charge for bags not included. For paper bags add 30¢ per bbl., not refundable

	Bulk		Bulk		Bulk		Bulk
Richard City, Tenn.	$2.60†	Buffington, Ind.	$2.55†	Steelton, Minn.	$2.65†	Muskegon, Mich.	$2.70†	Toledo, O.	$2.60†
Clinchfield, Ga.	2.60†	Independence, Kan.	2.50†	Leeds, Ala.	2.45†	Saginaw, Mich.	2.60†	Milwaukee, Wis.	2.75†
Kingsport, Tenn.	2.60†	Hannibal, Mo.	2.55†	Duluth, Minn.	2.65†	Wyandotte, Mich.	2.60†	Green Bay, Wis.	2.75†
West Des Moines, Iowa	2.65†	Northampton, Pa.	2.60†	Hudson, N. Y.	2.60†	Buffalo, N. Y.	2.60†	Ironton, O.	2.60†
Nazareth, Pa.	2.60†	Universal, Pa.	2.65†	Alpena, Mich.	2.50†	Oswego, N. Y.	2.75†	Montreal City	2.61
Bath, Pa.	2.60†	Waco, Tex. (+ 10¢ tax)	2.50†	Detroit, Mich.	2.60†	Cleveland, O.	2.60†	W. Winfield, Pa.	2.65†

†*Prices to hold for fourth quarter of 1952.*

PAVING BRICK, BLOCK, ASPHALT, ROAD OILS—F. O. B. CITY

	PAVING BRICK AND BLOCK			PAVING ASPHALT Per ton, less than 80 penetration		ASPHALT BINDERS—FLUXES Per gal., 80–300 penetration		CUTBACK ASPHALT Per ton		ROAD OIL Per gal.	ASPHALT EMULSION (Quick-breaking) Per gal.	
	Granite Per M lots of 50,000 4x4x8 in.	Brick per M 3x4x8½ in. carload lots	Wood per sq. yd. 3½ in. 16-lb. treat	Tank car	Drums	Tank car	Drums	Tank car	Drums	Tank car	Tank car	Drums
Atlanta	$73.00	$35.00	$2.25	$26.00	$33.25	$0.1975	$0.339	$0.095w	$0.185w	$0.105	$0.115	$0.225
Baltimore	150.00‡	58.00‡	....	22.00i	.....	.0809i	0.15i	.09iw	.17iw	.09i	.09i	0.12i
Birmingham	.....	45.50i	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Boston	.....	.....	.....	24.50a	35.50a	22.00ax	35.50ax	.....	.....	.09a	.105a	.22a
Chicago	155.00‡	90.00‡b	4.40/4.60‡f	20.25b	30.25b	19.25bx	29.25bx	.0875bw	.16bw	.075b	.....	.....
Cincinnati	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Cleveland	200.00	55.00d	4.27g	23.00t	.....	23.00t	.....	.1025tw	.194w	.....	.1115t	.194
Dallas	e	40.00	e	24.05	43.09	.1016	.2103	27.09	47.87	.0980	.1041	.2128
Denver	.....	48.00	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Detroit	.....	92.00	.. ..	26.82	....	26.82v	.....	.117w	.....	.0925	.....	.2811v
Kansas City	e	e	e	16.50cl	...	.055	.....	.07vw	.....	.0585e	0.435	.....
Los Angeles	e	—.—	e	15.50dmz	...	15.50dnz	.....	17.00dz	.....	16.00dv	.0825f	.1725f
Minneapolis	.....	—.—	2.97h	25.07	....	24.07	.....	.0894w	.....	.0794	.0935	.....
Montreal	.....	e	e	27.10n	36.65n	.135n	.183n	16.30nu	18.80nu	.132n	.184ns	.225ns
New Orleans	.....	—.—	.....	17.50e	....o	17.50ev	.....o	.085ew	.....o	.085p	.085	.....
New York	.....	.....	3.12f	26.26q	47.59q	25.26st	46.58st	.1071w	.2021w	.1071	.1072	.1993
Philadelphia	175.00	110.00	4.06	22.00	.....	.....	.....	.095u	.....	.....	.....	.....
Pittsburgh	165.00	48.00	4.60	23.00	37.00	.10	.20	27.00	39.00	.095	.09r	.205
St. Louis	.....	.....	.....	18.68/	.....	.1698	.....	.0865 / .089w	.....	0.15	.0975	.....
San Francisco	.....	55.00e	.....	17.00g	32.50gp	17.10gkv	22.50gkv	19.00g	36.50g	17.50w	.085y	.....
Seattle	.....	.....	.....	17.00A	37.50A	16.25Av	.....	19.50A	...	18.50Aw	.095A	.105Ar

‡ Delivered.
PAVING BRICK & BLOCK: a CL. b 3½ x 4 x 8½. c 2½ x 8½ x 4. d LCL, truck deliveries. e Not used. f 2" interior 6¢ treat. g 3". h 8¢ treat. i 3 x 3⅝ x 8½.
ASPHALTS: a Price at plant, Everett, Mass. b F.o.b. refinery, Lockport, Ill. c F.o.b. Sugar Creek, Mo. d F.o.b. refinery, El Segunda. e F.o.b. Baton Rouge. f F.o.b. Wood River or Roxana, Ill. g F.o.b. Richmond, Calif. h F.o.b. Martinez. i F.o.b. refinery, Baltimore. j F.o.b. refinery, Inglewood, Calif. k 50–110 penetr. l Less than 100 penetr. m 40–80 penetr. n Tax incl. o Drums not avail. p Shipped in steel bbl. q 40–85 penetr. r In customer's drums. s Shipped in drums, per drum. t 85–300 penetr. u Per 100 gal. v Per ton. w Per gal. x Also tank trucks. y F.o.b. Oakland. z F.o.b. refinery, Cleveland. A F.o.b. Norco, La.

IRON AND STEEL PRODUCTS—PER 100 LBS. BASE MILL PRICES

	STRUCT SHAPES—	PLATE CARBON STEEL	REINF BARS billet	RIVETS ½-in. structural	SHEET PILING Base	STEEL RAILS Per Net Ton Standard	Light	Re-rolled	TRACK SUPPLIES Angle Bars	Std Spikes	Tie Plates	Track Bolts
Birmingham Area	$3.85	$3.90	$3.95	$7.85	....	$75.50	$85.00	Not	$4.925	$6.65	$4.775	....
Chicago Area	3.85	3.90	3.95	7.85	$4.675	75.50	85.00	avail-	4.925	6.65	4.775	....
Pittsburgh Area	3.85	3.90	3.95	7.85	4.675	75.50	85.00	able	4.925	6.65	4.775	$9.85
Buffalo Area	3.85	3.90	3.95	7.75	4.675	75.50	85.00	....	4.925	6.65	4.775	9.85
Cleveland	....	....	3.95	7.85	4.675	.....	.....	....	....	.....	.....	9.85
Youngstown Area	....	....	3.95	....	....	.....	.....	....	....	6.65	....	....
Geneva	3.85	3.90	....	....	....	.....	.....	....	....	....	....	....
Los Angeles	....	....	....	....	....	.....	.....	....	....	6.65	....	....
Pueblo	3.85	3.90	3.95	....	....	75.50	85.00	....	4.925	6.65	4.775	9.85

IRON AND STEEL PRODUCTS—F. O. B. WAREHOUSE, PER 100 LBS., BASE PRICE

	STRUCTURAL SHAPES Per 100 lb. base price	REINFORCING BARS Per 100 lb., base price u 5 tons to carload lot *b* New billet	Rail steel	Add switch	$/cwt for Del.	EXPANDED METAL LATH *k* Per 100 sq. yd., carload lots Std. diamond mesh. 3.4 lb.	Std. ribbed 3.4 lb.	WELDED FABRIC REINFORCING *d* Per 100 sq. ft., carload lots 4x16 in., No. 5 & 10 wires	4x12 in., No. 8 & 12 wires	6x6 in., No. 6 & 6 wires
Atlanta	$7.31	$7.11	$7.11	$.025	$...	$36.00‡	$40.00‡			
Baltimore	6.47	6.81*l*	....	....	....	42.00	45.00			
Birmingham	5.95	5.80	5.80	.05	.15	47.00*p*	52.00*p*			
Boston	6.56*a*	6.38	6.38	....	....	39.50	43.50			
Chicago	5.95	5.33*ff*	5.33*ff*	.0625	....	46.00*C*	51.00*C*			
Cincinnati	6.42*ak*	6.63*r*	....	....	.15	37.50*azee*	41.00*azee*			
Cleveland	6.28	5.31*r*	....	....	....	37.50‡	41.00‡			
Dallas	9.05	7.25	7.25	....	....	49.00	52.00			
Denver	7.55	7.50*c*	....	....	....	50.00*a*	62.00*qq*			
Detroit	6.42	6.24*n*	....	....	.20	53.00	58.00			
Kansas City	6.70*mn*	6.97	....	....	....	35.50	39.00			
Los Angeles	6.85*fAh*	6.82*g*	....	....	....	48.00	54.00*kk*			
Minneapolis	6.51*kk*	7.40*ll*	7.40*ll*	....	....	36.00	39.50			
Montreal	6.65*iB*/6.95*A*	4.90*i*	4.90*g*	....	....	51.00*A*	57.00*k*			
New Orleans	....	5.80*ok*	....	.05	....	66.00	66.00			
New York	6.77	6.50	6.50	....	.30	38.50*st*	42.50*st*			
Philadelphia	6.42	6.67	....	....	....	39.50‡	43.50‡			
Pittsburgh	5.80/6.00	5.80/6.00	....	....	.10	36.60	38.60			
St. Louis	6.35*a*	5.75*c*	5.75*c*	....	....	47.00*aa*	53.00*aa*			
San Francisco	7.12	6.50*l*	....	....	....	40.50	43.50			
Seattle	4.50*e*	5.80*ed*	....	....	....	57.00*mmm*	47.00*mmx*			

A.P.M.* Joliet, Illinois, Donora, Penn., $2.81
F.o.b. Mill: Monessen, Penn., $2.91

A.P.M.* Joliet, Illinois, Donora, Penn., $1.96
F.o.b. Mill: Monessen, Penn., $2.03

A.P.M.* Joliet, Illinois, Donora, Penn., $2.95
F.o.b. Mill: Monessen, Penn., $3.05

* At Producing Mill.

‡ Delivered. *b* 1–5 tons, add 35¢. Less than 1 ton, add 50¢. *c* 20 tons or over base. *d* Mill price plus freight. *e* F.o.b. plant. *f* Includes delivered in free delivery zone. *g* 10,000 to 39,999 lbs. *h* List price. Dominion tax exempt. Provincial and Municipal tax extra. *i* Plus Dominion, Provincial any Municipal sales tax. *j* Price per ton. *k* F.o.b. city. *l* Intermediate and hard grade, new billet. *m* Per sq.yd. *n* 5–10 tons. *o* 5 to 20 tons base. *p* Del. of 500 sq. yd. or more. *q* Std. ribbed, 4 lb. per sq. yd. *r* 5 tons or over. *s* LCL. *t* Asphalt coated. *u* Note: Revised size extra — 1 in., 1¼ in., 1½ in., 10¢. ⅞ in., ¾ in., ⅝ in., 15¢. ½ in., 25¢. ⅜ in., 50¢. ¼ in, 80¢. ¼ in. $1.90. *v* 20 tons. Straight. *w* Copper bearing. *x* 2.5 lb. per sq. yd. *y* $0.0093 transportation tax included. *z* Copper alloy. *aa* Delivered truck to job. Contractor to do unloading. *dd* F.o.b. dock. *ee* F.o.b. cars. *ff* Carload lots. *gg* Including sales. *hh* 10,000–19,999 lbs. *kk* ½" ribbed. *ll* 5 to 8 tons, f.o.b. city. *mm* 2% off for cash. *nn* 1–5 tons. *oo* 10 tons to CL. *a* 2000–9999 lbs. *A.* Amer. struct'l shapes. *B.* Canadian shapes. *C.* Deliv to contractor.

PLUMBING, HEATING, WATER, SEWER AND DRAIN PIPE

	C. I. PIPE Per net ton f.o.b. 6 in. to 24 in.*a*	ASBESTOS CEMENT PIPE per lin. ft., f.o.b. city 6" Pr Cl. 150	12" Sew Cl. 1	VITRIFIED SEWER PIPE Per foot, Delivered std. 8 in. s.s.	ASTM C13-44T std. 12 in. s.s.	24 in. ds.	36 in. ds.	CLAY DRAIN TILE ASTM C4-24 Per 1,000 ft., carload lots, f.o.b. 6 in.	8 in.	CONCRETE SEWER PIPE Per ft., delivered: ASTMC 14-41 12 in.	24 in.
Atlanta	$101.00	$1.44	$2.42	....	....	....	....	....	....	....	....
Baltimore	109.00	1.46	2.42	.546	1.053	4.275*A*	11.377*5A*	178.20	274.80	.90	2.45
Birmingham	93.00	1.44	2.42	.42	.75	2.99	....	250.00‡	375.00‡	1.25*m*	2.75*m*
Boston	113.00	1.46	2.20	.553*uzz*	1.0665*uzy*	4.41*uzy*	11.90*uzy*	187.80*v*	289.20*v*	1.55*mg*	3.80*mg*
Chicago	107.00	1.44	2.20	.70*m*	1.35*m*	5.62*m*	13.50*m*	150.00‡	270.00‡	.80	2.80
Cincinnati	106.00	1.46	2.29	.567*y*	1.093*y*	4.32*y*	11.175*v*	164.40	254.10	.75*m*	2.80*m*
Cleveland	108.00	1.46	2.29	.49*x*	.945*x*	3.96*x*	10.66*x*	158.00*m*	245.65*m*	.75*m*	2.95*m*
Dallas	112.00	1.46	2.54	.436	.822	3.234*b*	9.17*b*	.....	.....	.49	1.60
Denver	115.00	1.55	2.54	.43*dd*	.74*dd*	3.18*dd*	....	.....	.....	.74*m*	2.50*m*
Detroit	108.00	1.46	2.29	.72	1.39	5.58	14.91	240.00*m*	360.00*m*	.80	3.20
Kansas City	113.00	1.46	2.29	.515	.92	3.64	9.20	216.70	465.00	.70*g*	3.00*g*
Los Angeles	124.00	1.53	2.29	.51*f*	1.07*f*	5.24*f*	13.06*f*	228.20*f*	348.90*f*	.95	2.70*ff*
Minneapolis*	112.00	1.50	2.42	.72*mo*	1.32*mo*	5.32*mo*	....	.....	.....	1.36*h*	3.87*h*
Montreal	115.00	....	....	.85*z*	1.50*z*	5.25*z*	....	.....	.....	1.17*j*	3.11*j*
New Orleans	101.50	1.44	2.42	.513	.93	5.15	....	265.00*bb*	455.00*bb*	.65	2.29
New York	111.35	1.46	2.20	.64	1.21	4.86	12.71	.....	.....	1.15	2.50
Philadelphia	110.00	1.44	2.20	.65	1.25	4.95*A*	12.65*A*	300.00‡	350.00‡	1.55*h*	3.75*h*
Pittsburgh	109.00	1.46	2.20	.406*m*	.772*m*	2.85*m*	7.652*m*	147.00	230.00	1.05*h*	2.50*h*
St. Louis	112.00	1.46	2.29	.51	.93	3.65	8.58	160.00*l*	360.00*l*	1.20*il*	2.70*Al*
San Francisco	122.00	1.55	2.29	.61*d*	1.20*d*	5.03*d*	12.57*d*	240.00*l*	400.00*l*	.73	3.02
Seattle	124.00	1.55	2.42	.51*b*	.91*b*	....	....	150.00*c*	.....	.86*ee*	2.56*ee*

	*WROUGHT STEEL PIPE (Full standard weight) Butt Weld‡ Black %	Butt Weld‡ Galv. %	2½ & 3 in., Lap Weld‡ Black %	Lap Weld‡ Galv. %
Lorain, Ohio	40.0	30.0	21.75	10.25*a*
Aliquippa, Pa.	40.0	30.0	22.75	10.25*a*
Sparrows Pt., Md.	38.0	28.0	21.75	10.25*a*
Benwood, W. Va.	40.0	30.0	21.75	16.0*c*
Youngstown, O.	40.0	30.0	22.75	....
Indiana Harbor, Ind.	39.0	29.0	21.75	14.25*a*
Sharon, Pa.	40.0	30.0	20.75	13.75*a*
Wheatland, Pa.	40.0	30.0	19.25*b*	13.75*a*
Ellwood, Ind.	40.0*b*	30.0*b*	20.75	13.75*a*
Fontana, Calif.	28.5*b*	....	14.75*b*	20.5*ab* 6.25*ab*/

‡ Delivered. *a* Class B & heavier. Based on existing freight rates; subject to rate change. Gas pipe and class A, $5 per ton additional. 4 in., $7 per ton additional. 30 in. and larger, usually, $1 per ton less. *b* Extra strength ASTM *C* 200–44T. *c* 4-in., $96. *d* SS361-A. *e* 30-in. *f* F.o.b. factory. *g* Culvert pipe. Reinforced, ASTM C76–41. *h* Reinforced, ASTM C75–41. *i* Reinforced, ASTM C76–37. *j* Centrispun. No. standard specifications in Can. *l* F.o.b. plant. *m* Truck delivery. *o* Listed price is based on LCL (no minimum). *p* Less than 5 tons, per price per ft. *t* Within switching limits. *u* ASTM C13–40. *v* C.L.f.o.b. origin, freight allowed. *x* 2 ft. lengths. *y* 3 ft. lengths. *z* CESA A 60–1941 specifications used. *aa Extra strength ASTM C–800–50.* A standard strength. * 6" to 8", $1.67 per ft.; carlots, F.o.b. track Class 150. *bb* Freight allowed to destination in city. *cc* Truck loads; f.o.b. plant, Newton. *dd* LCL delivered, f.o.b. truck. *ee* 1% off for cash. *ff* 21.

* WROUGHT STEEL PIPE: Discounts from standard list consumers carload prices. Base price approx. $200 per net ton. List prices per ft.: *Butt Weld:* ¼ in., 5½¢; ⅜ in., 6¢; ½ in., 6¢; ¾ in., 6¢; 1 in., 8½¢; 1¼ in., 11½¢; 1 in., 17¢; 1½ in., 23¢; 1¾ in., 27½¢; 2 in., 37¢; 2½ in., 58½¢; 3 in., 76½¢. *Lap Weld:* 3½ in., 92¢; 4 in., $1.09. 5 in., $1.48; 6 in., $1.92. Freight rates to destination to be added to price plus 3 percent tax on transportation.

WROUGHT IRON PIPE: List prices per ft. same as wrought steelpipe. Discount for Pittsburgh base. *Butt Weld* — ⅛ in. black, + 25.75, galv + 57.0; ¼ in. black, + 25.75, galv. + 56.5, ½ in. black, + 19.25 galv. + 52.75; *Lap Weld* — 2½ in. to 3½ in. black + 26.25, galv. + 55 5; 4½ in. to 8 in. black + 23.0, galv. + 50.75. Freight rates to destination to be added to name delivered price.

(Continued on page 109)

a 3½ to 4 in. *b* Continuous weld. *c* 5 and 6 in.

† Threaded and coupled.







HIGHWAY DEPARTMENT'S MOST USEFUL LOADER

Your Eimco can dig ditches, clean up slides, dig up shoulders, speed up new construction, in tunnels, loading trucks or in quarries loading rock.

The Eimco will load rock at the rate of 4 to 6 tons per minute average and sand or gravel at 6 to 8 yards per minute average.

The speed, efficiency and low cost of Eimcos make them preferred equipment in any highway department. Let us tell you of the many other advantages in using Eimcos.

You Can't Beat an Eimco

A419

EIMCO

THE EIMCO CORPORATION

The World's Largest Manufacturers of Underground Rock Loading Machines

EXECUTIVE OFFICES AND FACTORIES — SALT LAKE CITY 10, UTAH, U. S. A.

BRANCH SALES AND SERVICE OFFICES

NEW YORK 51-52 SOUTH STREET • CHICAGO 3319 SOUTH WALLACE STREET
BIRMINGHAM, ALA. 3740 FAYETTE AVE. • DULUTH, MINN. 216 E. SUPERIOR ST.
EL PASO, TEXAS, MILLS BUILDING • BERKELEY, CALIF. 637 CEDAR STREET
KELLOGG, IDAHO, 307 DIVISION ST. • LONDON W. 1, ENGLAND, 190 PICCADILLY

IN FRANCE: SOCIETE EIMCO, PARIS, FRANCE
IN ENGLAND: EIMCO (GREAT BRITAIN) LTD., LEEDS 12, ENGLAND
IN ITALY: EIMCO ITALIA S.P.A., MILAN, ITALY

Above: Digging ditch beside highway in Canada. Below, left to right: Clearing rock off highways, taking out shoulder for highway widening, loading in a tunnel, loading trucks in rock quarry.







You're looking into the Screenhouse Cofferdam for the 400,000 Kilowatt Kanawha River Power Plant, Glasgow, West Virginia — a $40 million project now under construction by American Gas and Electric Service Corp., N. Y. for Appalachian Electric Power Co.

ONCE AGAIN THE MORETRENCH WELL-POINT SYSTEM (left foreground) KEEPS AN AG & E JOB MOVING ALONG—

"IN THE DRY"

Repeat orders mean product satisfaction. When you want dependable, economical pumping, COUNT ON MORETRENCH!

MORETRENCH CORPORATION

90 West St. New York 6 | 4900 S. Austin Ave. Chicago 38, Illinois | 7701 Interbay Blvd. Tampa 9, Florida | 315 W. 25th St. Houston 8, Texas | Rockaway New Jersey

Canadian Representative: Geo. W. CROTHERS Limited, Toronto, Ontario

LUMBER, TIMBER, PLYWOOD—PER M FT., B.M., CARLOAD LOTS F. O. B.

SHORT LEAF YELLOW PINE AND DOUGLAS FIR

All S. L. Y. P. is No. 2 common or better and for No. 1 N. C. Box. (Prices in Bold Face)

All Fir boards, dimensions, planks No. 2, Fir small timbers and timbers are No. 1 Lengths up to 20 ft.

(Prices in italics)

	1x6 s4s	1x8 s4s	2x4 s4s	2x6 s4s	2x8 s4s	2x10 s4s	3x12 Rgh	6x12 Rgh	12x12 Rgh
Atlanta	† **$75.00**	**$78.00**	**$69.00**	**$71.00**	**$75.00**	**$78.00**	**$77.00**	.....	.....
Baltimore	* **90.00**	**94.00**	**75.00**	**75.00**	**80.00**	**90.00**	**110.00**	.....	.....
	101.00g	*101.00g*	*101.00g*	*101.00g*	*101.00g*	*101.00g*	*104.00*	*$118.00*	*$118.00*
Birmingham	† **83.50**	**83.50**	**70.50**	**80.50**	**83.50**	**85.50**	**95.50**	.....	.....
	85.50	*85.50*	*80.50*	*79.50*	*78.50*	*78.50*	*85.50*	*85.50*	*85.50*
Boston	**102/106**a	**104/110**a	**102/106**a	**95/104**a	**96/106**a	**110/115**a	.....	.....	.....
	* *95.00*	*95.00*	*100/106*	*100/106*	*100/106*	*100/106*	*108.00*	*107.00*	*107.00*
Chicago	**100.00	**105.00	**92.00	**100.00	**101.102	**105/106	**105.00**	.....	.....
	100.00	*101/102*	*104/105*	*108.00*	*108/110*	*108/110*	*110.00*	*110.00*	*110.00*
Cincinnati	* **99.00**	**105.00**	**88.00**	**98.00**	**105.00**	**110.00**	**122.50**	.....	.....
	109.50	*109.50*	*111.50*	*110.00*	*111.50*	*109.50*	*138.50*	*138.50*	*138.50*
Cleveland	** **99.00**	**103.00**	**86.00**	**92.00**	**98.00**	**101.00**	.....	.....	.....
			102.00	*102.00*	*104.50*	*104.00*	*117.00*	*117.00*	*117.00*
Dallas	k† **78.00**	**80.00**	**69.00**	**58.00**	**59.00**	**59.00**	**98.00**	.....	.....
Denver	* *Not in stock*		*137.00*	*138.00*	*134.00*	*136.00*	*139.00*	*155.00*	*155.00*
Detroit	‡ **110.00**	**113.00**	**101.00**	**110.00**	**114.00**	**104.00**	.....	.....	.....
	101.50	*102.50*	*105.50*	*106.25*	*105.25*	*110.00*	*117.75*	*122.50*	*122.50*
Kansas City	* **122.00**	**122.00**	**122.00**	**122.00**	**122.00**	**122.00**	.....	.....	.....
	122.00	*122.00*	*122.00*	*122.00*	*122.00*	*122.00*	*147.50*	*157.50*	*157.50*
Los Angeles	l *96.00*	*96.00*	*96.00*	*96.00*	*96.00*	*96.00*	*114.00*	*124.00*	*114.00*
Minneapolis	# *130.00*	*130.00*	*135.00*	*135.00*	*135.00*	*135.00*	*150.00*	*150.00*	*150.00*
Montreal	ab85.00	90.00	85.00	90.00	100.00	100.00	.....	.....	.....
	175.00	*175.00*	*175.00*	*175.00*	*175.00*	*175.00*	*176.00*	*176.00*	*170.00*
New Orleans	† **100.00**	**100.00**	**92.50**	**85.00**	**90.00**	**94.00**	**118.00**	.....	.....
	† *90.00*	*100.00*	*108.25*	*99.25*	*97.50*	*97.50*	*120.00*	*122.50*	*120.00*
New York	j **109/114**	**112/117**	**110/115**	**115/120**	**120/125**	**125/130**	**150/160**	.....	.....
			Range from $115.00 to $120.00				*150/145*	*144/155*	*144/155*
New York	** **98.00**	**102.00**	**82.00**	**97.00**	**99.00**	**100.00**	**125.00**	.....	.....
	94.00	*94.00*	*101.00*	*101.00*	*101.00*	*102.00*	*108.00*	*125.00*	*125.00*
Philadelphia	‡		**Range from $114.00 to $127.00**				**114/127**	.....	.....
			Range from $155.00 to $160.00				*150/140*	*150.00*	*160.00*
Pittsburgh	..... †		**Range from $90.00 to $95.00**			**110/120**	**110/120**	.....	.....
			Range from $110.00 to $120.00			*110/120*	*110/120*	*140/155*	*145/155*
St. Louis	f**c122.00**e	**124.00**e	**100.00**d	**115.00**e	**119.00**e	**125.00**e	.....	.....	.....
			*117.00*d	*125.00*e	*125.00*e	*125.00*e	*205.00*e	*205.00*	*205.00*
San Francisco	A *65.00*	*68.00*	*69.00*	*69.00*	*67.00*	*67.00*	*67.00*	*70.00*	*70.00*
Seattle	† *80.00g*	*80.00g*	*80.00g*	*80.00g*	*80.00g*	*80.00g*	*80.00g*	*80.00g*	*80.00g*

	LONG LEAF Y. P. Merchantable grade up to 20 ft.		PLYWOOD Rail freight increment (See note for base price)	
	2x12 Rgh	12x12 Rgh	⅜"	¾"
Atlanta	.....	.....	$22.32	$27.24
Baltimore	**$155.00**	**$155.00**	25.92*	31.60*
Birmingham	**115.50**	**155.50**	21.78	26.58
Boston	.....	.....	25.92*	31.60*
Chicago	**134.00**	**134.00**	22.45*	27.37*
Cincinnati	**145.00**	**145.00**	25.00*	30.48*
Cleveland	.....	.....	25.37*	30.93*
Dallas	**108.00**	**98.00**	18.72	22.80
Denver	.....	.....	13.92	16.98
Detroit	.....	.....	25.00*	30.48*
Kansas City	.....	.....	16.56	20.16
Los Angeles	.....	.....	16.61*ab	20.25*ab
Minneapolis	.....	.....	19.89*	24.25*
Montreal	.....	.....	.....	.....
New Orleans	**148.00**	**140.00**	18.72	22.80
New York	**210/240**	**210/240**	25.92*	31.60*
	.....	.....	.....	.....
New York	**190.00**	**190.00**	....	....
	200/210	**200/210**	25.92*	31.60*
Pittsburgh	**110/120**	**115/125**	25.92*	31.60a
St. Louis	.....	.....	18.72	22.80
San Francisco	.....	.....	12.22*a	14.91*a
Seattle	.....	.....	.....	.....

† F.o.b. mill. * F.o.b. city, CL, out of yard. ** F.o.b. city, CL, direct mill shipment. ‡ Deliv. to contr. CL. 1. Retail, LCL, at yard. # Retail, LCL, deliv. 2. Deliv. truck lots. 3. and.

LUMBER: **Bold Face type, Southern Pine.** *Italics, Douglas Fir.* *a* Spruce *b* Tax exempt. *c* 5M lots. *d* 8–12 ft. lengths. *e* 8–16 ft. lengths. *f* 18 ft. or under. *g* No. 1 common. *i* 8 ft. lengths. *k* No. 3 common. *l* 8–10 ft. lengths. *n* ⅓ #1, ⅓ #2 & ⅓ #3.

A Rail freight rate from Northwest mills to San Francisco are $11.50 to $15.00 per M ft bm. From Northern Calif. mills $9.00 by rail, $9.50 by truck. All rates for surfaced stock. For rough, add $3.00 to above figures.

PLYWOOD: Plyform grade Fir Plywood, 4' by 8' panels, 3-ply, sanded 2 sides, water resistant glue, carload lots, delivered per 1,000 sq. ft. surface. Seattle base price on ⅜", $159.00; on ¾", $181.00. Exterior plyform ⅜" $179.00, ¾" $203.00. For other centers add rail freight increment from table on proper size. Oiling and edge sealing charges included. *a* Lower rate by water shipment. *b* 50,000 lb. minimum.

* Incl. new freight rates. Rates for other cities not avail. as we go to press.

GLASS, EXPLOSIVES, CHEMICALS

	WINDOW GLASS: Discounts from jobbers list, Feb. 1, 1950a, Single or Double Thickness, A quality	WINDOW GLASS: B quality	EXPLOSIVES: Per lb. 40% Ammonia Gelatin in 50 lb. cases delivered in 200 lb. lots*
Atlanta	79%	80%	$0.2315
Baltimore	76%d	78%d	.2315
Birmingham	83%	83%	.1790
Boston	79–10%	79–10%	.2315
Chicago	78%	78%	.2315
Cincinnati	78%	78%	.2315
Cleveland	78–10–10%	78–10–10%	.2715
Dallas	75%	75%	.2390
Denver	81–5%	81–5%	.2365
Detroit	78–10–10%	78–10–10%	.2315
Kansas City	80–10%	80–10%	.2365
Los Angeles	75%	80%	.2340
Minneapolis	78–10%	78–10%	.2365
Montreal	40–5%bc	40–10–5%b	21.60ai
New Orleans	78%	77%	.2365
New York	82–10%	82–10%	.3975g
Philadelphia	78%	80%	.2315
Pittsburgh	82%	82%	.2040
St. Louis	80–10%	80–10%	.2365
San Francisco	70%	70%	.2315
Seattle	75%	78%	.2340

Price of 60% Ammonia Gelatin is $0.0125 per lb. higher than 40%

Glass; a Jobbers' list price per box, 14 x 20, ss, $42.75 for A quality, $37.50 for B quality; 14 x 20, ds, $60.00 for A quality, $52.75 for B quality. *b* Discount from list, Apr. 1951; sale- tax included, but 6% tax exemption not allowable for. *c* Single thickness. *d* Discount 6/15/52.

Explosives; * Urban prices influenced by service charges or local storage and delivery regulations do not consistently reflect quantity prices in less congested areas. *g* In borough of Kings, Queens, and Richmond and in Manhattan south of Canal St., add delivery charge of $20.00 per trip. *h* F.o.b. city per 100 lb. forcite, 40%. Forcite 60%, $23.35. *i* F.o.b. Beloeil (near Montreal).

40% Ammonia Gelatin price ranges in other than urban areas, per lb. (except Seismograph Grades)

	C/L 20,000 lb. net	Tons	200 lb. lots
E. of the Miss., except Fla. and Me.	$0.179	$0.2115	$0.2315
W. of Miss. to Rocky Mtn. States, Fla. and Maine	.184 – 1915	.2165– 224	.2365– 244
Rocky Mtn. States	.184 – 1965	.2165– 224	.2365– 249
Pacific N. W. States	.1815– 194	.214 – 2265	.234 – 2465
Pacific S. W. States	.179 – .1865	.2115– .214	.2315–.2365

PILES, TIES F. O. B.

PILES

Prices per linear foot, fir and pine, bark off, f.o.b. cars, New York. Fir based on Wash. and Ore. points to New York shipping area; pine based on freight from Norfolk.

Dimensions	Points	Length	By Rail: Pine*	By Rail: Fir
12-in. at butt	6-in.	30 to 50-ft.	$0.51	....
12-in.— 2-ft. from butt	6-in.	50 to 59-ft.	.54]	....
12-in.— 2-ft. from butt	6-in.	60 to 69-ft.	.58	..
12-in.— 2-ft. from butt	6-in.	90 to 100-ft.	....	....
13-in.— 3-ft. from butt	8-in.	91 to 100-ft.	....	....
14-in.— 2-ft. from butt	6-in.	50 to 69-ft.	.50/.68	....
14-in.— 2-ft. from butt	6-in.	70 to 79-ft.	.78/.83	.93
14-in.— 2-ft. from butt	8-in.	80 to 85-ft.	.83/.93	.94
14-in.— 2-ft. from butt	8-in.	85 to 89-ft.	....	1.00
14-in.— 2-ft. from butt	8-in.	90 to 100-ft.	....	1.02

* Pine piling over 80-ft. available only in limited quantities.

RAILWAY TIES

Prices f.o.b. per tie for carload lots:		6"x8"x8' Untr.	6"x8"x8' Tr.¶	7"x9"x8'6" Untr.	7"x9"x8'6" Tr.
Boston	Oak::	....	....	....	....
	Pine	....	....	....	....
New York	S. L. Sap Pine	$2.55	$4.35	$3.45	$5.45
	Mixed Oak	3.10	4.65	3.70	5.95
Birmingham	Hardwood	2.40	3.88a	2.85	4.58a
Chicago	Red Oak	...	4.00a	....	5.00a
Los Angeles	Douglas Fir:::	....	....	....	....
	Redwood	....	....	....	....
Philadelphia	Red Oak	2.55	3.90	3.45	5.10
St. Louis	White Oak	3.04	....	3.85	....
	Red Oak	2.94	3.60a	3.67	4.68a
	Sap Pine or Cypress	3.41a	....	4.44	....
San Francisco	Douglas Fir	2.20e	3.25af	2.92bf	4.30eaf
Montreal	Birch or Maple:::	.... h	.... h	.... h	.... h

Tr.— Treated; Untr.— Untreated. *a* Creosoted. *b* 7" x 9" x 8'. *e* Empty cell. *e* Green. *f* F.o.b. cars. *h* No constant price available. *i* Not available.

CHEMICALS

Water, sewage treatment, road work, f.o.b. carlots, New York

Bleaching powder in drums f.o.b. works, per 100 lb::	$5.02
Chlorine cylinders, liquid, per lb, f.o.b. works	.0875
Calcium chloride, 77–80%, flaked, 100-lb. paper bag, f.o.b. works, ton	25.00
Silicate of soda, 52 deg., in drums, f.o.b. works, per 100 lb.:::	2.10
Soda ash, 58%, in paper bags, per 100 lb. dense	1.60
Sulphate of aluminum, commercial, in 100-lb. bags f.o.b. works	1.65
Sulphate of copper, in bags, 99% per 100 lb. f.o.b. works:::	8.95

STRUCTURAL CLAY BUILDING TILE, BRICK AND LIME—DELIVERED

	STRUCTURAL CLAY TILE — PARTITION — SCORED			STRUCTURAL CLAY TILE — LOAD BEARING — SCORED			BRICK		LIME		
	Per M. lots of 2,000 pieces or over,			Per M. lots of 2,000 pieces or over,			Per M. in quantity		Per ton, In paper, Carload lot,		
	3x12x12 in.	4x12x12 in.	8x12x12 in.	8x12x12 in.	10x12x12 in.	12x12x12 in.	Common backing	Straight hard	Hydrated finishing	Common hydrated	Pulverized, or lump
Atlanta	$195.00	$207.50	$247.50	$327.00	$342.00	$381.50	$27.38	$27.38	$19.00	$17.50	$17.50
Baltimore	183.00	195.00	366.00	415.00	541.00	618.00	36.00*k*	41.00*k*	30.00	21.00	....
Birmingham	118.00*p*	128.00*p*	236.00*p*	283.00*p*	.....	.....	23.50*ff*	28.00*gg*	26.37	17.10	*
Boston	196.00†	209.00†	392.00†	383.25†	.....	.....	34.50*p*	37.50*p*	30.00†	28.00†	*
Chicago	135.00	145.00	280.00	.... ..	.....	. .	23.00	25.00	30.80	26.00	....
Cincinnati	185.00*j*	195.00*j*	340.00*jdd*	.....	.....	.....	34.50*j*	46.00*j*	26.37*j*	24.62*j*	.....
Cleveland	172.00**	183.00**	.....	.....	.....	.....	32.00	32.00	25.50	23.50	31.00*ee*
Dallas	.....	118.00	.....	.....	. . .	. . .	19.75	35.25	32.00	21.80	.....
Denver	.....	.....	.....	.....	.....	.....	34.00	40.00	34.80*bb*	28.00*bb*	34.00*bb*
Detroit	127.75	136.25	255.55	.....	317.25	382.60	34.90*cc*	33.30*cc*	32.00	30.00	.....
Kansas City	115.50	122.50	245.00	245.00	303.50	367.00	26.00	26.00	30.50	24.50	27.00
Los Angeles	r	r	r	r	r	r	24.50‡	.....	34.00	34.00	35.00
Minneapolis	171.50*p*	192.50*p*	386.00*p*	192.50*wp*	.....	.....	32.00*np*	36.00	38.00*bbe*	28.00*bbe*	40.00*bbde*
Montreal	150.00*aq*	162.50*aa*	300.00*aa*	.....	.....	.....	31.00	41.50	34.80	32.50	24.60*u*
New Orleans	170.00	170.00	310.00	380.00	.....	.....	31.00	.....	.....	28.00	28.00
New York	138.70*h*	147.90*h*	203.40*eh*	221.90*kn*	.....	.....	35.00	.....	36.00	32.00	....
Philadelphia	126.30	134.80	252.60	302.74	361.35	.....	32.00	42.00 '	25.00	23.00	2.97
Pittsburgh	112.00	117.00	189.00	216.00	279.00	317.00	36.00	46.00*y*	25.00	23.00	2.97*m*
St. Louis	139.00*cc*	160.00*cc*	322.00*cc*	395.00*cc*	.....	.....	40.00*nl*	36.00*s*	.85*aaa*	.65*aaa*	1.10*aaapes*
San Francisco	156.85*s**	177.10*s**	235.30*dds**	.....	.....	.....	37.00	....	26.60	26.60	2.65*m*
Seattle	175.00*cc*	190.00*cc*	.....	190.00*ccw*	.....	.....	39.00*s*	49.00*s*	37.50*sAA*	1.45*f*	3.90*mAA*

† F.o.b. yard Roxbury. *a* Smooth. *b* Per 50 lb. bags. *c* 6 x 12 x 12 in.-3 cell. *d* Pulverized hot. *e* 5% 10th following month. *g* 5½ x 8 x 12. *h* F.o.b. trucks, job site N.Y.C. *j* Truck load or over. *k* $1.00 discount *l* Red face. *m* Per bbl., 180 lb. lots. *q* Provincial and Municipal tax extra. *r* Not used because of earthquake danger. *s* 2% discount for cash. *t* 5½ x 8 x 11¼. *u* Tax exempt. *v* Sand lime. *w* 5 x 8 x 12. *y* Stacked. *z* Pebble lime price per 80 lb. sack. *aa* Price per sack. Lime not sold per ton. *bb* LCL. *cc* Truck delivery. *dd* 6 x 12 x 12. *ee* Pebble lime. *ff* 80% common. *gg* Select. *hh* LCL. *kk* F.o.b. yard. *ll* Per 60 lb. sack, no incr., ton price no longer quoted. ** Warehouse delivery. * F.o.b. Stockton.

PAINT, ROOFING—F.O.B. CARLOAD LOTS

	RED LEAD	WHITE LEAD	READY-MIXED PAINT			ROOFING SUPPLIES Carload lots f.o.b. factory				
	Per 100 lb. in 600-lb. (Approx.) Dry *a*	Per 100 lb. in 100 lb. cases in oil *w*	Per gal., drums Graphite *b*	Aluminum *c*	Ferric Oxide *d*	Rolls, slate surfaced, 85–90 lb. per sq.	Asphalt felt, per 100 lb.	Tar felt, per 100 lb.	Asphalt coating per gal.	Tar pitch 360 lb. bbl. per ton
Atlanta	$17.00	$28.275	$1.75	$2.70	$1.65	$2.06‡	$2.06‡	$2.06‡	$1.00‡	$36.00‡
Baltimore	16.75	27.90	2.65	4.10	3.22	2.50	4.17	4.17	.42	37.00
Birmingham	17.00	28.275	3.90	3.40	....	2.80	2.75	2.75	....	40.50*ee*
Boston	16.75	27.90	....	....	....	2.87*eg*	2.79*eg*	3.04*g*	42*g*	42.00*g*
Chicago	16.75	27.90	....	. .	....	2.73‡*u*	3.04‡*o*	3.04‡*o*	38.00‡*bbr*	43.00‡
Cincinnati	16.75	27.90	..	..	....	2.50	2.50	2.50	.42*y*	42.36
Cleveland	16.75	27.90	2.48*pgg*	2.88*gg*	2.38*gg*	2.50*q*	2.50*o*	2.50*o*	.39*y*	43.20*hh*
Dallas	17.00	28.65	....	4.05	....	3.50*q*	3.75*o*	4.35*o*	.36	46.00
Denver	17.25	28.40	3.07	5.15	2.87	3.31*a*	2.40*o*	2.40*o*	.43*ff*	44.00
Detroit	16.75	27.90	2.35	3.40	2.50	2.75	2.50*f*	2.50	.51	40.00
Kansas City	16.75	28.02	....	2.71*ys*	2.65 '	2.50	2.50*o*	2.50*o*	.313*s*	48.00
Los Angeles	16.75	28.15	3.30*	4.50*	4.20*	2.97*	2.01*e*	*l*	.44*	*l*
Minneapolis	16.75	29.88 28.02	....	....	....	2.40*kdd*	2.50*kdd*	2.50*kdd*	.36*rdd*	37.00*r*
Montreal	....	20.70	2.95*Dff*	4.05*Eff*	3.35*Fff*	4.82*t*	3.65*tf*	3.65*tf*	1.24*kt*	3.78*kt*
New York	16.75	27.90	....	....	....	2.50	2.50*o*	2.50*o*	.36*z*	37.00*
Philadelphia	16.75	27.90	3.25	3.65	3.15	2.54	2.94	2.94	.37	26.00
Pittsburgh	16.75	27.90	2.65	2.65	3.15	2.50	2.87*o*	2.87*o*	.30	42.00
St. Louis	16.75	27.90	....	....	....	2.50	2.50*h*	2.50*h*	.33*y*	38.00
San Francisco	16.75	28.15	2.40	2.90	3.40	2.95	4.00*za*	....	.49	....
Seattle	16.75	28.40	2.96*m*	2.80*m*	....	3.58*mgcc*	3.05*hmcc*	....	.59*mcc*	52.00*mc*

‡ Delivered. Note: Red lead in oil 50c higher than white lead in oil. *a* Red lead prices change frequently due to pig lead price changes. *b* U. S. War Dept. Spec. 3-49A. *c* ASTM Spec. D266-31. *d* 80% minimum ferric oxide. *e* 15 lb. *f* Per 432 sq. ft. *g* F.o.b. yard, Roxbury. *h* Per roll. 65 lb. *i* Net carload lot prices; Minneapolis and vicinity. *j* Asphalt pitch. *k* Per cwt. *l* Not used. *m* 1% discount for cash. *n* F.o.b. city. *o* Per 60-lb. *p* 6-drum. *q* Per 90-lb. roll. *r* F.o.b. factory Chicago. *s* 466 Med. *t* Federal tax included. *u* Per 90 lb. square. *v* Per ton. *w* Price to large paint contractors is $1.25 less. *x* Mineral surfaced. *y* 55-gallon container. *z* Drums. *aa* Approximate cost per 100 lbs. *bc* Roofers coating and cement. Price per ton. *cc* LCL, truck delivery. *dd* 2% cash discount. *ee* Asphalt, in 100 lb. package. *ff* 5-gal. drums. *gg* F.o.b. factory. *hh* Incl. freight. *D*, Std Black. *E* Ready-mixed, *F*, Over 80% ferric oxide. * Aver. wt. approx. 500 lbs

SKILLED AND COMMON WAGE RATES—PER HOUR

	Bricklayers	Carpenters	Struct. Iron Workers	Hoisting Engineers	Plasterers	Electrical Workers	Steamfitters	Common Labor Building	Common Labor Heavy Const.
Atlanta	$2.90	$2.35	$2.60	$2.25	$2.75	$2.60	$2.90	$1.13	$1.13
Baltimore	3.20*d*	2.58	3.125*t*	2.85/3.00	2.75	2.875	2.875*t*	1.565*t*	1.565*t*
Birmingham	3.00	2.50	2.50	2.16	2.52	2.75	2.65	1.225	1.325
Boston	3.06*	2.625	2.82	3.00	3.05	3.00*d*	2.904	1.99*	1.99*
Chicago	3.25*k*	3.00*m*	3.05**	2.80	3.43*	3.212*f*	3.09*	2.20*m*	2.20*m*
Cincinnati	3.12	2.625	2.815	2/2.50/3.05	2.90	2.90	2.90	1.92	1.92
Cleveland	3.12	3.075*r*	3.075	3.075	3.075	3.075	3.07*c*	2.325	2.325
Dallas	3.4375	2.4875	2.625	2.50	3.437	2.75	2.7625	1.325	1.35
Denver	3.45	2.625	2.50	2.63	3.30	2.90	2.82	1.725	1.725
Detroit	3.15**	2.93**	3.15**	2.90	3.31*m*	3.05	3.00*	2.15**	2.15**
Kansas City	3.50	2.55	2.68	2.515/2.76	3.175	2.70	2.90*x*	1.88	1.88
Los Angeles	3.175	2.57	2.70*w*	2.45	3.437	2.75	2.90	1.94	1.94
Minneapolis	3.05	2.55	2.72	2.50	2.90	2.71*n*	2.70	1.82	1.82
New Orleans	2.85	2.22	2.65	2.50	2.525	2.65	2.65	1.225	1.225
New York	3.85*r*	3.24*bB*	3.50*B*	3.50*B*	3.95*A*	3.795*as*	3.445*bp*	2.05	2.05
Philadelphia	3.61*i*	2.90	3.32*i*	3.30	3.475*i*	3.45**	3.29*	1.75	2.05
Pittsburgh	3.40	3.00	2.875	3.00	3.15	3.00	3.00	1.90	1.90
St. Louis	3.55*	2.90*h*	2.90	2.95	3.00	3.09*c*	2.90	1.97	1.97
San Francisco	3.25*w*	2.705	2.85	2.56	3.125*	3.00	2.75	1.85	1.85
Seattle	3.30	2.58	2.78	2.71	3.15	2.80	2.75	2.18	2.14
Montreal*†	1.90	1.70	1.80	1.60	1.90	1.80	1.85	1.20	1.20

* Cost of living bonus now included in basic wage. † Plus 2% vacation pay.

a 6 hr. day. *b* 7 hr. day. *c* Incl. 3% vac. stamp fund for bricklayers; 4% for electricians plus 7¼¢ WF. *d* Incl. 10¢ H&WF. *e* Incl. 6¢ H&WF. *f* Incl. 6% WF. *g* Incl. 11½¢ WF. *h* $2.45 homes & housing plus 5¢ VF. *i* Incl. 3½% WF and 15¢ PF. *j* Incl. 9¢/hr WF. *k* Incl. 7½¢/hr WF. *l* Incl. 4% VF. *m* Incl. 5¢/hr WF. *n* Incl. 6¢/hr WF. *o* Incl. 3% WF. *p* Incl. 3% WF, 3% PF. *r* Incl. 3% WF and 20¢ PF. *s* Incl. 5% W&PF, 4% VF, 1% NC, 6 PH. *t* Incl. 7½¢ H&WF. *w* Incl. 1½% WF. *x* Incl. 10¢ WF. *w* Negotiating. *z* Await. WSB appr. *a* Incl. 8% WF. *d* Incl. 7½¢ IF, 5¢ H&WF. *i* Incl. 10¢ WF, 10¢ PF & 10¢ VF. *B* Incl. 3% WF, 6 PH. *C* Incl. 7¢ IF.

MEXICO CITY PRICES

In Pesos, F.o.b. City		Oct.'52	Nov.'52
Common Wages—Building (8 hr. day)	av. per hr.	.83*	.83*
Common Wages—Heavy Const. (8 hr. day)	av. per hr.	.93*	.93*
Skilled Labor Wages			
Carpenters (8 hr. day)	av. per hr.	2.25*	2.25*
Bricklayers (8 hr. day)	av. per hr.	2.25*	2.25*
Struct. Iron Workers (8 hr. day)	av. per hr.	1.50*	1.50*
Struct. Steel Shapes 3"-15" x 12 meters	per metric ton	1,193.13	1193.13
Reinf. Steel, Corr. Rods			
⅜" x 11 meters	per ton	1,355.67	1355.67
½" x 11 meters	per ton	1,344.46	1344.46
⅝" x 11 meters	per ton	1,333.25	1333.25
¾" x 11 meters	per ton	1,322.04	1322.04
⅞" x 11 meters	per ton	1,322.04	1322.04
1" x 11 meters	per ton	1,322.04	1322.04
Gravel truck load of 3½ cu. meters			
Blue Gravel	per tr. load	50.00	50.00
Rose Gravel	per tr. load	47.00	47.00
Cement, Std. Port. (Tolteca)	per ton	160.00	160.00
Lumber			
Mex. Sacred Fir (OYAMEL)	per M ft.	750.00	750.00
1st Class Pine	per M ft.	1400.00	1400.00
2nd Class Pine	per M ft.	1100.00	1100.00

* Increase by 1/6th—work 6 days, paid for 7 days.

ENR Skilled Average: (Bricklayers, Carpenters, Ironworkers): $2.942 **ENR Common Average:** $1.817

YOUR WHOLESALER IS CONVENIENT



You can consider yourself fortunate in being able to share in a system of distribution that brings to you so many real opportunities through a wholesaler.

You, no doubt, fully recognize the many advantages that accrue to you by having close at hand a wholesaler who can appreciate your purposes and can furnish you with the kind of products that best meet your needs right when you want them—a wholesaler who also takes a personal interest in your welfare and is ready to extend a helping hand whenever you are confronted with special problems which demand the advice of someone having a wider perspective of things along with more varied experience.

Happily, most men, like you, consider their wholesalers their good neighbors, possessing such thorough knowledge of their communities that their requirements can be anticipated and supplies made available in time for use.

All good wholesalers know what, when and how to buy in order to be prepared for your demands. You can be certain, too, that all good wholesalers are familiar with the high quality of Wolverine tube.

We observe that users are glad that they can again buy this dependable copper tube in unrestricted quantities. WOLVERINE TUBE DIVISION, Calumet & Hecla Consolidated Copper Company, Inc., *Manufacturers of tubing exclusively,* 1457 Central Avenue, Detroit 9, Michigan.

BUY FROM YOUR WHOLESALER



will you miss the boat on your next bid?

When you need a bond, you need it *fast*. For getting it in *time* may spell the difference between rejection and acceptance of your bid.

To save time, talk to an Agent of the Indemnity Insurance Company of North America *now*. Ask him to establish your credit line with Indemnity, the largest independent company, which offers the lowest bonding rate to contractors of skill, integrity and responsibility.

Once your credit line has been established with Indemnity, you can be sure of getting bonds on future jobs without delay. In addition, because of Indemnity's low bond rates, no one will be able to outbid you on bonds. This is vitally important, for quite often a job goes for the difference in a bid made possible by low, *preferred* bond rates. See your Indemnity Agent for all the details.

Ask your Agent for a copy of Indemnity's Contractors' Bid Book . . . *use it at your next letting.*

Look to the future...establish your credit line *now!*

Indemnity's low preferred rates are not available in Louisiana and Texas.

INDEMNITY INSURANCE COMPANY OF

NORTH AMERICA

1600 Arch Street, Philadelphia 1, Pa.

PROTECT WHAT YOU HAVE©

Bids—Low Bids—Contracts—Second Section

NEW ENGLAND

BIDS ASKED—HEAVY CONSTRUCTION
STATE HIGHWAY LETTINGS
STREETS AND ROADS
December 8 Connecticut December 19 Vermont

BIDS ASKED—BUILDINGS

Mass., Belchertown—SCHOOL—B.A. 12/16—Town, Supt. Schools, brick elementary school, off S. Main St. $493,000. Plans deposit $50. Bernhard Dirks, Mohawk Trail, Greenfield, archt. CD 6/30/52.

▲ **R. I., Newport**—HOUSING—B.A. 12/22—Newport City Housing Auth., Newport, housing, bounded by Chapel St., Edgar Ct., Memorial Blvd. $1,000,000. Plans deposit $25. CD 5/28.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **John E. Pringle Co., Inc.**, 475 Fifth Ave., New York 17, N. Y. CA. $4,000,000. general contract. 1 and 2 story, brick, block SHOPPING CENTER, incl. between 30 to 35 stores, incl. department type store, rest, medical dental center, 1,500 car parking area, GREENWICH, CONN. Home Owners Mutual Enterprises, Inc., 230 Park Ave., New York, N. Y. O'Hara, Hedlander & Edson, 45 E. Putnam Ave., Greenwich, Conn., archts. Housing project abandoned because of zoning restriction. CD 4/23, under CA.

▲ **Anderson Fairoaks Constr. Co.**, 141 S. Marshall St., Hartford, Conn., LB $1,125,000, MR-46 HOUSING, WALLINGFORD, CONN. Boro of Wallingford Housing Auth., 900 Center St., Wallingford, Conn. Bids No. 19.

MIDDLE ATLANTIC

BIDS ASKED—HEAVY CONSTRUCTION
STATE HIGHWAY LETTINGS
BRIDGES
December 16 Maryland
STREETS AND ROADS
December 9 Maryland December 18 New York
December 19 Pennsylvania

SOON LETS CONTRACT—BUILDINGS

▲ **Del., Wilmington**—HOSPITAL—The Memorial Hospital, 1501 Van Buren St., soon lets contract superstructure Part 2, hospital addn. $3,500,000. York & Sawyer, 101 Park Ave., New York, N. Y., archts.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

NEW YORK—Dpt. P. Wks., The Governor Alfred E. Smith State Office Bldg., Albany

White Oak Excavators, Inc., Plainville, Conn. CA. $926,957, est. $989,000. Menands-Troy Bridge, 1.67 mi. Loudonville-Menands, S.H. -1879, FARC 52-90, FASH 52-13, Albany Co. Bids Oct. 30. CD 11/3, under LB.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **Joseph H. Bauer & Assoc.**, 490 Potter Blvd., Brightwaters, N. Y. CA $1,000,000. 100 HOUSES, 30-acre tract on Brook Ave., north of Sunrise Hy., BAY SHORE, N. Y. Rob-Den Homes, c/o contractor.

▲ **Kissena Park Apartments**, c/o Julius Fishkind, archt., 161-19 Jamaica Ave., Jamaica, N. Y. Owner Builds. $3,000,000. four 6 story APARTMENTS, Kissena Blvd., 45 and Cherry Aves., FLUSHING, N. Y.

▲ **Maran Constr. Co.**, 1910 Arthur Ave., New York 57, N. Y. LB $1,732,000, general constr.;

Heating Maintenance Corp. of N. Y., 220 E. 138 St., New York 51, N. Y., LB $472,770, heating for Flushing HIGH SCHOOL addn., FLUSHING, N. Y. Co-ordinator of School Constr., 49 Flatbush Ave. exten., Brooklyn 1, N. Y. Bids Nov. 18. CD 10/22.

Berne Constr. Co., 110 Mamaroneck Ave., White Plains, N. Y., CA. $750,000. 60 HOUSES, 15-acre tract on Secor Rd., between Hartsdale and Saw Mill River Rds., HARTSDALE, N. Y. Hartsdale Farms Homes, c/o contractor.

▲ **Westland Gardens Homes**, c/o Schulman & Soloway, archts., 100-15 Queens Blvd., Forest Hills, N. Y. Owner Builds. $2,500,000. 250 HOUSES on tract at New York Ave. and W. 22 St., HUNTINGTON, N. Y.

▲ **Peter Marshall Homes**, c/o Matern & York, archts., 90-04, 161 St., Jamaica, N. Y. Owner Builds. $1,000,000. 75 HOUSES, 18-acre tract Hicksville Rd., south of Southern State Parkway, MASSAPEQUA, N. Y.

▲ **Stratton Heights, Inc.**, c/o Lee Perry, archt., 419 North Ave., New Rochelle, N. Y. Owner Builds. $5,000,000. 185 HOUSES on tract on Baraud Rd. near Puritan Dr., NEW ROCHELLE, N. Y.

▲ **Thomas Crimmins Constr. Co.**, 624 Lexington Ave., New York, N. Y., CA foundations;

Bethlehem Steel Co., E. 3 St., Bethlehem, Pa., CA steel, for 27 story OFFICE, 261 Madison Ave. east side from 38 to 39 Sts., NEW YORK, N. Y. 260 Madison Ave. Corp., c/o Sylvan Bien, archt., 565 Fifth Ave., New York 17, N. Y. Total est. $12,000,000.

Gregory Lawns Home, c/o Rudolph Novak, archt., 713 Main Ave., Clifton, N. J., Owner Builds, $600,000 41 HOUSES on tract in Greglawn Dr. off Broad St., CLIFTON, N. J.

▲ **Whitpain Properties, Inc.**, Morris Rd., Ambler, Pa. Separate Contracts. $1,435,000, 82 RESIDENTIAL homes, Morris Rd., Sect. 1; $1,100,000, RESIDENTIAL DEVELOPMENT, Morris Rd., Sect. 2, AMBLER, PA. Paul M. Hesser, 140 W Phil-Elena St., Phila. Pa., archt.

L & D Building Co., Box 487, Latrobe, Pa., LB $939,000. 1, 2, 3 story, steel HIGH SCHOOL, ARMAGH, PA. United Joint School Dist., Armagh, Pa. Bids Nov. 17. CD 10/21.

▲ **L. F. Driscoll Co.**, 18 W. Chelten Ave., Phila. Pa., CA. $2,039,827, HOSPITAL, LAUNDRY, GARAGE, paving, etc. BRISTOL, PA. Lower Bucks County Hospital, Bristol, Pa. Bids Sept. 12. CD 10/7, under LB.

▲ **Albert A. Toll**, Washington Lane and Ashburn Rd., Elkins Park, Pa., Separate Contracts. $1,000,000. RESIDENTIAL DEVELOPMENT, Washington Lane, etc. ELKINS PARK, PA. Leopold Hauf, Jr., 101 Walsh Rd., Lansdowne, Pa., archt.

▲ **T. J. Regan Builders, Inc.**, 301 York Rd., Jenkintown, Pa. Separate Contracts. $1,000,000. RESIDENTIAL DEVELOPMENT, Bethlehem Pike, FLOURTOWN, PA. J. Lee Thorne, 122 S. 17 St., Phila., Pa., archt.

▲ **Leimbach Constr. Co.**, 3906 Hickory Ave., Baltimore, Md. LB $1,017,220. Elmer A. Henderson Elementary SCHOOL (colored) Wolfe, Biddle, Washington and Chase Sts., BALTIMORE, MD. City, Bureau Bldg. Constr., 410 E. Municipal Bldg., Baltimore, Md. Bids Nov. 19. CD 11/5.

SOUTH

BIDS ASKED—HEAVY CONSTRUCTION
STATE HIGHWAY LETTINGS
BRIDGES
December 12 Georgia
STREETS AND ROADS
December 12 Georgia

BIDS ASKED—BUILDINGS

▲ **Fla., Miami**—HOUSING—B.A. 12/16—Miami Housing Auth., 327 N.W. 62 St., 512 housing units for Negroes, $4,500,000. CD 6/19.

Miss., Picayune—HOUSING—B.A. 12/16—Picayune Housing Auth., Picayune, 65 housing units, Miss. 66-1 and Miss. 66-2, $600,000. CD 5/6/52.

TULSA TRUCK POWER WINCHES FOR EQUIPMENT INSTALLATION

Tulsa Winches are designed for heavy and difficult jobs. They are built of the finest available materials insuring long, trouble free service. All Tulsa Winches are equipped with automatic worm brake designed to hold the load while suspended. Load can be lowered only by power. Larger models, such as the Model 64 shown below, are also equipped with drum brake for maximum safety. Tulsa Winches are completely controlled by levers located in the truck cab.

Tulsa Winches are available in capacities from 6500 to 80,000 lbs.

SETTING INDUSTRIAL ENGINE Model 18-G Tulsa Winch (6500 lb. capacity) to raise the gin poles and Model 64 Tulsa Winch (40,000 lb. capacity) to handle the load.

Contact your nearest distributor or write to

Tulsa* Winch
TULSA, OKLAHOMA DIVISION OF VICKERS Inc.

*Reg. U. S. Pat. Off.



▲ Tenn., Jackson—HOUSING—B.A. 12/16—Jackson Housing Auth., Jackson, 215 Negro Housing units. $2,000,000. CD 2/5.

▲ Va., Fairfax—SCHOOLS—B.A. 12/18—Bd. Educ., Fairfax Co., Fairfax, Merrifield High School, Falls Church, $500,000, Earl Bailey, 6915 29 St. N., Arlington, archt.; Falls Church High School, $600,000, Bixon & Norman, 1103 E. Main St., Richmond, archts. CD 4/10.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ † W. A. Smith Constr. Co., 1209 10th St., Houston, Tex. CA. $2,079,373. railroad from Leeland, N. C. to new army ammunition Depot at Sunny Point, NORTH CAROLINA. U. S. Eng., 308 Customhouse, Wilmington, N. C. Bids Nov. 18. CD 10/31.

▲ GEORGIA—State Hy. Dpt., Atlanta.

Lothridge Bros., Gainesville, Ga., CA, $97,201 PR-1203 (1), Rabun Co.; CA, $116,669, S-1241 (1), Newton Co.;

Crummey & Crummey, Rochelle, Ga., CA, $114,075, S-0679 (2), Pulaski Co.; CA, $128,987, S-0532 (2), Randolph and Terrell Counties;

Ocmulgee Constr. Co., McRae, Ga., CA, $117,556 S-0686 (5), Wilkinson Co.; CA, $91,015, S-0582 (1), Laurens Co.;

C. L. Rhodes, Decatur, Ga., CA, $77,188, FI-001-4 (1) Contract 2, Clayton Co.;

J. G. Attaway Constr Co., Statesboro, Ga., CA, $63,329 S-0731 (1), Bulloch Co.;

R. A. Bowen, Inc., Macon, Ga., CA, $80,307, S-1640 (1), Jones Co.;

E. F. Groover, Maultrie, Ga., CA, $249,142, S-0546 (13) and S 0546 (4), Tift and Worth Counties;

E. A. Hudson Sons, Bolton, Ga., CA, $1,010,804 FI 001-4 (1), Contract 1, Clayton Co., Bids Nov. 21. Grand total $2,146,273. CD 11/12.

Modern Welding Co., Owensboro, Ky., CA, $652,707 natural gas system, FORT VALLEY, GA. City, Fort Valley, Ga. Bids Nov. 18. CD 10/16.

▲† Gahagan Constr. Corp., 90 Broad St., New York, N. Y., LB, $2,268,801, constr. Levee 7, major project in Central-Southern Florida flood control project 17 mi. from West Palm Beach Canal southwest and south to Hillsboro Canal, CIVENG 08-123-53-15-B, FLORIDA U. S. Eng., 575 Riverside Ave., Jacksonville, Fla. Bids Nov. 18. CD 10/20.

▲ LOUISIANA—State Hy. Dpt., Highway Office Bldg., Baton Rouge.

Foster & Creighton Co., American National Bank Bldg., Nashville 3, Tenn. LB $742,913. viaduct and c. conc. 0.436 mi. Spring Street Viaduct (Shreveport) State Rte. 20, S. P. 53-09-03, F. A. Proj. U 412 (1), Caddo Parish;

Kansas City Bridge Co., 928 Broadway St., Kansas City 6, Mo. LB $150,000. bridge removal 0.169 mi. portions of Calcasieu River Bridge at Lake Charles, State Rt. 1092, S. P. 810-24-27, Calcasieu Parish;

W. R. Fairchild Constr. Co., Box 127, Hattiesburg, Miss. LB $196,887. four 30 ft., four 40 ft. reincon. deck girder bridge, sixteen 20 ft. concrete slab span bridge, twelve 20 ft. concrete slab span bridge 0.159 mi. Dixie Inn-Minden Hy., State Rte. 4, S. P. 1-04-15, F. A. Proj. F 116 (9), Webster Parish. Bids Nov. 19. CD 10/30 and 10/31.

▲ LOUISIANA—State Hy. Dpt., Highway Office Bldg., Baton Rouge.

T. L. James & Co., Inc., Box 531, Ruston, La. LB $561,421. patching, widen. existing c. conc. 13.91 mi., Welsh-Mermentau Hy., State Rte. 2, S. P. 3-07-07 and 3-08-08, Jefferson Davis Parish;

W. R. Aldrich & Co., Box 1751, Baton Rouge, La. LB $477,426. c. conc. 3.356 mi. Orange-Toomey Hy., State Rte. 2, S. P. 3-02-20, F. A. Proj. FI 411 (4), Calcasieu Parish;

Henry & Hall, Dubach, La. LB $290,946. bit. surf. tr. 7.286 mi. Epps-West and Darnell-West Hys., State Rtes. 455 and 592, S. P. 161-06-07 and 185-03-11, F. A. Secondary Proj. S 67 (3), West Carroll Parish;

Barber Bros. Co., Box 629, Baton Rouge, La. LB $360,450. bit. surf. tr. 15.009 mi. Hammond-Covington Hy., State Rte. 7, S. P. 13-09-20, Tangipahoa and St. Tammany Parishes;

W. H. Patterson & Co., Box 2229, Baton Rouge, La. LB $65,850. bit. surf. tr. 3.1 mi. Hadden's Ferry-Anacoco Hy., State Rte. 138, S. P. 133-02-04, Vernon Parish;

T. W. Kleinpeter, Box 5186 Audubon Station, Baton Rouge, La. LB $127,924. bit. surf. tr. 6.774 mi. Toomey-Starks Hy., State Rte. 121, S. P. 187-01-04, Calcasieu Parish. Bids Nov. 19. CD 10/31 and 10/30.

▲ † James F. O'Neil, 1501 S. Rendon St., New Orleans, La. CA $2,175,000. dehumidification and electrical systems at Michoud Ordnance Plant, Inv. 53-34, NEW ORLEANS, LA. U. S. Eng., 606 Santa Fe Bldg., Galveston, Tex. Bids Oct. 31, awarded Nov. 20. CD 11/6, under LB.

Chattanooga Gas Co., 811 Broad St., Chattanooga, Tenn. Owner Builds. $750,000. 1953 natural gas sys. imprvs., CHATTANOOGA, TENN.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ Howar Bros., 1829 K St., N. W., Wash., D. C. Owner Builds. $1,650,000. 186 multi-family unit HOUSING, S. Ridge Rd., ARLINGTON, VA. Edwin Weihe, 927 15th St. N. W. Wash., D. C., archt.

P. L. Anderson & Sons, Danville, Va., CA $498,890, 1 story 55,000 sq. ft. Coca-Cola bottling PLANT, DANVILLE, VA. Danville Coca-Cola Bottling Co., Danville, Va. Bids Nov 18. CD 10/30.

E. A. Scott & Sons, Americus, Ga., CA, $675,000 100 HOUSING Units, SWAINSBORO, GA. Swainsboro Housing Auth., Swainsboro, Ga. Bids Nov. 20. CD 10/28.

Howard Greenfield, Box 697, Hollywood, Fla., Owner Builds, $700,000, 75 RESIDENCES, HOLLYWOOD, FLA.

Greenville Municipal Separate School Dist., Greenville, Miss., rejected bids Nov. 18, high school, GREENVILLE, MISS. LB $938,800. CD 11/25, under LB.

L. B. Priester & Son., Box 869 Meridian, Miss. LB $938,800. High SCHOOL, GREENVILLE, MISS. Greenville Municipal Separate School Dist., Greenville, Miss. Bids Nov. 18. CD 10/22.

† C & B Constr. Co., 124 Albert Pike, Hot Springs, Ark. LB $898,579. inert storage WAREHOUSES, Louisiana Ordnance Plant, SHREVEPORT, LA. U. S. Eng., 300 Broadway, Little Rock, Ark. Bids Nov. 19. CD 11/20.

▲ Sullivan & Cozzart, 822 W. Kentucky St., Louisville 10, Ky. CA $1,145,620, general contract. HOSPITAL, Brook and Chestnut Sts., LOUISVILLE, KY. Jewish Hospital Assn., Floyd and Kentucky Sts., Louisville, Ky. Bids Sept. 23, awarded Nov. 20. CD 9/26, under LB.

Wehr Constr. Co., 2127 S. Floyd St., Louisville 8, Ky. LB $692,700. Fern Creek County High School addn., Fern Creek, LOUISVILLE, KY. Jefferson Co. Bd. Educ., 618 W. Jefferson St., Louisville, Ky. Bids Nov. 20. CD 11/6.

MIDDLE WEST

BIDS ASKED—HEAVY CONSTRUCTION

STATE HIGHWAY LETTINGS

BRIDGES

December 9 Indiana

STREETS AND ROADS

December 9 Indiana, Wisconsin December 16 Ohio

▲ Ill., Chicago—B.A. 12/11—City, City Hall, two-level Wacker Dr. from Adams to Jackson Sts. $1,000,000. CD 11/7.

▲ O., Cincinnati—B.A. 12/16—City, City Hall, constr. Mill Creek Outfall and diversion sewer from Ohio River to Gest St. and west Branch-Ohio River Interceptor. $1,500,000. Plans deposit $10. T. J. Montgomery, city engr. CD 5/29.

10 Different Jobs for UNIVERSAL CONCRETE CRIBBING

1. Bridge abutments and wings
2. Erosion control walls
3. Flood control levees
4. Loading docks
5. Grade crossing approaches
6. Highway underpasses
7. Hydraulic intake and outlet works
8. Shore, river and harbor protection walls
9. Industrial property conservation
10. Railway and highway embankment retaining walls

Write for free 8-page "CRIBBING" folder!



CONTRACTORS! If doing business abroad, Universal can supply you with pipe-making machines and all accessories for making pipe. Write for details.



Universal also produces closed-face cribbing in addition to open-face type shown in photo. Drawing shows construction technique.

UNIVERSAL CONCRETE PIPE CO.

Home Office: 297 S. High St., Columbus 15, Ohio

ALABAMA: Decatur, Dothan, Florence. FLORIDA: Miami, Ocala (Florida Concrete Pipe Co.), St. Petersburg, Tallahassee, Tampa. GEORGIA: Atlanta. KENTUCKY: Louisville (Dixie Concrete Pipe Co.). MARYLAND: Baltimore (Jessups). NEW JERSEY: Kenvil. NEW YORK: Binghamton, New York City, Port Washington, Rochester, Syracuse. OHIO: Columbus, Zanesville. PENNSYLVANIA: Norristown, Pittsburgh. TENNESSEE: Nashville. WEST VIRGINIA: Clarksburg, Charleston, New Martinsville, Wheeling. AFFILIATE — Concrete Pipe Co. of Ohio, Cleveland, Sandusky, Youngstown, Ohio; Erie, Penn.

BIDS ASKED—BUILDINGS

▲ **Mich., Detroit**—AUDITORIUM—B.A. 12/16—City, J. E. Frawley, pres. Memorial Hall Comn., foundations, piles and pile caps contract brick, steel, stone Henry-Edsel Ford Auditorium, Woodward, Jefferson and Randolph Sts., $3,000,000, Crane, Kiehler & Kellogg, 112 Madison Ave., and O'Dell, Hewlett & Luckenbach, 2300 Dime Bldg., archts. CD 10/11/50.

▲ **Mich., Detroit**—HOUSING—B.A. 12/17—Detroit Housing Comn., Harry J. Durbin, secy., 409 Griswold St., Edward J. Jeffries Homes, incl. eight 14 story, brick apartments, Haynes, Gibson, Seldon and Lodge Expressway, Area No. 2, Mich. 1-7, $9,000,000. Plans deposit $25, refundable, Smith-Hinchman & Grylls, Inc., 243 W. Congress St., Detroit, archt. CD 11/13.

▲† **Ill., Lemont** — HEATING PLANT — B.A. 12/23 — Atomic Energy Comn., Lemont, heating plant, Argonne National Laboratory, $1,000,000, Jackson & Moreland, 19 E. 47 St., New York, N. Y., engrs. CD 11/17/48.

▲ **Wis., Mendota**—RECEIVING and INTENSIVE TREATMENT—B.A. 12/30—State Dpt. P. Welfare, 128 S. State Capitol Madison, 2 story, 190x360 ft., rein.-con., brick steel receiving and intensive treatment bldg. $2,500,000. Roger C. Kirchhoff, Madison, state archt. Brust & Brust, 135 W. Wells St., Milwaukee, Zone 3, archts. CD 6/21/51.

▲ **Mich., Detroit**—HOUSING—B.A. 1/7—Detroit Housing Comn., H. J. Durbin, secy., 409 Griswold St., Edward J. Jeffries Homes, incl. five 14 story brick, steel apartments, Canfield, Willis, Gibson and Lodge Expressway, Area Nov. 4, Mich. 1-7A, $5,000,000. Plans deposit $25, refundable, Smith-Hinchman & Grylls, Inc., 243 W. Congress St., Detroit, archt. CD 1/10/45.

SOON LETS CONTRACT—BUILDINGS

▲ **Ill., Chicago**—TESTING FACILITY—Ford Motor Co., 3000 Schaefer Rd., Dearborn, Mich., soon lets contract superstructure for jet engine testing facility, $2,500,000. Albert Kahn Associated Architects & Engineers, Inc., New Centre Bldg., Detroit, Mich., archt. CD 10/9.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ **Thomas D. Nolan Co.**, 4017 S. Brook St., Louisville, Ky., CA, $1,394,000, Section 1 Fall Creek Interceptor Sewer, N.W. Ave. to Sutherland Ave.;

Columbia Constr. Co., 2108 Columbia Ave., Indianapolis, 18, Ind., CA, $1,474,744, Section 2 Sutherland Ave. to 42 St., INDIANAPOLIS, IND. Bd. Sanitary Comrs., City Hall, Indianapolis, Ind. Bids Nov. 3. CD 11/25, under LB.

▲ **ILLINOIS**—State Div. Hys., Springfield,

The Standard Paving Co., 30 N. La Salle St., Chicago, 2, Ill., CA, $682,082, c. conc. 3.75 mi., U.S. 40, Clark Co. (Correction—cost);

S. J. Groves & Sons Co., 1104 W. Reynolds St., Springfield, Ill., CA, $1,618,680, c. conc. base course widn., bit. resurf. 0.52 mi. Ill. 34 and c. conc. 8.89 mi. Ill. 146, Hardin Co.;

Joyce Bros. Constr. Co., 715 Myers Bldg., Springfield, Ill., CA, $854,032, c. conc. base course widn., c. conc. base course 2 bridges 8.29 mi. U.S. 36, Scott Co.;

Triangle Constr. Co., 480 N. Evergreen Ave., Kankakee, Ill., CA, $993,636, c. conc. base course widn., c. conc. base course, c. conc. 21.07 mi. Ill. 37 Williamson and Johnson Counties. Grand total $4,148,430. Bids Nov. 13, awarded Nov. 24, CD 11/19, under LB.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ **Shelby Constr. Co., Inc.**, 1108 Canal St., New Orleans, La. Owner Builds. $5,000,000. 334 HOMES, COLUMBUS, O. Todd Tibbals, 965 E. Broad St., Columbus, O., archt.

A. Siegler & Sons, 4923 Lee Rd., Cleveland, O. Owner Builds. $750,000. 50-house HOUSING, Monica Dr., GARFIELD HEIGHTS, O.

▲ **Procon, Inc.**, 80 E. Jackson St., Chicago 4, Ill. CA. $8,500,000. catalytic REFINING unit, LIMA, O. Standard Oil Co. of Ohio, Standard Oil Bldg., Cleveland, O. Universal Oil Products Co., 310 S. Michigan St., Chicago 4, Ill., engr. Awarded Nov. 19. CD 12/6/51.

▲ **A. Siegler & Sons**, 4923 Lee Rd., Cleveland, O. CA. $5,000,000. (1st unit), 1 story, 125,000 sq. ft. brick 32 unit SHOPPING CENTER, Northfield and Libby Rds., MAPLE HEIGHTS, O. Northfield Center Development Co., 4923 Lee Rd., Cleveland, O. CD 4/22.

Alger-Rau, Inc., 17024 Miles St., Cleveland, O. LB. Approx. $975,000. Junior HIGH SCHOOL, MENTOR, O. Bd. Educ., Mentor, O. Fulton, Krinsky & DelaMotte, 6014 Euclid Ave., Cleveland, O., archts. CD 4/8.

A. Siegler & Sons, 4923 Lee Rd., Cleveland, O. Owner Builds. $600,000. 44-house HOUSING, Commonwealth Ave., PARMA HEIGHTS, O.

▲ **E. W. Hauser Constr. Co., Inc.**, 920 Lemcke Bldg., Indianapolis, Ind. CA. $1,000,000, large WAREHOUSE, INDIANAPOLIS, IND. Sears, Roebuck Co., 7 E. Congress St., Chicago, Ill. Awarded Nov. 15.

▲ **E. H. Marhoefer & Co.**, 505 N. La Salle St., Chicago, 10, Ill., CA, $1,743,395, Norman Beatty Memorial HOSPITAL, WESTVILLE, IND. Bd. P. Wks., State House, Indianapolis, 4, Ind. Bids Oct. 30, awarded Nov. 20. CD 11/19, under LB.

▲ **Ragner Benson**, 4744 W. Rice St., Chicago, Ill., CA, $1,250,000, 2 story OFFICE addn., tower, bsmnt. addn. to 5 story building, CHICAGO, ILL. A. C. Nielsen Co., 2101 W. Howard St., Chicago, Ill. Bids Oct. 2, awarded Nov. 17. CD 9/24.

▲ **Gust K. Newberg**, 2040 N. Ashland St., Chicago, 14, Ill., CA, $1,750,000, HOSPITAL addn., Chicago, ILL.

Take Bad Weather Off Your Work Schedule This Winter!



HERMAN NELSON PORTABLE HEATERS

Bad weather ahead? Certainly! But that need not upset your winter work schedule. You can beat rough weather with the help of Herman Nelson Portable Heaters. These furnaces on wheels provide clean, pure, hot air to warm your workers, protect concrete pours, thaw and dry materials, cure plaster—do scores of other heating and drying jobs.

The only completely safe portable heater that uses flexible ducts to spot heat where most needed and remember, only uncontaminated air heaters are absolutely safe!

Find out how you can profit by using Herman Nelson Portable Heaters on your job this winter. Mail the coupon below for full information.



HERMAN NELSON DE LUXE I
Completely automatic, including temperature control. Fresh air delivery 2,000-2,350 cfm. Capacity rating 280-450,000 BTU. Oil fired, electric powered. Other models available—with gasoline or electric power—and with capacities 125-385,000 .BTU.

Herman Nelson Division, Dept. 24
American Air Filter Company, Inc., Moline, Illinois

Gentlemen: Please send me complete information about Herman Nelson Portable Heaters and a free copy of your Cost Control Booklet.

Name_____

Title_____

Company_____

Address_____

City_____ State_____

Diamond Core

Drilling

CORE BORINGS for Foundations, Dams, Bridges and all Heavy Structures GROUT HOLES

Tinney Drilling Co.
Grafton, W. Va.

Would you use 1925 construction equipment today? No. Why not change over and equip your jobs with modern office trailers and cut costs.

CONTRACTORS' OFFICE TRAILER
Models 24'—28'—35' Price $2100. to $3500.
Birch finish, drafting table, 2 built-in desks with letter files & drawers, other conveniences. Can offer three year finance plan. Write for pictures and plans.

TRAILER VILLAGE SALES, INC.
8642 Pulaski Highway, Baltimore 21, Md.
Phone: Essex 2233

...Water Hospital, 5700 N. Ashland Ave., Chicago, Ill. Awarded Nov. 19. CD 9/16.

▲ Darin & Armstrong, 2041 Fenkel Blvd., Detroit, Mich., CA. $2,000,000, substructure 1 story, 450x500 ft. jet engine testing facilities, CHICAGO, ILL. Ford Motor Co., 3000 Schaefer Rd., Dearborn, Mich. Bids Oct. 24, awarded Nov. 21. CD 10/22.

▲ Carroll Constr. Co., 333 N. Michigan Ave., Chicago, 1, Ill., LB. $1,850,000, 2 story, 150x410 ft., steel, brick High SCHOOL, LIBERTYVILLE, Ill. School District 120, Libertyville, Ill. Bids Nov. 19. CD 10/22.

▲ Steinle-Wolfe, Inc., 128 N. Jefferson St., Fremont, O. CA $6,866,428, six 14 story, brick Frederick G. Douglass APARTMENT bldgs., incl. 672 housing units, Hastings, Brewster, St. Antoine and Winder Sts., DETROIT, MICH. City, Detroit Housing Comn., 409 Griswold St., Detroit, Mich. CD 11/11, under LB.

Owen Ames & Kimball Co., 38 Pearl St. N.W., Grand Rapids, Mich. CA $531,560, brick, steel tuberculosis SANATORIUM, GRAND RAPIDS, MICH. Kent County Sunshine Sanatorium, 700 Fuller St. N.E., Grand Rapids, Mich. Bids Nov. 5. CD 1/9/51.

▲ Francis J. Corr, Inc., 1120 Sheridan St., Lansing, Mich. LB. $1,126,940, general contract brick, steel mental HOSPITAL, State Home & Training School, LAPEER, MICH. State, A. N. Langius, dir. State Bldg. Dpt., Lansing, Mich. Bids Nov. 12. CD 10/15.

▲ Pearson Constr. Co., Benton Harbor, Mich. CA. Est. $1,500,000, 3 story, brick, steel, concrete HOSPITAL addn., MUSKEGON, MICH. Mercy Hospital Sisters of Mercy, 1521 Jefferson St., Muskegon, Mich. Bids Oct. 15. CD 10/1.

WEST OF MISSISSIPPI

BIDS ASKED—HEAVY CONSTRUCTION

STATE HIGHWAY LETTINGS
BRIDGES
December 16, 17 Texas
STREETS AND ROADS
December 16 Nebraska, Texas December 17 Texas

BIDS ASKED—BUILDINGS

▲ Tex., Waco—DORMITORY—B.A. 12/19—Baylor University, 1401 S. 5 St., 3 story, 95,000 sq. ft. reinf.-con. fdn. and frame, stone, partial bsmnt., 320-capacity women's dormitory. $750,000-$1,000,000. Easterwood & Easterwood, 601 Service Mutual Bldg., archts. R. S. Smith, Texas & Pacific Bldg. and Leonard E. Kanto, N. P. Anderson Bldg., Fort Worth, engrs. CD 7/17.

▲ Tex., Galveston—WAREHOUSE, etc.—B.A. 1/3—Galveston Wharves, 2324 Strand St., large warehouse across from 37th St. pier, Approx. $1,500,000; cotton storage warehouse, portion 275,000 sq. ft. tract $1,000,000; machine and garage shop, $200,000. Extended date. CD 11/19.

▲ Tex., El Paso—OFFICE—B.A. 1/6—El Paso Natural Gas Co., Bassett Tower, 16 story, bsmnt. office, $2,250,000. Edwin B. Carroll & L. J. Daeuble, Jr., 1001 E. Yandell Blvd., archts. CD 2/27/51, under LB.

SOON LETS CONTRACT—BUILDINGS

▲ Tex., San Antonio—DEPARTMENT STORE, etc.—Sears, Roebuck & Co., Romana Plaza, soon lets contract Contr. 1, department store, $1,742,400; Contr. 2, plumbing and gas lines, $108,000; Contr. 3, central heating plant, ventilating, $90,000; Contr. 4, automatic sprinkler sys. for main bldg., incl. main water lines, $85,000; Contr. 5, outside electrical work; Contr. 6, refrigeration unit, service station, $90,000; Contr. 7, site earthwork, grading, drainage, leveling, $125,000; Contr. 8, construction and paving auto parking area, $150,000. Bartlett Cocke, 3501 Broadway, San Antonio, George L. Dahl, 2101 N. St. Paul St., Dallas, and John Stokes Redden, c/o owner, 3609 Arthington Blvd., Chicago 7, Ill., archts. W. E. Simpson, Millam Bldg., engr. CD 11/5.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲ State Hy. Comn., Jefferson City, Mo., rejected bids Oct. 17, 4 rein.-con. piers, 3 pneumatic 16,160 cu. yd. concrete, Cole and Callaway Counties, MISSOURI. LB $1,786,250. CD 10/22, under LB.

▲† Walters Contg. Corp., 57-36 Woodside Ave., Woodside, L. I., N. Y. LB $1,055,765, est. $1,461,182 refueling and fuel storage facilities, hydrant sys., facilities;

Chicago Bridge & Iron Co. 332 S. Michigan St., Chicago, Ill., LB $99,800, bulk fuel storage, Eng. 23-028-53-26, Sedalia Air Force Base, SEDALIA, MO. U. S. Eng., 601 Davidson Bldg., Kansas City 8, Mo. Bids Nov. 18., CD 10/28.

▲† Martin K. Eby Constr. Co., Inc., 610 N. Main St., Wichita, Kan. CA $1,534,992, est. $1,714,007, hangar and maintenance bldg., Sedalia Air Force Base, SEDALIA, MO. U. S. Eng., 601 Davidson Bldg., Kansas City 8, Mo. Bids Nov. 19. CD 10/29.

▲† Baumann Constr Co., Nevada, Mo. CA $1,336,472, est. $1,472,057, constr. Group B bldgs., incl. fire station, telephone bldg., barracks, Sedalia Air Force Base, SEDALIA, MO. U. S. Eng., 601 Davidson Bldg., Kansas City 8, Mo. Bids Nov. 20. CD 10/17.

ARKANSAS—State Hy. Dpt., Little Rock.
Ellis & Koontz, Ft. Smith, Ark., CA, $70,314 blacktop and new overpass, 1.53 mi. Hy. 71, Bentonville, Benton Co.;

Forgren Bros., 3923 N. 23 St., Ft. Smith, Ark., CA, $98,012, grav. base course bit. 1 rein.-con., structural steel bridge 0.466 mi. Antoine River Bridges and approaches, FAP S-209 (8), Hy. 26, Clark and Pike Counties, CD 11/12;

McGeorge Contg. Co., Inc., foot of Nebraska St., CA, $584,877, blacktop 21.048 mi. Hy. 7, Perry Co., CD 11/6. Grand total, $753,203. Bids Nov. 21.

▲† Western Constr. Corp., 400 Benson Bldg., Sioux City, Ia., CA $4,333,468, earthwork, Stage IV, Fort Randall Reservoir Proj., Lake Andes, Inv. 25-066-53-89, SOUTH DAKOTA. U. S. Eng., 1709 Jackson St., Omaha, Neb. Bids Nov. 7. CD 11/11, under LB.

▲† Peter Kiewit Sons Co., 1024 Omaha Natl. Bank Bldg., Omaha, Neb., CA. $1,254,411, aircraft parking apron maintenance docks, Rapid City Air Force Base, Inv. 25-066-53-61, RAPID CITY, S. D. U. S. Eng., 1709 Jackson St., Omaha, Neb. Bids Nov. 13. CD 11/18, under LB.

† Olson Constr. Co., 410 S. 7 St., Lincoln, Neb. LB $680,886, bachelor officers quarters at Lincoln Air Force Base, Inv. 25-066-53-53, LINCOLN, NEB. U. S. Eng., 1709 Jackson St., Omaha, Neb. Bids Nov. 21. CD 10/28.

† Trinity Constr. Co., P. O. Box 3024, Houston, Tex., LB $741,999, est. $1,113,710, embankment for relocation of Hy. 77 and R. R. at Garza Little Elm Dam, near Lewisville, CIVENG 41-443-53-12, TEXAS. U. S. Eng., 100 W. Vickery St., Fort Worth, Tex. Bids Nov. 18. CD 11/6.

† COLORADO—Bureau P. Rds., Dpt. Commerce, Bldg. 40, Denver Federal Center, Denver.
Lowdermilk Brothers, Box 150, Englewood, Colo., CA, $546,971, est. $496,326, 1.75 mi. Forest Hy. Proj. 29-P, Boulder-Idaho Springs, Boulder Co. Bids Oct. 28, awarded Nov. 20. CD 11/5, under LB.

John H. Keller, 3613 E. 44 Ave., Denver, Colo., LB, $505,978, sewage treatment plant, ENGLEWOOD, COLO. City, City Hall, Englewood, Colo. Bids Nov. 10.

▲† Campbell & Kay, Box 4091, Station A, Albuquerque, N. M., CA $1,167,153, range instrumentation sites, Serial No. Eng. 29-005-53-24, LAS CRUCES, N. M. U. S. Eng., Box 1538, Albuquerque, N. M. Bids Oct. 9. CD 10/17, under LB.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ Sauers Constr. Co., 1255 Larpenteur Ave. W., St. Paul, Minn. CA $1,196,198. Mounds View High SCHOOL, NEW BRIGHTON, MINN. Bd. Educ., Independent School Dist. 38, D. D. Wendt, clk., New Brighton, Minn. Bids Nov. 20. CD 10/28.

Lippert Bros. General Contractors, 2800 N. Santa Fe St., Oklahoma City, Okla. LB $676,594, HOTEL, PARSONS, KAN. Community Hotel Inc., Parsons, Kan. Bids Nov. 6. CD 11/6.

W. R. Grimshaw, Kome Bldg., Tulsa, Okla., CA. $510,000, est. $500,000, CHURCH EDUCATIONAL BLDG. addn., TULSA, OKLA. First Presbyterian Church, 709 S. Boston St., Tulsa, Okla. Awarded Nov. 6. CD 1/9.

▲† Lembke, Clough & King, Inc., P. O. Box 245, Albuquerque, N. M. CA, $1,149,533 (incl. Alt.), masonry, frame SCHOOL, SHIPROCK, N. M. Bureau Indian Affairs, Dpt. Interior, Interior Bldg., Wash., D. C. Bids Nov. 19, awarded Nov. 20. CD 11/25, under LB.

FAR WEST

BIDS ASKED—HEAVY CONSTRUCTION

STATE HIGHWAY LETTINGS
STREETS AND ROADS
December 17, 18 California

SOON LETS CONTRACT—BUILDINGS

▲ Calif., Inglewood—HOSPITAL—Sisters of St. Joseph of Carondelet, c/o Albert C. Martin & Assocs., archts., 333 S. Beaudry St., Los Angeles, soon lets contract 4 story, rein.-con., Daniel Freeman Memorial Hospital. $2,500,000. CD 5/23/51.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲† P. S. Lord Mechanical Contractors, 4407 S.E. Milwaukie St., Portland, Ore., LB, $1,398,000, est. $1,680,000, 2 rein.-con. pumping plant with two 84 in. 1400 ft. steel sewers, RICHLAND, WASH. Atomic Energy Comn., Hanford Operations Office, Richland, Wash. Bids Nov. 18. CD 10/8.

▲† S. A. Healy Co., 20 N. Wacker Dr., Chicago, Ill., LB. $6,798,101, est. $6,925,475, earthwork, pipe line and structures for San Jacinto-San Vincente Aqueduct, Station N-1968 plus 15 to S34 plus 26, San Diego Proj., Spec. DC 3822, CALIFORNIA. Bureau Reclamation, Dpt. Interior, Dist. P. Wks. Office, Eleventh Naval Dist., 1220 Pacific Hy., San Diego, Calif. Bids Nov. 20. CD 11/12.

▲† A. Teichert & Son, Inc., 1931 Stockton Blvd., Sacramento, Calif., CA. $1,805,414, est. $2,000,000 Pacoima Wash improvement, Tujunga Wash to Arleta Ave. CIVENG-04-353-53-14, CALIFORNIA. U. S. Eng., 751 S. Figueroa St., Los Angeles, Calif. Bids Oct. 31. CD 11/6, under LB.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ Robert E. McKee, Inc., 4700 San Fernando Rd., Los Angeles, Calif., CA. $2,786,439, general contract communicable diseases unit, Los Angeles County HOSPITAL;

A. S. Schulman Electric Co., 641 Imperial St., Los Angeles, Calif., CA. $673,379, electrical work for same, LOS ANGELES, CALIF., Los Angeles Co., Hall of Records, Los Angeles, Calif. Bids No. 13, awarded Nov. 18. CD 11/21, under LB.

▲ Austin Co., 618 Grand Ave., Oakland, Calif., CA, $2,500,000, pipe and conduit manufacturing PLANT, Central Ave. between Cherry Rd. and railroad, NEWARK, CALIF. Orangeburg Mfg. Co., Inc., c/o contractor.

L. C. Anderson Co., 3040 Hancock St., San Diego, Calif., CA. $548,900, 36,000 sq. ft. Mission Elementary SCHOOL, OCEANSIDE, CALIF. Oceanside-Libby Union School Dist., 210 S. Horne St., Oceanside, Calif. Bids Oct. 15. CD 10/30, under LB.

Howard J. White, Inc., 44 Encina Ave., Palo Alto, Calif., CA. $587,747, Louis Road, Charleston Road and Ventura Elementary SCHOOLS, PALO ALTO, CALIF. Palo Alto Unified School Dist., 543 Channing Ave., Palo Alto, Calif. Bids Nov. 17, awarded Nov. 19. CD 11/6.

F. E. Young, 2141 Main St., San Diego, Calif., CA, $934,500, JUVENILE HALL, SAN DIEGO, CALIF. San Diego Co., Civic Center, San Diego, Calif. Bids Oct. 28. CD 11/5, under LB.

▲ Gainsford Manor, Mansfield Corp., Markin Co., 450 S. Beverly Dr., Beverly Hills, Calif., Owner Builds, $1,184,500, 133 frame, stucco DWELLINGS, Bona Vista Lane, Ceres, Elmore, Homage Ave., Luming Dr., WHITTIER, CALIF.

ALASKA

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

▲† U. S. Eng., Anchorage, rejected bids Nov. 13, 135,000 cu. yd. wet-mixed concrete, aggregate and grout at Ladd and Elelson Air Force Bases, Inv. 53-23, ALASKA. LB $4,591,075. New bids Dec. 2, under Inv. 53-40. CD 11/20, under LB.

CANADA

BIDS ASKED—BUILDINGS

▲ Que., Montreal—STATION—B.A. 12/22—R. A. Emerson, ch. engr. Canadian Pacific R.R., Windsor Station, Zone 3, 7 story, bsmnt., 60x300 ft., main bldg. addn., St. Antoine St. $1,500,000. Plans deposit $100. CD 11/21.

▲ Ont., Toronto—OFFICE—B.A. 12/23—Confederation Life Assn., 12 Richmond St. E., 10 story, 2 penthouses, bsmnt., sub-bsmnt., 175x175 ft. rein.-con., steel, brick stone office bldg., Bloor St. E. Approx. $8,000,000. Wiggs Walford, Frost & Lindsay, 91 A Bloor St. W., engrs. Marani & Morris, 1250 Bay St., archts. CD 2/8.

▲ Ont., Toronto—ENGINEERING—B.A. 1/6—Hydro-Electric Power Comn. of Ontario, 620 University Ave., superstructure 5 story, 110x140 ft. steel, limestone engineering bldg., 2 story penthouse. Murray and Orde Sts. $3,000,000-$4,000,000. Sproatt & Rolph, 83 Cumberland St., archts. CD 1/25/51.

HEAVY CONSTRUCTION

LOW BIDS AND CONTRACTS

Robb Engineering Works Ltd., 51 La Planche St., Amherst, N. S., CA, $400,000, dock and terminal facilities Govt. Rys., PORT AUX BASQUES, NEWFOUNDLAND, Dpt. Transport, Ottawa, Ont. Bids Oct. 24. CD 9/26.

▲ Swansea Constr. Co. Ltd., 363 Rogers Rd., Toronto, Ont., CA. $1,164,149, roads, walks, grading, sewers, watermains, Air Force Base, Downsview, TORONTO, ONT. Defence Constr. Ltd., 441 Queens Quay W., Toronto, Ont. Bids Sept. 39, awarded Nov. 15. CD 9/15.

▲ Key Constr. Ltd., 1040 Bleury St., Montreal, Que., CA. $1,088,574, another section of Meuliue-Atlantic tributary sewer, MONTREAL, QUE. Municipality, City Hall, Montreal, Que. CD 6/8/51.

BUILDINGS

LOW BIDS AND CONTRACTS

▲ Provincial Constr. Co. Ltd., P.O. Box 1021, Vancouver, B. C., CA. $2,000,000, 2 story, 200,000 sq. ft. concrete slab DEPARTMENT STORE, NEW WESTMINSTER, B. C. Woodward's Department Stores Ltd., Hastings and Abbott Sts., Vancouver, B. C. J. C. Page, 101 W. Hastings St., Vancouver, B. C., archt. CD 12/12/45.

W. H. Cooper Constr. Co. Ltd., 21 Hunter St., E., Hamilton, Ont., CA, $500,000, ENGINEERING BLDG., Hillyard St., HAMILTON, ONT. International Harvester of Canada Ltd., Sherman Ave. N., Hamilton, Ont. Bids Oct. 10. CD 10/8.

Diamond Bros. Ltd., 3729 Bathurst St., Toronto, Ont., Owner Builds. $852,000, 142-suites, two buildings 80x172 ft., one building 76x118 ft., all brick, APARTMENT BLOCK, Victoria Park and Biscayne Aves., TORONTO, ONT. Wilfred Shulman, 463 Spadina Ave., Toronto, Ont., archts.

▲ P. Aubuchon, 155 Somerville St., Montreal, Que., Owner Builds, $1,000,000, BUNGALOWS, Henry and Racette Sts., MONTREAL NORTH, QUE.

W. C. Wells Constr. Co., Ltd., 140 Ave. F North, Saskatoon, Sask., LB, $766,047, PUBLIC BLDG., YORKTON, SASK. Dpt. P. Wks., Hunter Bldg., Ottawa, Ont. Bids Nov. 12. CD 10/23.

(Proposal Advertisements see pp. 122 to 124)

Contract awards maintain record pace

Heavy construction maintained its record pace in November.

Contract awards, as reported by ENGINEERING NEWS-RECORD, hit $1,080 million last month, and pushed volume for the first 11 months of '52 to a new record of $14.8 billion, 16% ahead of 1951.

Commercial building contracts rose sharply for the third consecutive month, racking up a total of $147 million. This was the biggest month on record for commercial building which is now running 24% ahead of the corresponding '51 period.

Contract awards for private mass housing totaled $246 million in November, contributing to an 11-month 1952 total that is 48% above the comparable period last year.

Industrial building settled down to $228 million in November, as against $365 million in October, but the November total still added up to a good month for industrial contracts.

• **Public works**—Bridge construction remained strong with $48 million in new contracts, a little under the post-Korea high of $54 million set in October of this year. Awards for streets and roads dropped to $66 million in November. This was substantially under the $115 million reported in October and the $110 million for September. For the year to date, awards for streets and roads are 23% ahead of 1951 and have set an all-time high in contract dollar volume for a single year.

Contracts for public buildings, including public housing, also dropped in November.

Public housing accounted for $23 million in awards. The total volume for the year in this category is 3% under 1951. Other public buildings had $138 million in November contracts, about half as much as October.

So far this year, public buildings contracts, excluding housing, are 112% ahead of 1951. This is due primarily to new Atomic Energy Commission projects which have almost $2.5 billion in awards.

Waterworks, with $18 million, and sewerage, with $28 million, fared about as well in November as in October. Waterworks volume this year is 6% above the corresponding 1951 period, while sewerage work is running 10% behind.

More construction money in '53

More mortgage money will be available in the second quarter of 1953, Miles Colean, economist, told a meeting of the National Retail Lumber Dealers Association.

Colean qualified the prediction, however. He said money for construction through mortgage financing would depend upon the extent to which banks and insurance companies reenter the market.

He also explained that this flow of mortgage money would be helped by an increase in interest rates for Veterans Administration and Federal Housing Administration-insured loans. Such an increase is expected under the new administration.

• **Urge end of controls**—The Lumber Dealers themselves urged an end to all controls—by permitting the Defense Production Act to expire.

NLRDA, in a resolution, called for action to "promptly unfreeze the fixed-interest rate on FHA and VA loans for residential construction in order that they may be competitive with the free-market rate of the conventional lender."

Private mortgage institutions were urged by the Lumber Dealers to provide a secondary mortgage market to end homebuilders' reliance on the Federal National Mortgage Assn.

Another resolution called for a return to the basing point system.

ENGINEERING CONSTRUCTION CONTRACTS—NOVEMBER, 1952

ENGINEERING NEWS-RECORD *reports continental U. S. Construction projects of the following minimum costs—Waterworks, excavation, drainage and irrigation,* $34,000; *other public works,* $60,000; *industrial buildings,* $82,000; *other buildings,* $300,000

Four Weeks—Thousands of Dollars (000 Omitted)

	November, 1952							U. S. Cumulative			
	New England	Middle Atlantic	South	Mid-West	West of Mississippi	Far West	Total U. S.	Eleven Months 1952	Eleven Months 1951	% Change '51 to '52	Canada November 1952
Public Works											
Waterworks	197	1,631	5,573	686	3,714	5,753	17,554	206,407	195,254	+ 6	1,848
Sewerage	1,275	4,619	1,916	7,202	7,621	5,513	28,146	279,746	311,558	−10	2,950
Bridges	599	12,561	18,160	7,930	4,914	3,688	47,852	376,924	282,657	+33	1,471
Earthwork and drainage	157	167	10,055	535	7,773	10,602	29,289	453,425	472,186	− 4	724
Streets and roads	2,042	21,613	6,726	10,418	17,796	7,553	66,148	1,345,818	1,098,155	+23	6,437
Public buildings, residential	5,287	1,251	2,278	4,129	953	9,158	23,056	575,512	594,435	− 3	5,927
Other public buildings	11,663	24,277	50,558	18,032	16,415	16,798	137,743	4,175,041	1,970,978	+112	14,991
Unclassified	2,691	3,907	20,619	4,212	23,625	11,041	66,095	787,007	914,983	−14	12,680
Total public	**23,911**	**70,026**	**115,885**	**53,144**	**82,811**	**70,106**	**415,883**	**8,199,880**	**5,840,206**	**+40**	**47,028**
Federal government (included in above classifications)	9,989	13,363	60,772	6,650	35,721	24,789	151,284	4,370,766	2,139,405	+104	22,129
Private											
Bridges	.....	.....	150	.....	.....	.....	150	15,719	11,790	+33	.....
Industrial buildings	1,026	11,920	31,901	30,706	54,397	98,196	228,146	2,596,355	3,864,262	−33	7,607
Com'l buildings, residential	9,715	105,898	34,155	32,681	31,562	32,207	246,218	2,782,717	1,880,489	+48	11,996
Other commercial buildings	3,258	71,612	12,582	52,071	4,876	2,650	147,049	711,962	573,462	+24	3,200
Unclassified	.....	175	6,046	12,752	19,911	3,549	42,433	475,635	605,981	−22	520
Total private	**13,999**	**189,605**	**84,834**	**128,210**	**110,746**	**136,602**	**663,996**	**6,582,388**	**6,935,984**	**− 5**	**23,323**
Total Engineering Construction:											
November, 1952—4 weeks	**37,910**	**259,631**	**200,719**	**181,354**	**193,557**	**206,708**	**1,079,879**	.....	.....	.....	**70,351**
October, 1952—5 weeks	89,495	304,299	261,654	187,624	440,156	163,153	1,446,381	.....	.....	.....	213,645
November, 1951—5 weeks	39,523	219,676	165,186	166,400	317,891	116,099	1,024,775	.....	.....	.....	71,896
Eleven Months—1952	**586,975**	**2,445,801**	**3,526,000**	**3,254,440**	**3,219,873**	**1,749,179**	.....	**14,782,268**	.....	.....	**1,127,244**
Eleven Months—1951	584,220	2,396,629	2,613,850	2,233,175	3,158,360	1,789,956	.....	.....	12,776,190	+16	1,102,279
% Change '51 to '52	+0.5	+2	+35	+46	+2	−2	.....	.....	.....	.....	+2

ATLANTIC Pneumatic TOOLS

Use with your standard power pavement equipment . . . .

THE ATLANTIC PNEUMATIC ROCK BREAKER

Splits Large Rocks and Boulders quickly
No Plugs and Feathers — No Explosives
Nearly 4½ times faster



- Effective quick action in removing stones, boulders and rocks from excavations and ditches.
- Eliminates the slow and costly plug and feather method, and the risky and troublesome use of explosives.
- The specially heat-treated Atlantic Tool Steel used in the Atlantic Pneumatic Rock Breaker gives it the extreme toughness to withstand the severest usage and resist breakage regardless of the hardness of the stone.
- Used with standard power pavement breakers. No tool upkeep. Tougher than any stone. A size for every service.



Write for descriptive folder ERB.

Specialists in Tool Steels for chisels, drills, blacksmiths tools and Alloy Steels for axles, bolts, pins, pistons and shafts.

Non-tempering tool steels for greater safety and speed.

ATLANTIC STEEL CORP. 1775 BROADWAY, N. Y. 19

Stang WELLPOINT SYSTEM

For KNOW-HOW ENGINEERING SUPERVISION EQUIPMENT to keep jobs DRY

The Stang System has proved its efficiency and economy on both large and small jobs all over the United States. Stang engineering and supervision in planning, installation and operation insures a DRY JOB at all times.

JOHN W. STANG CORPORATION

2 Broadway, New York 4, N.Y. | 2123 S. 56th St., Omaha, Neb. | 8221 Atlantic Ave., P.O. Box 631, Bell, Cal.

Pennsylvania seeks financing for hospitals

The State of Pennsylvania is faced with the problem of financing a $30-million to $50-million expansion of the commonwealth's mental hospital system.

One method of meeting the problem will be offered to the forthcoming 1953 session of the state legislature, which will be asked to increase the borrowing capacity of the General State Authority by as much as $50 million. Because of constitutional limitations, the only way the state can finance multi-million-dollar projects without voter approval of constitutional amendments is through the General State Authority.

• **Refinancing turned down**—The GSA was created by the 1949 state legislature. It has been authorized to float bond issues totaling $235 million. This money is earmarked for construction. Pennsylvania voters, at the recent election, overwhelmingly rejected a plan to refinance GSA's bond issues. This created a serious problem.

All but $22 million of GSA's present legal borrowing limit already has been allocated for construction. The balance is earmarked tentatively for necessary projects, leaving no money available for new construction.

A survey estimated an additional 6,257 beds would be needed in state mental institutions. The construction cost of providing these facilities might run as much as $50 million. To obtain such a large sum through voter approval of constitutional amendments might take several years. However, if the legislature authorizes GSA to boost its debt limit, voter approval would not be required and funds would be assured for early construction.

Virginia authority plans port survey

The Virginia State Ports Authority has retained the New York firm of Coverdale & Colpitts, consulting engineers, to make a survey of Virginia ports, which will be used as the basis of the authority's development program.

It will cover present and potential water-borne commerce in Virginia, existing transportation and terminal facilities, port services, markets and other factors affecting freight and ocean rates and services. Rehabilitation and expansion of Virginia ports could involve huge expenditures for construction.

Plan completion of major expressway

Toledo City Manager Arnold V. Finch, in the midst of preparing the city budget for 1953, last week sought from the Ohio State Highway Department new cost estimates and a time schedule for completion of the $21-million Toledo Expressway.

Already, he has some unofficial information to work on. Roughly $18.8-million worth of construction remains to be done on the expressway and a bridge across the Maumee River that is the key structure in the project (ENR Sept. 6, 1951, p. 26). Of this amount, about $12.8 million is scheduled to be placed under contract next year.

Construction is moving ahead fast on the Maumee River Bridge wet piers under a $2.2-million contract with Merritt, Chapman & Scott Corp. Contracts for the dry piers are expected to be let next month, and for the superstructure in April. Howard, Needles, Tammen and Bergendoff, project consultants, had a Dec. 1 filing date on plans for the land piers and trestle work.

Contracts for the Summit St. interchange are expected to be let in July, and the expressway section from Front to Weedville Sts. next November.

• **Bridge structure**—Under Vernon L. Rock, MC&S superintendent on the Maumee River Bridge project, Pier No. 1 has been completed, and construction is racing ahead to advance Piers 2 and 5 before ice and high-water make the Maumee a difficult place to work during the coming winter months.

The two piers that flank the ship channel will support a bascule-type lift span. Each measures 130 by 54 ft and rises 15 ft above the water. The other three piers, off-channel, are 84½ by 10½ ft and rise approximately 40 ft above water. The five piers contain a total of 30,000 cu yds of concrete.

Construction involves driving 57,000 lineal ft of sheet piles for the five coffer-dams, dredging 20,000 cu yds of river bottom from within the coffer-dams, and driving 42,000 ft of steel bearing piles down 75 ft to bedrock.

Protruding from the top of the structure are "breather pipes" designed by the Ohio Highway Department to help dissipate the heat generated when the concrete is poured. These are of 24-in. diameter, and are used nine to a pier, extending from the base block to the top.

ATLANTIC Pneumatic TOOLS

A New ECONOMY

for ELECTRIC—GAS—WATER COMPANIES, MUNICIPALITIES and CONTRACTORS

ATLANTIC PNEUMATIC PIPE DRIVER



Universal Joint between driving head and shank widens working angles, simplifies driving in small spaces.

Pays for Itself on the First Job. Drives pipe underground 25 feet an hour.

Up to 2" pipe through ordinary soil. Drives under highways, abutments, lawns, etc., without excavating. No delay coupling added lengths; no burred pipe ends.

NO TRENCHING, BACKFILLING OR SURFACING.

Takes Power from Standard Paving Breaker!

A SIZE FOR EVERY SERVICE

Only 3 parts: Driving point, driving head, driving shank. Weighs only 8 lbs. Standard sizes fit from 1" to 2" standard pipe. Special sizes for extra heavy pipe. Shank fits standard pavement breakers. Lasts for years. Pays Dividends over and over again. Acme of simplicity and low cost! Made from Select Steel. Specially Heat-treated to Withstand Heavy Blows.

Specialists in Tool Steels for chisels, drills, blacksmith tools and Alloy steels for axles, bolts, pins, pistons and shafts
Non-tempering tool steels for greater safety and speed

Write for descriptive folder EPD.

ATLANTIC STEEL CORP. 1775 BROADWAY, N. Y. 19

AIR LOCOMOTIVE for Tunnel Haulage



Operates at 100 p.s.i. pressures. May be recharged at any Air Valve. Prices for 24" gage (fob) factory begin at $1600

MAYO TUNNEL & MINE EQUIPMENT LANCASTER, PA.

DEPENDABLE OHIO LOCOMOTIVE CRANES

DIESEL • GASOLINE • ELECTRIC • STEAM



25 TO 50 TONS CAPACITY

THE OHIO LOCOMOTIVE CRANE CO. BUCYRUS, OHIO

ATLAS SPEED SYSTEM OF STEEL FORM CONSTRUCTION

Here's Your Solution To High Cost Form Labor

You Don't Buy New Forms For Every Poured Concrete Job

STEEL FORMS—Good for reuse again and again on job after job indefinitely without repair. Cut material costs way below wood.—Many records of 400-500 and more uses.

SPEED Steel Forms—Can be set up, stripped, cleaned and moved in way less time . . . No heavy bracing needed.

Atlas Speed Steel Forms go together with wedge clips . . . NO special fastenings or wrenches needed. NO studs on walls—Fewer posts and girts.

Let's talk it over. Just send us prints of the job. Glad to give you Layouts, Costs Studies and complete facts to fit your individual conditions. Supervision by specialists available at no extra cost to you.



The same forms can be used for walls, slabs, circular tanks, sewers, tunnels, manholes, etc.



Write Department RN for complete facts

IRVINGTON FORM AND TANK CORP.
20 Vesey Street, New York 7, N. Y.

Atlas *Labor-Saving* Concrete Forms for every Purpose

"GUNITE" *for* repairs *and* new construction

1. Dam repairs and reconstruction
2. Thin wall construction
3. Bunker and stack linings
4. Tunnels and pipe linings
5. Structural steel encasement
6. Prestressed tanks
7. Restoration defective masonry structures
8. High and low pressure grouting

phone or write us for . . .
estimates **MU. 3-1973**

Many Years Experience of Pneumatic Mortar Work

LEWIS & McDOWELL INC.
GUNITE ENGINEERS & CONTRACTORS
285 MADISON AVE., NEW YORK CITY

OWNER • ARCHITECT ENGINEER • CONTRACTOR

PLASTIMENT*-CONCRETE SATISFIES ALL FOUR BECAUSE

- MIXES BETTER
- HANDLES EASIER
- PLACES FASTER
- STAYS DURABLE

*PLASTIMENT is the chemically Retarding Densifier especially developed for concrete work which requires your guarantee. Retards set, densifies mix to provide controlled properties far superior to reference concrete. Designed for use with all types of aggregates and all methods of mixing and placing, PLASTIMENT-Concrete's ease of handling and superior results find ready on-the-job acceptance in every phase of construction. For full details, write or call.

APPROVED: PLASTIMENT and other Sika Products have been tested and approved on Federal, State and Municipal projects, and are approved under Building Codes of principal cities.

Sika
SIKA
CHEMICAL CORPORATION
35 GREGORY AVE • PASSAIC, N. J.
TELEPHONE PRescott 7-8020

BUSINESS AND FINANCE

Loan official sentenced

A sentence of five years in a federal penitentiary and a $24,000 fine was handed down last week in Federal District Court at San Diego, Calif., to the first of 24 persons indicted in connection with irregularities in financing of homes built under the Veterans Administration Insured Homes Plan.

Judge J. Frank McLaughlin, of Honolulu, who has been assigned to San Diego for the cases, imposed the sentence of Alton Bookman Jackson, who until shortly after his indictment was vice president of San Diego Federal Savings & Loan Assn. Jackson was convicted in a jury trial on eight counts of purchasing GI eligibility certificates from individual veterans at prices ranging from $100 to $300.

The case grew in part out of Teague Committee hearings in San Diego in December of 1951. Jackson also faces trial on several other indictments which also name former VA regional officials and contractors.

His sentencing came shortly after three contracting firm officials went on trial before Judge McLaughlin on charges of bribing a VA official and conspiring to bribe a VA official to influence his appraisal on a VA-insured home loan.

The contracting firm officials are Chris A. Cosgrove, Roy Russell Brockbank and Howard R. Mueller. Cosgrove is president of the Cosgrove-Brockbank-Mueller Co. which has done extensive tract home building in San Diego.

States studying school financing

School construction—and how to pay for it—was a prime topic in a number of states last week, including North Dakota, Maryland, Pennsylvania and Texas.

A bill to aid school districts in financing their building programs will be introduced in the 1953 North Dakota legislature at the request of the State Department of Public Instruction. Key to the North Dakota plan is provision for long-term loans from a state revolving fund.

The State School Equalization Fund in North Dakota now has about $13 million. The revolving fund for school construction would be started by taking $5 million out of this fund.

School districts would repay the loans over a 30-year period with money raised from 10-mill building fund levies which they would be required to impose in order to become eligible for the loans.

Meanwhile, in Maryland, it was reported that the legislature will be asked to approve an additional $30-million borrowing authority to finance school construction in Baltimore.

In Pennsylvania, the Philadelphia Board of Education announced last week that it plans to issue bonds to raise $27 million for expansion and improvement of school buildings.

Dallas, Tex., with a green light from the voters on a $24.8-million bond issue, will start construction early next year on a two-year emergency school building program.

Activity This Week

As reported to ENR
(in millions of dollars)



Contracts by type of work

	This Week	Cumulative 49 wks. 1952	1951	% chge
Waterworks	$3.0	$209.5	$199.0	+5
Sewerage	8.6	288.2	314.4	−8
Bridges	6.2	399.5	303.2	+32
Highways	26.2	1,371.6	1,121.7	+22
Earthwork, waterways	14.9	468.2	492.5	−5
Buildings:				
Public	34.7	4,209.6	1,986.1	+112
Housg., pub.	7.8	583.6	598.2	−2
Housg., priv.	80.9	2,863.6	1,926.4	+49
Commercial	72.1	784.0	583.9	+34
Industrial	46.6	2,642.9	4,004.0	−34
Unclassified	43.2	1,305.8	1,570.9	−17
Total	**$344.2**	**$15,126.5**	**$13,100.3**	**+15**

NOTE: Minimum size projects included are: Waterworks and waterway projects, $34,000; other public works, $60,000; industrial buildings, $82,000; other buildings, $300,000.

ENR indexes		Base Year = 100 1913	1926	1949
Constr. cost	Dec.	587.49	282.41	123.16
	Nov.	588.61	282.94	123.39
Bldg. cost	Dec.	425.26	229.88	120.88
	Nov.	426.04	230.30	121.10
Volume	Nov.	504	205	146

CLINTON BRIDGE CORPORATION
Division of
ALLIED
STRUCTURAL
STEEL COMPANIES

PLASTEEL—Chosen by Allied Structural Steel Companies' Clinton Bridge Corporation Division for its west loading yard building at Clinton, Iowa because "Plasteel has lived up to all of its statements in every respect."



CHOOSE
Plasteel
MICA-PROTECTED STEEL
ROOFING and SIDING

MICA makes the DIFFERENCE

Like Thousands of Other Top Industrials from Coast-to-Coast

Plasteel is designed for industry's toughest needs. With its steel core coated with asphaltic-plastics on both sides and its outer surface coated with mica, Plasteel gives you complete roofing and siding protection! Further, it's engineered for efficient erection!

Plasteel is tested and classified by Associated Factory Mutuals and Underwriters' Laboratories.

PLASTEEL PROTECTED STEEL ROOFING AND SIDING
PLASTEEL PRODUCTS CORP.
WASHINGTON, PENNSYLVANIA

ENR 12-52
Plasteel Products Corporation
Washington, Pennsylvania
Please send Plasteel Sample..... Data Sheet.....
Name..... Title.....
Company.....
Street..... City..... State.....

DUDGEON HYDRAULIC JACKS
SALES RENTALS
• CAPACITY TO 600 TONS
FOR:
• PILE TESTING
• UNDERPINNING
• BRIDGES
• PIPE PUSHING
• SOIL TESTING

Write to Dept. R
RICHARD DUDGEON INC.
789 BERGEN ST. • ST 9-4040 • BROOKLYN, N. Y.

TEST BORINGS for
• COAL
• MINERALS
• DAMS & BRIDGES
• BUILDINGS
"We look into the Earth."
PENNSYLVANIA Drilling CO.
DRILLING CONTRACTORS AND MFRS.
PITTSBURGH 20, PA.

Construction costs down as lumber prices fall

Falling lumber prices in seven cities brought small declines in ENGINEERING NEWS-RECORD's construction and building cost indexes for December.

This was the first decline in either index since mid-1951.

The construction cost index (1913 equals 100) stood at 587.49 this month, 0.2% lower than in November. The building cost index was also 0.2% lower this month as it moved to 425.26 (1913 equals 100).

The drop in lumber prices was concentrated in fir 2x4's which were reported down in 7 of the 20 cities covered. Pine 2x4's were lower in price in only two cities. The declines ranged from $1 per mftbm to $9 per mftbm.

• **Wages**—The only change in wage rates this month was a 26-cent raise for carpenters in Birmingham, Ala. The increase boosted their rate to $2.50 an hour. But more increases are in the making. San Francisco bricklayers are still negotiating for a 22.5-cent package increase. And structural ironworkers in Boston have started negotiations on a new contract which may be settled this month.

The price of cement remained the same this month. It has not changed since August. No change was reported in ENR's 3-mill average price of structural steel.

Here's the city-by-city rundown on price and wage changes this month:

Baltimore: Fir 2x4's dropped $9 to $101 per mftbm. Pine 2x4's also declined in price, going down $5 to $75 per mftbm.

Birmingham: Carpenters won a 26-cent raise; new rate, $2.50 an hour.

Boston: Fir 2x4's dropped $7 to $110 per mftbm. No change in price on pine 2x4's.

Cincinnati: Fir 2x4's went down $3.50 to $111.50 per mftbm. Pine 2x4's unchanged.

Cleveland: Fir 2x4's declined $2 to $102 per mftbm. No change in pine.

Detroit: Fir 2x4's down $6 to $105.50 per mftbm. Pine 2x4's down $1 to $101 per mftbm.

Test case filed

National Panelcrete, Inc., licensing agency for construction methods developed by William P. Neil Co., Ltd. and Buttress & McClellan, Inc., has filed suit in U. S. District Court in Los Angeles against O. K. Earl Jr., Inc., of Pasadena, Calif.

The suit charges infringement of a U. S. patent covering the Buttress & McClellan method of casting concrete building elements. The court action seeks an injunction against further infringement and general compensatory damages.

This is the first suit brought by Panelcrete and will be, in effect, a test case on enforcement of patents on tilt-up construction methods.

ENR Cost Indexes in 21 Cities
1913 = 100

City	Construction Cost 1952 Dec.	Nov.	1951 Dec.	Building Cost 1952 Dec.	Nov.	1951 Dec.
Atlanta	418	418	395	371	371	351
Baltimore	526	533	513	416	423	413
Birmingham	450	450	416	378	372	353
Boston	629	633	588	425	429	410
Chicago	661	661	624	433	433	413
Cincinnati	609	611	548	420	422	401
Cleveland	682	683	626	428	429	403
Dallas	455	455	437	382	382	371
Denver	612	612	564	462	462	425
Detroit	663	666	601	438	442	416
Kansas City	623	623	586	446	446	417
Los Angeles	610	610	569	415	415	398
Minneapolis	628	628	592	454	454	438
Montreal	512	512	484	395	395	385
New Orleans	466	466	435	397	397	379
New York	653	653	615	484	484	462
Philadelphia	636	636	582	480	480	461
Pittsburgh	607	607	557	439	439	416
St. Louis	628	631	587	447	450	427
San Francisco	559	560	527	390	391	379
Seattle	635	635	592	400	400	383

OFFICIAL PROPOSALS

Bids: December 15, 1952

DELAWARE RIVER PORT AUTHORITY
CAMDEN, NEW JERSEY
DEMOLITION AND REMOVAL OF BUILDINGS AND ERECTION OF A BRICK WALL

Sealed bids will be received for the Demolition and Removal of Buildings Numbers 529 and 531 Penn Street, Camden, New Jersey and other work on the site to be identified as Contract No. 12-A at the office of the Secretary of the Delaware River Port Authority, Administration Building, Bridge Plaza, Camden, New Jersey until 1:30 P.M. Eastern Standard Time, Monday, December 15, 1952 and then and there will be publicly opened and read.

A more complete description of the work and full information for bidders are given in the Contract Documents and Specifications for this Contract, which may be obtained upon a deposit of $10.00 which will be remitted upon receipt of bid or the return in good condition of the copies so taken within thirty days after the opening of bids.

Each proposal must be accompanied by a certified or cashier's check in the sum of $3,000 payable to Delaware River Port Authority and drawn upon a National or State bank or trust company having an office either in Philadelphia, Pennsylvania or Camden, New Jersey and the Surety's consent must be shown. The bidder to whom the contract is awarded will be required to furnish a Performance and Labor and Materialmen's Bond in the sum of 100 percent, but in no case less than $25,000.

The Authority will afford prospective bidders an opportunity to inspect the work to be done.

The Authority reserves the right to waive any informalities in the bids received; to reject any or all bids; and to award the contract only to those experienced in this class of work and to the bidder whose proposal is deemed by the Authority to be most advantageous to the public interest.

DELAWARE RIVER PORT AUTHORITY
JOSEPH K. COSTELLO, SECRETARY

Bids: January 8, 1953

The Construction of the Grant Park Garage (North) at Monroe and Randolph Streets and Michigan Avenue Chicago, Illinois

THE CHICAGO PARK DISTRICT will receive bids until eleven (11:00) o'clock A.M., prevailing Chicago Time, on January 8, 1953, for the furnishing of materials, equipment, labor and services for the construction of the Grant Park Garage (North) at Monroe and Randolph Streets and Michigan Avenue, Chicago, Illinois, in accordance with the provisions of the Form of Proposal, Requirements for Bidding and Instructions to Bidders, Drawings, and Specifications, all of which are on file in, and may be obtained at the office of the undersigned.

Copies of said documents may be obtained by depositing with the undersigned the sum of Fifty Dollars ($50.00) for each set, which deposit will be refunded upon return of the documents in good condition within thirty (30) days after the date upon which bids are opened.

The Proposal shall be accompanied by a certified check in the amount of Three Hundred Thousand Dollars ($300,000.00) as a bid deposit.

The work includes, but is not confined to the following:

Construction of Grant Park Garage (North), Underground Utilities, Restoration of Park Facilities, and All Miscellaneous Work pertinent thereto. Among items included in the construction of the two level underground garage are the following major items:

1. Fifty Five Thousand Five Hundred (55,500) cubic yards of concrete
2. Three Hundred and Fifty Thousand (350,000) cubic yards of general excavation
3. Thirty Three Hundred (3,300) tons of reinforcing steel
4. Eight Hundred (800) tons of steel sheeting

The CHICAGO PARK DISTRICT reserves the right to reject any or all Proposals or to accept any Proposal which, in its judgment will be for the best interest of the public.

Only bids submitted in conformance with the provisions of the Requirements for Bidding and Instructions to Bidders will be considered.

CHICAGO PARK DISTRICT
By C. Wagner, Director of Purchases
Administration Building
425 E. 14th Boulevard
Burnham Park
Date: 12/4/52. Chicago 5, Illinois

OFFICIAL PROPOSALS

APPEAR HERE EACH THURSDAY. PROPOSAL ADVERTISEMENTS ACCEPTED UP TO 10:30 A.M. FRIDAY FOR THE ISSUE DATED THE FOLLOWING THURSDAY. SEND ALL ADVERTISEMENTS TO CLASSIFIED ADVERTISING DIVISION, 29TH FLOOR, McGRAW-HILL PUB. CO., INC., 330 W. 42 ST., N. Y. 36, N. Y.

Bids: January 14, 1953

CITY OF NEW LONDON, CONNECTICUT
SEWAGE PUMPING STATIONS, FORCE MAINS, SEWERS AND APPURTENANCES

Sealed bids for the construction of Sewage Pumping Stations, Force Mains, Sewers and Appurtenances for the City of New London, Connecticut, will be received at the office of the City Purchasing Agent, Municipal Building, New London, Connecticut, until 2:30 P.M., Eastern Standard Time, on January 14, 1953, and then at said office publicly opened and read aloud.

The Information for Bidders, form of bid, form of contract, plans, specifications and form of performance bond, may be examined at the office of the City Purchasing Agent, New London, Connecticut, and at the office of Keis & Holroyd, Consulting Engineers, 257 Broadway, Troy, New York. Copies thereof may be obtained at the said offices of the City Purchasing Agent or Keis & Holroyd upon payment of $25.00 for each set. Any bidder upon returning such set promptly and in good condition, will be refunded his payment, and any non-bidder upon so returning such set within 30 days, will be refunded $20.00.

The City of New London, Connecticut reserves the right to waive any informalities in, or to reject any, or all bids.

A certified check made payable to the order of the City of New London, Connecticut, in the amount of five per centum (5%) of the bid must be deposited by each bidder with his bid as a guarantee that in case the contract is awarded to him, that he will, within five (5) days thereafter execute such contract and furnish a satisfactory bond. On failure to do so he shall forfeit the deposit as liquidated damages, and acceptance of the bid will be contingent upon the fulfillment of this requirement by the Bidder.

The successful Bidder will be required to furnish a performance bond satisfactory to the City of New London, Connecticut in the amount of the contract, and having as surety thereon such surety company or companies as are acceptable to the City of New London, Connecticut.

The work will be divided into three sections as follows:

Section I —Force Mains, Gravity Sewers and Appurtenances
Section II —Pumping Stations
Section III—Outfall Sewer

The work may be let as one contract or separate contracts may be let for each of the three sections except that manufacturers of cast iron pipe, cast iron specials, valves and valve boxes may bid directly to the City for furnishing these materials for Sections I and III.

No bidder may withdraw his bid within 40 days after the date set for the opening thereof. Any bid may be withdrawn prior to the above scheduled time for the opening of bids or authorized postponement thereof.

THE CITY OF NEW LONDON, CONNECTICUT
By WILLIAM RUDDY, Purchasing Agent
Dated: November 24, 1952
Keis & Holroyd, Consulting Engineers
257 Broadway, Troy, New York

Bids: December 15, 1952

Bridge Construction

WASHINGTON SUBURBAN SANITARY COMMISSION
CONTRACT NO. 1207-W

Sealed proposals for constructing a 210 ft., 3 span girder bridge with 1,700 ft. of approach roads with necessary piling, riprap, etc., on the Edmarst Mt. Zion Church Road over the Patuxent River, Montgomery County, Maryland, will be received at the office of the Washington Suburban Sanitary Commission, Hamilton Street, Hyattsville, Maryland, until Monday, December 15, 1952 at 2:00 P.M., Eastern Standard Time, at which place and time they will be publicly opened and read.

Plans and specifications may be obtained from the office of the Chief Engineer of the Commission, Hyattsville, Maryland, upon deposit of $25.00, which deposit will be returned to bidders or to those returning plans and specifications in good condition.

Raymond W. Bellamy
L. S. Ray
J. Norman Ager
Commissioners

Attest:
James B. Parkhill
Secretary-Treasurer

Bids: December 30, 1952

Gasoline-Engine Generator Sets

GASOLINE-ENGINE GENERATOR SETS
CONTRACT 437

SEALED BIDS will be received by the Board of Water Supply, at its offices, thirteenth floor, 120 Wall Street, New York City, until 11:00 A.M., Eastern Standard Time, on Tuesday, December 30, 1952, for Contract 437, for furnishing, testing, delivering and unloading gasoline-engine generator sets with switchgear and appurtenances for the West Branch and the Kensico South effluent chambers of the Delaware Aqueduct, all as set forth in the specifications.

No bid will be received and deposited unless accompanied by a certified check upon a National or State bank, drawn and made payable to the order of the Comptroller of The City of New York, in the amount of two thousand dollars ($2,000.00), for the proper execution of the contract.

At the above place and time the bids will be publicly opened and read. Pamphlets containing information for bidders, forms of bid and contract, specifications, requirements as to surety, etc., can be obtained in Room 1316 at the above address, upon application in person or by mail, by depositing the sum of five dollars ($5.00) in cash or its equivalent for each pamphlet. Within 30 days following the award of contract or rejection of bids, the full amount of such deposit will be refunded for each pamphlet submitted as a bid and a refund of four dollars ($4.00) will be made for each other pamphlet returned in acceptable condition. For further particulars, apply at the office of the Chief Engineer at the above address.

IRVING T. A. HUIE, President, RUFUS E. McGAHAN, EDWARD C. MAGUIRE, Commissioners, Board of Water Supply; BETTY COHEN, Acting Secretary.

Bids: December 16, 1952

Wabash Memorial Bridge Over the Wabash River Near Mt. Vernon, Indiana

Sealed proposals will be received at the office of the Chairman, of the Indiana State Toll Bridge Commission, in Room 302, Indiana State House, Indianapolis, Indiana, until 10:30 A.M., Central Standard Time, on the 16th day of December, 1952. Said proposals will then be immediately publicly opened and read.

Proposals are for furnishing the materials and completely constructing a portion of a vehicular bridge over the Wabash River near Mt. Vernon, Indiana. It is intended that the award will be made for Contract I, "Bridge Substructure and Superstructure", and Contract II, "Toll House and Office Building"; to one or two bidders in separate contracts.

The bridge, together with approach roads, will provide a connection between Indiana State Route 62 and Illinois State Route 141. The approach roads are not a part of the work included in these contracts.

The bridge will serve highway traffic only and is to have a concrete roadway of 26'-0" clear width with 2'-0" safety curbs. The main spans will be through trusses of the three-span continuous tied-arch type, spanning openings of 283½ feet, 441 feet and 283½ feet. The approach spans will consist of four units of three-span continuous girders, each span being 115' center to center of bearings and each unit totaling 345' in length. All substructure units will be reinforced concrete with the approach piers supported on steel bearing piles and the main piers founded on rock, approximately 29' below mean low water elevation.

In addition to the bridge construction, a toll house and office building will be constructed adjacent to the Indiana Highway approach road.

Final estimates indicate that the construction will require approximately 2,125 tons of structural carbon steel, 340 tons of structural low-alloy steel, 10,300 cubic yards of concrete, 400 tons of reinforcing steel and 12,200 lineal feet of steel piling.

The Bureau of Public Roads, U. S. Department of Commerce, the claimant agency under the National Production Authority has advised that the project meets the criteria of essentiality and is eligible for an allotment of controlled materials. Contractors requesting plans will be advised of the quarterly allocations as soon as this information is available. Steel sheet piling for temporary use will not be included in this allocation as it can be purchased or rented by the Contractor as equipment.

Proposals shall be submitted in sealed envelopes addressed to the Chairman of the Indiana State Toll Bridge Commission, Room 302, Indiana State House, Indianapolis, Indiana.

Copies of the plans, proposals and special provisions are on file at the following addresses:

1. Walter G. Koch, Chairman
   Indiana State Toll Bridge Commission
   c/o International Steel Corporation
   Evansville 7, Indiana
2. Sverdrup & Parcel
   Consulting Engineers
   118 Syndicate Trust Bldg.
   St. Louis 1, Missouri
3. F. W. Dodge Corporation
   American Building
   30 East Central Parkway
   Cincinnati 2, Ohio
4. F. W. Dodge Corporation
   Architects & Builders Bldg.
   333 North Pennsylvania
   Indianapolis 4, Indiana
5. F. W. Dodge Corporation
   Vaughan Building
   300 West Main
   Louisville 2, Kentucky

These plans, proposals and special provisions will be furnished prospective bidders at the office of Sverdrup & Parcel, or copies will be forwarded upon receipt of request for same. In either case, the following charges will be made for these documents.

Bridge Substructure and Superstructure—Contract I $20.00
Toll House and Office Building—Contract II 5.00

Checks should be made payable to "Sverdrup & Parcel." No refunds or credit will be made for material returned.

Proposals should be made upon Standard Forms furnished by the Indiana State Toll Bridge Commission. Bidding proposals will be furnished no later than 3:30 A.M., Central Standard Time, on the day of letting.

The right is reserved to reject any or all bids, to advertise for new bids, to waive technicalities or to award on any bid that is most advantageous to the Commission.

INDIANA STATE TOLL BRIDGE COMMISSION
Walter G. Koch, Chairman
November 24, 1952

U. S. Government

Department of Commerce, Bureau of Public Roads, November 24, 1952. SEALED BIDS will be received at the office of the Division Engineer, Bureau of Public Roads, 1440 Columbia Pike, Arlington, Virginia, until 11:00 a.m., E.S.T., DECEMBER 19, 1952, for Project 1B5-C4, Baltimore-Washington Parkway, Prince Georges County, Maryland. 3.151 miles Concrete Paving and other work from Defense Highway to point about ½ mile north of Good Luck Road. The approximate quantities of the more important items are: 100,000 cu. yd. Borrow for Topping, 90,000 sq. yd. Reinforced Cement Concrete Pavement, and 5,200 units of Seeding. Minimum wage rates have been fixed as required by law. Plans, specifications, and proposal forms are available upon request at the address given above. H. J. Spelman, Division Engineer.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Invitation No. DS-3848) will be received at Denver, Colorado, until December 30, 1952, for furnishing steel structures for transformer circuits and switchyard at Folsom Power Plant and transformer structures at Nimbus Power Plant for Folsom Unit, American River Division, Central Valley Project, California. Delivery is desired within 270 days. For particulars, address Bureau of Reclamation, Building 53, Denver Federal Center, Denver, Colorado.

MICHAEL W. STRAUS, Commissioner

OFFICIAL PROPOSALS

Bids: December 18, 1952

New York State Road Work

NOTICE TO CONTRACTORS: STATE DEPARTMENT OF PUBLIC WORKS, ALBANY, N. Y.,—Pursuant to the provisions of the Highway Law, and Article 2, Title 9 of the Public Authorities Law, sealed proposals will be received until ten-thirty o'clock A.M., eastern standard time on the 18th day of December 1952, by Henry A. Cohen, Director, Bureau of Contracts and Accounts, 14th Floor, The Governor Alfred E. Smith State Office Building, Albany, N. Y., for the following projects:

County	Contract No.	Name	Miles	Type	Deposit	Estimated Cost of Work
		DISTRICT No. 3				
		William Robinson, District Engineer, Weigh Lock Building, Syracuse, New York				
Cayuga & Seneca	O. T. 52-23P R. C. 52-120	New York State Thruway Ontario section, sub. 3 Tyre—3¼ mile west of Montezuma) Halsey Corners—Savannah Pt. 1 S. H. 8323	4.15 Thy. 0.65 Acc.	8" & 9" Cem. Conc. Pavt. 2 @ 25' Var. Wide=4.78 Mi. Gr. Sep. Alpha I Beam 212-21' Dk. Plate Girder Bridge 620' Twin Conc. Bx. Br. 40'	$215,000 Plans $50	$3,916,000
		DISTRICT No. 5				
		C. R. Waters, District Engineer, 65 Court St., Buffalo, New York				
Erie	O. T. 52-22 S. T. 52-34	New York State Thruway Ontario Section, sub. 14 (Transit Rd. Ransom Rd.) Transit Rd. Interchange Gunville Rd.; Marginal Rds.	5.46 Thy. 3.46 Acc.	2 Crse Cem. Conc. Pavt. 2 @ 25' Var. Wide=6.72 Mi. Asph. Conc. Type 1A Opt.=0.03 Mi. Bit. Mac. Ty. 1=1.11 Mi. Bit. Treated Gravel=0.94 Mi. Misc. Work=0.12 Mi. 4 Gr. Seps. Alpha I Beam 201.5', 155.01', 145.54', and 225.9' 1 Gr. Sep. (R.R.) Alpha I-Beam 252'	275,000 Plans $50	5,000,000

Maps, plans, specifications and proposal forms may be seen and obtained at the office of the State Department of Public Works, Bureau of Contracts and Accounts, Albany, N. Y., and at the office of the District Engineers noted above, and may also be seen at the office of the State Department of Public Works, 270 Broadway, New York City.

The deposit for Plans and Proposal Forms for each contract is indicated above. A refund will be made in full to bidders for return of one set, in good condition, within 30 days of award, or rejection of bids; refund for all other sets in good condition, similar period, will be 50% of deposit.

Special attention of bidders is called to "General Information for Bidders" in the proposal, specification, and contract agreement. Award of a contract is subject to the "Controlled Materials Plan" of the National Production Authority as well as to regulations issued thereunder.

Proposal for each contract must be submitted in a separate sealed envelope with the name and number of the contract plainly endorsed on the outside of the envelope. Each proposal must be accompanied by draft or certified check payable to the order of the "State of New York, Commissioner of Taxation and Finance" for the sum as specified in the advertisement and the proposal. The retention and disposal of the bidding check, the execution of the contract and bonds shall conform to the provisions of the Highway Law, as set forth in "Instructions to Bidders."

The right is reserved to reject any or all bids.

B. D. TALLAMY
Supt. of Public Works

Bids: December 15, 1952

New York State Road Work

NOTICE TO CONTRACTORS: STATE DEPARTMENT OF PUBLIC WORKS, ALBANY, N. Y.,—Pursuant to the provisions of the Highway Law, and Article 2, Title 9 of the Public Authorities Law, sealed proposals will be received until ten-thirty o'clock A.M., eastern standard time on the 15th day of December 1952, by Henry A. Cohen, Director, Bureau of Contracts and Accounts, 14th Floor, The Governor Alfred E. Smith State Office Building, Albany, N. Y., for the following project; in ROCKLAND & WESTCHESTER COUNTIES: J. S. BIXBY, DISTRICT ENGINEER, PLEASANT VALLEY ROAD, POUGHKEEPSIE, N. Y.

Contract No.	Type	Name of Highway and Miles	Deposit for Plans	Bid Deposit	Department Estimate
H T. 52-4	Bridge Superstructure (Tied Steel Arch, Deck Girders & Alph. I-Beam) Including Steel Towers	New York State Thruway-Hudson Section, Subd 9B (Tappan Zee Bridge) 3 miles	$100	$1,800,000	$35,764,000

Maps, plans, specifications and proposal forms may be seen and obtained at the office of the State Department of Public Works, Bureau of Contracts and Accounts, Albany, N. Y., and at the office of the District Engineer noted above, and may also be seen at the office of the State Department of Public Works, 270 Broadway, New York City.

The deposit for Plans and Proposal Forms for each contract is indicated above. A refund will be made in full to bidders for return of one set, in good condition, within 30 days of award, or rejection of bids; refund for all other sets in good condition, similar period, will be 50% of deposit.

Special attention of bidders is called to "General Information for Bidders" in the proposal, specification, and contract agreement. Award of a contract is subject to the "Controlled Materials Plan" of the National Production Authority as well as to regulations issued thereunder.

Proposal for each contract must be submitted in a separate sealed envelope with the name and number of the contract plainly endorsed on the outside of the envelope. Each proposal must be accompanied by draft or certified check payable to the order of the "State of New York, Commissioner of Taxation and Finance" for the sum as specified in the advertisement and the proposal. The retention and disposal of the bidding check, the execution of the contract and bonds shall conform to the provisions of the Highway Law, as set forth in "Instructions to Bidders."

The right is reserved to reject any or all bids.

B. D. TALLAMY
Supt. of Public Works

U. S. Government

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-3845) will be received at Ephrata, Washington until December 30, 1952, for furnishing labor and materials for earthwork, pipe lines, and structures for Area P-8 laterals, sublaterals, and wasteways, Potholes East Canal Laterals, Columbia Basin Project, Washington. Location: West of Ellopia, Washington. Principal items are: 490,000 cu. yds. excavation; 1,930 cu. yds. concrete; 31,000 lin. ft. concrete pipe; 9 outdoor-type pumping plants; 73,000 lbs. gates and other metalwork; and other work. Completion time 410 days. For particulars, address Bureau of Reclamation, Ephrata, Washington; or Building 53, Denver Federal Center, Denver, Colorado.

MICHAEL W. STRAUS, Commissioner.

OFFICIAL PROPOSALS

Bids: December 18, 1952

Construction of Turnpike

WEST VIRGINIA TURNPIKE COMMISSION

ADVERTISEMENT FOR PROPOSALS

NOTICE OF RE-ADVERTISEMENT

Sealed proposals will be received by the West Virginia Turnpike Commission for:

CONTRACT NO. 10

The work to be done under this Contract consists in performing the required grading and drainage for approximately 3.0 miles of the West Virginia Turnpike including the relocation of approximately 0.2 miles of side roads. This work is located between the North Portal of the Standard Tunnel, mile 68.3, and the Town of Miami, mile 71.3, Kanawha County, West Virginia, and is in connection with the construction of the West Virginia Turnpike in the State of West Virginia.

The principal items of work include:

	Approximate Quantity
Clearing and Grubbing	82 Acres
Excavation (all types)	1,650,000 C.Y.
Embankment	732,000 C.Y.
Concrete	3,600 C.Y.
Reinforcing Steel	204,000 Lbs.
Culvert Pipes and Underdrains —3600 Pipe	4,000 Lin. Ft.
Concrete Cribbing	16,400 Cu. Ft.

Proposals will be received at the office of the West Virginia Turnpike Commission, 1340 Wilson Street, Charleston 5, West Virginia until 9:00 A.M. Eastern Standard Time, and thereafter at the House of Delegates Chamber, State Capitol, Charleston, West Virginia until 10:00 A.M. Eastern Standard Time, on December 18, 1952, at which time and place said proposals will be publicly opened and read.

Contract documents may be seen and may be inspected by prospective bidders during office hours, after November 20, 1952, at the office of Howard, Needles, Tammen & Bergendoff, 804 Greenbrier Street, Charleston, West Virginia, and at the offices of the Engineers, Gannett, Fleming, Corddry & Carpenter, Inc., 123 Forster Street, Harrisburg, Pennsylvania, and at 6218 Penn Avenue, Pittsburgh 6, Pennsylvania, and at Chesapeake, West Virginia.

Contract plans and specifications will be furnished for Fifteen Dollars ($15.00) for each set, which is not refundable, upon application to Howard, Needles, Tammen & Bergendoff, 804 Greenbrier Street, Charleston, West Virginia, Mailing Address: P. O. Box 5266, Capitol Station, Charleston, West Virginia. Cross Sections are bound separately and will be furnished for Forty Dollars ($40.00) for each set. Make checks payable to Howard, Needles, Tammen & Bergendoff.

Proposals must be made upon the proposal forms furnished by the Commission in the manner designated in the Specifications, and must be enclosed in sealed, special addressed envelopes bearing the name and address of the bidder and the number of the contract on the outside, and must be accompanied by a CASHIER'S or CERTIFIED CHECK or PROPOSAL BOND in favor of the West Virginia Turnpike Commission FOR NOT LESS THAN FIVE (5) PER CENT OF THE AMOUNT OF THE PROPOSAL, but not less than $500.00 nor more than $200,000.00 and must be delivered at the place designated above on or before the day and hour named. Copies of the proposal form and proposal bond form to be used for submitting proposals, and of the special addressed envelope are furnished in detached form with the contract documents.

The contract will be awarded or the proposals rejected within thirty (30) days from the date of opening proposals. The right is reserved to reject any or all proposals, and to waive any or all formalities.

WEST VIRGINIA TURNPIKE COMMISSION
D. HOLMES MORTON, Chairman

November 20, 1952

CONTRACTORS WATCH THIS SECTION
for New Projects
Publish your announcements thru the "Proposal Section" of Engineering News-Record and get their bids.

WANTED

An Alert Mechanical Engineer with Some Knowledge of Electrical Engineering . . . Must Be a Good Calculator . . .

PHILIPS & DAVIES, INC.
KENTON, OHIO

SALARIED POSITIONS $3,500—$35,000

We offer the original personal employment service (established 42 years.) Procedure of highest ethical standards is individualized to your personal requirements. Identity covered; present position protected. Ask for particulars.

R. W. BIXBY, Inc., 272 Dun Bldg., Buffalo 2, N.Y.

SEARCHLIGHT SECTION

(Classified Advertising)

EMPLOYMENT: BUSINESS: **"OPPORTUNITIES"** :EQUIPMENT :USED OR RESALE

UNDISPLAYED RATE

$1.50 a Line, minimum 3 lines. To figure advance payment count 5 average words as a line.
Discount of 10% is allowed if full payment is made in advance for 4 consecutive insertions.
POSITION WANTED and Individual Selling Opportunity undisplayed rate is one-half of above rate, payable in advance.
Box Numbers in care of our New York, Chicago and San Francisco Offices count as one additional line.
NEW ADVERTISEMENTS: Address N. Y. office, 330 W. 42nd St., N. Y. 36, N. Y., for December 18th issue, closing December 8th.

Replies are forwarded each day as received at each of the offices mentioned without additional charge.
EQUIPMENT WANTED or FOR SALE Advertisements acceptable only in Displayed Style.

DISPLAYED RATE

The advertising rate $17.10 per inch for all advertising appearing on other than a contract basis. Contract rate quoted on request.
An advertising inch is measured ⅞ inch vertically on one col., 3 col.—30 inches to a page. E.N.R.

REPLIES (Box No.): Address to office nearest you
NEW YORK: 330 W. 42nd St. (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITIONS VACANT

COMPUTOR FOR established concern, experienced in subdivision and property surveys, location Western Suffolk County, Long Island, N. Y. Write Stating salary requirements. P-6071, Engineering News-Record.

DESIGN ENGINEERS—Men having experience in design and preparation of drawings and reports for highway, sanitary sewer and municipal-type storm drainage systems including inlets, collection systems, interceptors and culverts. Good pay for qualified men with training and experience. Opportunity for advancement. Furnish full information regarding education, training and experience, age, references and salary required. Replies strictly confidential. P-6036, Engineering News-Record.

DESIGNERS-DRAFTSMEN, for highways and bridges. Excellent opportunities. Be prepared to submit complete experience record. Ammann & Whitney, Consulting Engineers, 76 Ninth Ave., New York 11, N. Y.

EXPERIENCED ESTIMATOR and Chief Engineer between the ages of 35 and 45, to take complete charge of office—make quantity take-offs—help price—buy—expedite and do some field supervision. All our work is competitive. We specialize in industrial, commercial and public works. Only experienced and high-grade men need apply. Permanent job for right man. Excellent salary and bonus. Office located in Ohio. Send qualifications, experience. Photograph optional. P-5978, Engineering News-Record.

PLUMBING ESTIMATOR—Experienced man capable of assuming responsibility to take charge of estimating and contract work. This is an exceptional opportunity with an old established plumbing contractor located in Connecticut. Write fully stating experience, reference, education, marital status and salary details. P-5991, Engineering News-Record.

QUANTITY SURVEY Man with thorough knowledge of building construction details to act as assistant to chief. Must have substantial experience with General Contractors, public Work preferred. Write full details. Do not bother to answer unless you have proper background. Will pay $10,000 per annum to right man. Location Washington, D. C. P-6116, Engineering News-Record.

SURVEY PARTY Chiefs and Instrumentmen—Men having experience in Topographic, Property and Utility layouts. Good pay for qualified men with training and experience. Opportunity for advancement. Furnish full information regarding education, training and experience, age, references and salary required. Replies strictly confidential. Dept. of Public Works, Baltimore County, Towson 4, Maryland.

WANTED: CONSTRUCTION Superintendent for industrial and commercial construction; located Middle Atlantic States. Send full particulars: education, experience and salary in first letter to Lewis C. Bowers & Sons, Inc., 341 Nassau St., Princeton, N. J. Atten: J. R. Pelikan.

WANTED: CONSTRUCTION Engineers. Minimum 5 years' experience on industrial construction. Ages 30-45. Send full particulars: education, experience and salary in first letter to Lewis C. Bowers & Sons, Inc., 341 Nassau St., Princeton, N. J., Atten: J. R. Pelikan.

POSITIONS WANTED

CIVIL ENGINEER. 18 years experience in heavy construction. Dams, powerhouses, buildings and other concrete structures. Preparations of estimates, bids, schedules, cost reports, etc., and active supervision of engineering and/or construction of project. Prefer position as chief engineer or project manager with prime contractor. Foreign or domestic. Complete resume upon request. PW-6068, Engineering News-Record.

GEOLOGIST—UNIV grad. Single. Age 29. 1½ yrs. in analytical chemistry, 5 years in publications—desires a position in which these qualifications can be used—Midwest preferred. PW-6146, Engineering News-Record.

STRUCTURAL ENGINEERING
ARCHITECTURAL ENGINEERING
OUR COURSES of instruction by mail HAVE HELPED THOUSANDS to better positions and to pass State Board Examinations. Forty-first year. Write today.
WILSON Engineering Corp.
College House Offices - HARVARD SQUARE, CAMBRIDGE, MASS.

SUPERINTENDENTS AND PROJECT MANAGERS TRAINING COURSE
All instruction by mail. Send today for sample lesson and complete details
GEO. E. DEATHERAGE & SON
5 E. Preston St. Baltimore 2, Maryland

POSITIONS WANTED

CIVIL ENGINEER, 25, married, desires position in California. 1 year experience Govt. Agency —2 years field and office work with general contractor. PW-6157, Engineering News-Record.

CIVIL ENGINEER, 42, German, presently employed U. S. Air Force, building Air Fields and other heavy construction in Germany speaks several languages, can take complete charge of projects, will go anywhere in U.S.A. or other foreign countries. Excellent references. PW-6163, Engineering News-Record.

CIVIL ENGR. 30, married, B.S. C.E. Purdue Univ. 1948, 3 yrs. experience as Field Engr. in Strip mine, 1 year service with Army Engrs. in Korea. Desires position with contracting firm. Location preferred Southeast. Available January 1. PW-6174, Engineering News-Record.

CONSTRUCTION ENGINEER C.E. graduate, age 52, long administrative experience all phases large scale general contract building in Field and Office. Employed seeks new connection. PW-6137, Engineering News-Record.

CONSTRUCTION ENGINEER, C.E. graduate, age 34. Experienced on large construction projects—Dams, Pipe Lines, Atomic Energy Projects, etc. PW-6090, Engineering News-Record.

CONSTRUCTION SUPERINTENDENT, concrete pipe manufacturer, considerable experience. PW-6086, Engineering News-Record.

ENGINEER, GRADUATE C.E.; 30; married. 7 years heavy construction, excavation, foundations, public works. Experienced administration, estimating, office-engineering. Knowledge home-building and real estate. N. Y. Employed, will relocate for responsible position with future. PW-6143, Engineering News-Record.

EXECUTIVE ENGINEER, long experience, management large company, heavy construction docks, foundations, tunnels, difficult subaqueous structures, etc. PW-6428, Engineering News-Record.

POSITIONS WANTED

REGISTERED CIVIL Engineer with background of construction supervision, general management, promotion and heavy equipment sales. Presently employed as manager of a general construction company. Midwest location preferred. PW-5975, Engineering News-Record.

SANITARY ENGINEER, B.E. (Civ.), M.S. (San.), 4 years experience, design and operation, water treatment and distribution, sewerage and sewage treatment. PW-6070, Engineering News-Record.

SUPERINTENDENT OF Maintenance & equipment, 28 years experience as operator, mechanic, foreman and super. of equipment. Sober, reliable. PW-6032, Engineering News-Record.

PART TIME WORK WANTED

CONSTRUCTION BID Estimates and quantity surveys for Architects, Engineers and Contractors in the Cleveland Area. Write PTWW-6005, Engineering News-Record.

BUSINESS OPPORTUNITY

Investment Offered—

Civil Engineer, young, Lic. P.E.-N.Y.; B.S.-M.I.T.; M.S.-Columbia. Seven years varied experience teaching, consulting, waterfront structures, public works. Desires association with Civil or Consulting firm with or without immediate investment. BO-6105, Engineering News-Record.

• WANTED •
INDUSTRIAL PLANTS
Will arrange thru purchase of (1) Capital stock, (2) Assets, (3) Machinery and equipment, whole or in part—Personnel usually retained, strict confidence. **Box 1351,** Church St. Sta., New York 8, N. Y.

ATTENTION CONTRACTORS:
List your equipment with us for quick sales. We also store your equipment in our yard for a small fee until sold if you desire.
Consult us for your equipment needs.
FINEST CONSTRUCTION & EQUIPMENT CORP.
147-47 Farmers Blvd., Jamaica 5, N. Y.
Tel. LA 7-3637

NOTICE
EXCAVATING CONTRACTORS
275,000 CUBIC YARDS OF DIRT TO MOVE
We are accepting bids on the removal of 275,000 cubic yards of dirt to be moved on our premises. Maximum haul 1000 yards. Ten acres of timber clearing to be done. Bids due at our office December 15, 1952. Work to start not later than January 1, 1953 and to be fully completed in approximately ninety (90) days.
If interested please write or phone for full specifications of cuts and fills.
FORT LINCOLN CEMETERY
3201 Bladensburg Road Washington 18, D. C.
Lincoln 3-3578

are you a

Mechanical DRAFTSMAN?

if so, you'll enjoy working with . . .

GENERAL ELECTRIC

at HANFORD WORKS

Richland, Wash., Atomic Energy Plant





- Top Salaries
- Challenging, Steady Work
- Good Working Conditions and Drafting Equipment
- Liberal Benefit Plans

You'll also enjoy Richland's sunny, dry climate . . . the superb scenery of the Pacific Northwest. And your work . . . steady, interesting and challenging . . . will be in the new field of Atomic Energy.

Priority housing is yours, also. Moderate rentals, variety of homes to choose from in Richland, 24,000 population. Dormitories for single people.

General Electric Company's benefit plans . . . health and life insurance, stock bonus plan, paid vacations and holidays, retirement plan . . . all add up to Good Employment.

WRITE TODAY for additional information and application.

GENERAL ELECTRIC

Richland, Washington

ENGINEERS WANTED

STRUCTURAL ENGINEER

Graduate Engineer, 10 years experience, design of heavy structures with emphasis on long span bridges.

ELECTRICAL ENGINEER

Graduate Engineer, minimum 5 years experience, power distribution, building services and communications.

MECHANICAL ENGINEER

Graduate Engineer, minimum 10 years experience in design of mechanical building services and distribution, boiler houses and steam distribution. Some experience in heavy machinery desirable but not essential.

LIBERAL SALARIES

commensurate with experience and ability. Vacations with pay and other benefits.

SUBMIT COMPLETE RESUME

of education and experience, salary requirement, references, and availability date with first letter.

PALMER & BAKER, INC.

Consulting Engineers
Architects - Naval Architects
Marine Engineers

P. O. BOX 346

MOBILE ALABAMA

SALESMAN

Call on heavy duty truck fleets. Contractors and industrial accounts in Bucks County, Penna., and southern New Jersey counties. Representing distributor of air cooled and liquid cooled gasoline and diesel engines and electric plants. Must have practical experience on internal combustion engines and able to do necessary field service. Good successful sales record required. Salary, expenses and commission. Permanent, good field with well established company. Replies must be detailed, give age, education, experience, positions held, earnings and availability.

SW-5950, Engineering News-Record
330 W. 42 St., New York 36, N. Y.

COST ENGINEER

Unusual opportunity for Cost Engineer on major plant project in California. Requires cost and construction experience, but principal qualifications are intelligence, interest and ambition. Functions include unit cost analysis, special cost reports and cost forecasts. A responsible position and one offering opportunity for advancement in an expanding, progressive organization.

Write giving complete qualifications, references and salary requirements. Your reply will be held confidential.

BECHTEL CORPORATION
220 Bush Street
San Francisco, California

The Tennessee Valley Authority wants Civil, Structural, and Office Engineers and Estimators. The work is design and construction of large steam electric and hydroelectric projects and transmission systems. Salaries start at $3700-$4450 and $5325 for 40-hour week. All jobs carry automatic within-grade increases for satisfactory service, liberal vacation leave, sick leave, and retirement benefits. Design and estimating jobs are in Knoxville and Chattanooga, Tennessee. Field and office engineering jobs are at construction sites in the Tennessee Valley area and at Paducah, Kentucky. Write the

TENNESSEE VALLEY AUTHORITY

Division of Personnel

KNOXVILLE TENNESSEE

CHEMICAL ENGINEERS AND CHEMISTS FOR APPLICATION RESEARCH IN Fluorocarbon Polymers WITH Leading Organization in Petroleum & Petrochemical Fields

OPPORTUNITY to join a staff of highly trained and experienced scientists where initiative and ability form the basis for salary and increasing responsibility. The work involves the development of industrial and commercial outlets for new products, and these positions can lead to important jobs in technical service or chemical sales.

QUALIFICATIONS—3 to 5 years' experience in protective coatings, rubber compoundings, films and fibers. Ph. D. helpful but not essential. Applicants should have a pleasing personality and be able to deal with customers on a high technical level.

LOCATION—These research laboratories are conveniently located in metropolitan New Jersey.

(Two 1952 graduates interested in this type of work will be considered for our training program.)

Please send complete resume of background and experience and include salary desired. Interviews will be arranged promptly for qualified applicants.

Box #197, Room 1201
230 West 41 St. New York 36, N. Y.

ENGINEERS and DESIGNERS

Arthur G. McKee and Company has permanent openings in their Cleveland, Ohio and Tulsa, Oklahoma offices for qualified men as:

Instrument Specifications Engineers
Piping Designer
Pressure Vessel Designers

with experience in petroleum refinery design.

Good hourly rates plus overtime
45 hours—5 days per week
Annual profit-sharing bonus
No age limitation

These opportunities are well worth your while to investigate.

Write giving details of background and experience.

ARTHUR G. McKEE & CO.
2300 Chester Ave. Cleveland 1, Ohio

CONSTRUCTION ESTIMATOR

Qualified Estimator, thoroughly experienced in estimating and quantity take-off. Background in power plant work, process piping and general industrial construction absolutely essential. State education, experience, qualifications and salary requirements. All applications will be acknowledged.

P-5997, Engineering News-Record
330 W. 42 St., New York 36, N. Y.

ME...an AIRCRAFT ENGINEER *in California?*

Yes, Lockheed can train you—at full pay!

The step up to Aircraft Engineering—and a better life in Southern California—isn't as steep as you might expect.

Aircraft experience isn't necessary. Lockheed takes your knowledge of engineering principles, your experience in other engineering fields, your aptitude, and adapts them to aircraft work. You learn to work with closer tolerances, you become more weight conscious.

What's more, Lockheed trains you *at full pay*. You learn by doing—in Lockheed's on-the-job training program. When necessary, you attend Lockheed classes. It depends on your background and the job you are assigned. But, always, you learn at full pay.

These opportunities for engineers *in all fields* have been created by Lockheed's long-range production program—building planes for defense, planes for the world's airlines.

And remember this: When you join Lockheed, your way of life improves as well as your work.

Living conditions are better in Southern California. The climate is beyond compare: Golf, fishing, motoring, patio life at home can be yours the year 'round. And your high Lockheed salary enables you to enjoy life to the full.

Note to Men with Families: Housing conditions are excellent in the Los Angeles area. More than 50,000 rental units are available. Thousands of homes for ownership have been built since World War II. Huge tracts are under construction near Lockheed.

Send today for illustrated brochure describing life and work at Lockheed in Southern California. Use handy coupon below.

ENGINEER TRAINING PROGRAM
M. V. Mattson, Employment Mgr., Dept. ENR-12

LOCKHEED
Aircraft Corporation
Burbank, California

Dear Sir: Please send me your brochure describing life and work at Lockheed.

My Name _____

My Field of Engineering _____

My Street Address _____

My City and State _____

He works with Doctor-like thoroughness



Milling operation on #3 Brown Sharpe milling machine.
Milling slot in Hoist control lever for American locomotive crane now being rebuilt for Bobcock-Wilcox Tube Co., Barberton, Ohio.



Turret Lathe operation on #5A Gisholt turret lathe.
Turning—boring—facing and cutting to length. Bronze bushings for Lorain 820 turntable rollers. With parts in short supply as they are today, the ability to help ourselves is money in our customers' pockets.

Boring mill operation on 60 in. Niles vertical boring mill.
Turning and facing cylinder end casting for Robot laundry washer.



Rebuilding—to make like new—
CONSTRUCTION EQUIPMENT

AN INVITATION

To Use the World's Largest Equipment Rebuilding Facilities

Where rebuilding is a business—with over 25 years of experience on all types of construction equipment—where highly trained mechanics with precision tools—can build back into your equipment many years of additional and efficient usefulness—using the same thoroughness employed in rebuilding our own used equipment.

You are invited to investigate our complete facilities.



L. B. SMITH INC.

CAMP HILL, SUBURB OF HARRISBURG, PA.

L. B. SMITH INC.

New and Used Equipment News

Prepared Monthly by Ed Woolford at Camp Hill, Pa.

VOL. 1 NO. 9

AIR COMPRESSORS

Gardner-Denver 500 cu. ft. diesel, new condition.
Gardner-Denver 500 cu. ft. diesel, good operating condition.
Schramm 105 cubic foot gas powered compressor on 4 steel wheels.
Worthington two-stage, water-cooled, vertical 250#, 60 CFM, new condiiton.
Paving breakers, jackhammers, wagon drills, tie tampers.

QUARRY EQUIPMENT & BINS

2540 Cedarapids AAAA primary unit on rubber, diesel power. Rebuilt.
2436 Lippman "Grizzly King" w/hopper, undercrusher conveyor, 75 HP motor.
2036 Cedarapids AAA primary unit on rubber, diesel power. Rebuilt.
1036/2418 Cedarapids Jr. Tandem unit on rubber.
Cedarapids Rock-It plant w/2025 jaw, 3033 hammermill. New.
1236 Cedarapids Model 6C plant. New.
4033 Cedarapids Model 6C plant. New.
2020 Cedarapids double impeller. New condition.
4024 Cedarapids roll. Rebuilt.
3018 Cedarapids roll. Rebuilt.
1236 Cedarapids twin jaw crusher. New.
4033 Cedarapids hammermill. New.
10x7 Allis Chalmers Blake type jaw crusher. Rebuilt.
#1 Cedarapids Kubit impact breaker. New condition.
B-3 Jeffrey swing hammer pulverier. Rebuilt.
4' x 6' Kennedy Van Saun single deck screen.
3' x 6' Kennedy Van Saun triple deck screen.
60" dia. x 14' long Traylor revolving screen. Rebuilt.
36" Wemco single pitch sand screw. New condition.
15 cu. yd. Cedarapids sand drag. New.
16" x 90' bucket elevator.
60-ton, 2-compartment, 8' x 18' storage bin w/clam gates.
100-ton, 2 compartment, 13'x23' storage bin.
Special bins to your specifications.
Conveyors—18"—24"—30"—36". Also belt.

TRUCKS—TRAILERS

27FD Euclid rear dumps.
28FD Euclid rear dumps.
1½-ton Ford with any body.
2000-gallon tanks on semi-trailer mounting.
New and rebuilt dump bodies.

GENERATORS & LIGHT PLANTS

1½ KW to 125 KW, alternating and direct current gasoline and diesel powered.

SHOVELS—CRANES

Osgood Model 900, 1¼ yd. diesel combination.
Lorain 40 truck crane on Mack 3-axle truck.
Lorain TL, ¾ yd. diesel.
Unit 514, ½-yd. gasoline crawler shovel. Good condition.

SHOVEL & CRANE ATTACHMENTS

Lorain L-41 Chain Crowd Shovel Attachment. Rebuilt.
Lorain 40 Hi-Lift shovel attachment.
P&H 203 shovel attachment.
Chain crowd Lorain 30A shovel attachment.
Bucyrus-Erie 1½-yd. rock bucket.
McCaffrey Model 648 for 1¼ to 2-yd. crane.
McCaffrey Model 636 for ¾-yd. to 1-yd. crane.

BACKHOE BUCKETS & ATTACHMENTS

Lorain 30 hoe attachment complete.
¾-yd. Lorain, 40, LBS #6105. 44" cutting width.
¾-yd. Amsco 40" cutting width, LBS #8101.

CLAM—DRAG—SCRAPER BUCKETS

LIFTING MAGNETS

1—45" Ohio lifting magnet, rebuilt.

SHOVEL DIPPERS

Lorain 41, ¾-yd. LBS #8600, rebuilt.
New Lima 1-yd. Amsco, LBS #2295.
Bucyrus-Erie 1¼-yd. gas air, LBS #3782, fair.
Lorain 75B, 1½-yd. manganese bucket, LBS #8538.
Lorain 75B, 1¼-yd. extended lip, 1¾-yd. LBS #2260.
Pettibone-Mulliken 2-yd. Lorain 82 or 820, manganese, LBS #5361.
Pettibone-Mulliken 2-yd. for 3500 Manitowoc LBS #5763.
Esco 2½-yd. cast weld dipper with bail & teeth.

CONCRETE EQUIPMENT

Blaw-Knox gas-electric finisher, 10½'-12½', rebuilt.
Koehring 10'-12' finishers, rebuilt.
Cleveland formgrader, new 1944, rebuilt.
Corr formgrader, new 1944, rebuilt.

TRACTORS

TD-24 International with Bucyrus-Erie angleblade.
TD9 International diesel with 1 yd. Loadover.
Model CR Tournapull w/16-yd. Model E16 Tournarocker, rebuilt.

WELL DRILLS & TOOLS

Sanderson-Cyclone #42 well drill, new.
Sanderson-Cyclone #44 well drill, new.
Bits—Stems—Bailers—Sockets—Etc.

Barber-Greene 44C Trenching Machine 18" to 24" cutting width, 7' depth.

PUMPS

New Layne Bowler type 18 deep well pump with right angle gear drive. 3000 GPM at 120' TDH.
Used and rebuilt pumps, all sizes, gasoline, electric or diesel.

GRADERS

Austin Western 77 tandem drive, scarifier, 12' blade, gas power, hydraulic controls.

GASOLINE AND DIESEL ENGINES

Caterpillar D-13000, rebuilt.
Murphy ME-6, & ME-46, rebuilt.

***Phone* HARRISBURG, PA. 7-3431**



L. B. SMITH INC.

CAMP HILL, SUBURB OF HARRISBURG, PA.

DIESEL POWER

FOR

IMMEDIATE SHIPMENT

UNIT CAPACITIES—10 TO 1875 KVA

A.C.—50 AND 60 CYCLES

VARIOUS VOLTAGES

A PARTIAL LISTING OF OUR INVENTORY

KW	Make	Model	HP	RPM	KW	Make	Model	HP	RPM
1500	Fairbanks Morse	33E16	2000	300	320	Buckeye	80	480	600
1136	Fairbanks Morse	38E1	1600	720	320	Enterprise	DSG-6	560	450
1100	General Motors	16-278A	1600	720	300	General Motors	8-268A	450	1200
1000	General Motors	16-567B	1440	720	250	Fairbanks Morse	37-E	375	360
750	General Motors	12-567	1080	720	200	General Motors	8-268A	350	900
500	Baldwin	VO-8	750	514	100	Worthington	HR-5	150	600
500	General Motors	8-278A	750	720	100	General Motors	3-268A	150	1200
500	General Motors	8-567	720	720	60	General Motors	6-71	90	1200
400	Ingersoll-Rand	8-8	600	720	30	International Harvester	UD-14	45	1200
350	Baldwin	VO-6	510	450					

D.C. UNITS ALSO AVAILABLE

A. G. SCHOONMAKER COMPANY, INC.

ENGINE DIVISION, 50 CHURCH ST., NEW YORK 7, N. Y.

FOR SALE

1035 CFM I. R. Air Comprs. new 1949.
65 Ton G.E. Diesel Elec. Locomotive.
50 Ton Colby 240 Elec. Gantry Crane.
3 Yd Lima 1201 Dragline 120' Bm. 1947.
30 Ton Ind. Brownhoist Gas Loco. Crane..
½ Yd Link Belt LS-50 Shovel-Backhoe-Crane.
130 HP Christian 2D Diesel Hoist.
10 Ton Unit 1020 Pneu. Tired Crane.
25 Ton Wiley Steel Stiffleg. 110' Bm.

MISSISSIPPI VALLEY EQUIPMENT CO.

509 Locust St. St. Louis 1, Mo.

NEW AND REBUILT

STORAGE BATTERY

LOCOMOTIVES

1½ to 10 Ton — 18" to 56" Track Gauge

GREENSBURG MACHINE CO.

Greensburg, Penna.

SHOVELS—CRANES—DRAGLINES

Buc-Erie 170-B Electric Shovel. New 1949.
Buc-Erie 120-B Electric Shovel. 5 yds.
Page 625-S Diesel Dragline 150 ft. boom.
Page 618-S Diesel Dragline 110 ft. boom.
Northwest 80-D Diesel Shovel, rebuilt, 2½ yd.
Manitowac Mod 3500 Diesel Shovel.
Buc. Erie 54B Dragline, 100 ft. boom, 3 yd.
Buc. Erie 51B Shovel, 2 yd. Near new cond.
Koehring 304 Shovel ¾ yd. Rebuilt. Diesel.
P&H 855-B 1½ yd Shovel-Crane-Drag. Diesel.
P&H 255-A 20 ton Truck crane 80 ft. boom.
Lorain Mod. Mc-414 Moto-Crane 70 ft. Boom.
Lorain Mod TL-20 Moto-Crane, 60 ft. Boom.

TRAXCAVATORS—PAYLOADERS

Cat. D-4 Tractor with Athey Mobile Loader.
Cat. D7 Traxcavator. Rebuilt.
Cat. D4 Traxcavator. Rebuilt.
Hough Payloaders Models HLA, HFH, HE, HA.

CONCRETE PLANTS—BINS & SILOS

B-K P-4120, 3 compt., agg., one for cement.
Large plant 212 yds., 6 compt., agg. and cement elevators, 56-S Mixer. Excellent.
Large plant 400 yds., 5 compt. with 2 yd. Koehring Mixers. Write for details.
Cement bin 400 bbls. with batcher. NEW.
Agg. bin. 100 tons 3 cpts. 2 yd. weighbatcher, NEW.

ASPHALT PLANTS

Barber Greene Model 842 Utility Plant
McCarter Iron Works Complete 3000# pug mill.
Cummer 1500 lbs. Semi-Port. Very good.
Std. 1500 lbs. Batch. Sta. Bit.
Simplicity Model S-100. Diesel powered.
B-G Model 840-830 Maintenance Plant. Complete.

STIFF LEG AND GUY DERRICKS

Steel Stiff leg Derrick 100 Ton 100' Boom.
Steel Stiff leg Derrick 25 Ton 80' Boom
American 20 ton stiff leg derrick 90' boom.
Stiff leg derrick 15 ton 100 ft. boom.
American 20 ton Guy derrick 100 ft. boom.

CONCRETE MIXERS AND PAVERS

2—Koehring Tilting Mixers, 4 yds. Complete.
Smith 56S Tilting Mixer, 2 yds.
Jaeger BP-S Asphalt Paver & attachments.
2 Ransome 34-E Dual Drum Pavers Diesel.
Rex 28-S Builders Mixer. Elec. NEW 1947.

ROAD AND AIRPORT FORMS

Blaw-Knox and Heltzel 8100 ft. 9"x9"; 10,000 ft. 8"x8", 6000 ft. 12"x9" airport forms.

RICHARD P. WALSH CO.

30 Church St. New York 7, N. Y.
Cable RICHWALSH Cortlandt 7-0723-4

CRANE: 1—Overhead Electric Traveling Crane, 7½ ton capacity, 80' span, 4 motor, bucket operating, 440 volt, AC, cage control, in operation now, available January 1953. With or without one Hayward 2-½ yd. capacity, type E, bucket; one Blaw Knox 2-½ yd. type 730-W bucket, rebuilt.

LOCOMOTIVE CRANE: 25 ton capacity, thoroughly modern, gasoline powered, case steel trucks, air brakes, with or without 1-¼ yd. Hayward clam shell. Sale or rent.

CAR DUMP: Link Belt, will dump standard R.R. Gondola cars up to 90 tons capacity, transfer table 54'. Specifications and photos available.

COMPRESSOR: Worthington DC2, 29/18-½ x 21, motor 600 H.P. synchronous, 440 volt, with all auxiliary equipment.

MINE HOISTS: Single and double drum 100 to 1500 H.P. with all electrical equipment. Complete specifications, drawings and photos available.

DIESEL MOTOR: Caterpillar D13000 portable on skids, 122 H.P.

KILNS: 2—8' x 266 ft. Kilns, brick lined, ⅞" plate, used only 2 years @ 1000 deg. heat, like NEW, with or without Fuller Lehigh grate type Coolers. 1—7' x 120' and 2—8' x 65'.

WE BUY AND SELL EQUIPMENT THROUGHOUT NORTH AND CENTRAL AMERICA.

A. J. O'NEILL

Lansdowne, Pa.

Phila. Phones: MAdison 3-8300—3-8301

Pile Driving Equipment

Vulcan and McKiernan-Terry
Steam Pile Hammers and Extractors
Pile Driving Accessories
Drop Pile Hammers and Caps
Steel Sheet Piling

CONTRACTORS MACHINERY Co.

2637 Southwest Blvd. Kansas City 8, Mo.
Phone Valentine 4740

LOCOMOTIVES

1—Brookville 10T-30" Ga. Diesel—Like New.
1—Plymouth 20 Ton Diesel—48" & Std. Ga.
2—Plymouth 25 Ton—36" Ga.—Gas.
3—Whitcomb—15 Ton—36" Ga.—Diesel.
5—Trucks Complete with Motors. Whitcomb 65 Ton Diesel-Electric. Like new Bargains.

1—WHITCOMB-0-4-0-STD. GA, 50 TON DIESEL ELEC.—BARGAIN

19—Hopper Cars—15 Ton—36" Ga.
3—Hopper Cars—50 Ton. Excellent.
2—Conway Mod. 75 Muckers. #256 & 305. Bargains.
Southwark 500 Ton Hydraulic Press—High Speed—Like New.

R. H. BOYER

2005-13 W. Bellevue St. Phila. 40, Pa.
Phone Sagamore 2-7132

FOR SALE

New Wire Rope Blocks

12" Snatch Blocks with Hooks	$13.50
14" Snatch Blocks with Hooks	18.50
16" Safety Snatch Blocks with Shackles	20.00
14" Double Blocks with Shackles	13.00
18" Single 20 Ton with S. Shackle	25.00
18" 3-Sheave 30 Ton with Shackle	50.00
18" 4-Sheave 30 Ton with Shackle	75.00
#32 Drop Forge Hooks, New	2.00

ABERTHAW COMPANY

133 Southampton St. Boston 18, Mass.

DEFORMED CONCRETE REINFORCING BARS

For Immediate Delivery

Intermediate and/or Structural Grade ⅜" to 1" round, 1" to 1¼" square. Free of C.M.P. Allotment.

Structural Steel. Wire Road Mesh.

Industrial Machinery & Supply Co.

15 Park Row New York, N. Y.

SALE OR RENT

1—TL 20 Lorain Truck Crane
1—20-Ton Bay City Truck Crane, 80' Boom, 15' Jib
1—¾ Yd. Bay City Diesel Crane
1—¾ Yd. Northwest 25 Backhoe and Dragline, 1948
4—500 cu. ft. Chicago-Pneumatic Diesel Air Compressors
1—2 Yd. Koehring 803 Crane
1—10-Ton Plymouth Diesel Loco.
1—30-Ton Davenport Diesel Locomotive
2—1½ Yd. Bay City Crane or Shovel, Diesel
1—45' Boom & 10' Jib for Link Belt 85 or 90, New
1—45-Ton G.E. Diesel Elec. Locomotive
1—50-Ton Whitcomb Diesel Elec. Locomotive
1—65-Ton G.E. Diesel Elec. Locomotive
1—40-Ton Industrial Brownhoist Oil Fired Loco. Crane. New 1943

B. M. WEISS CO.

Girard Trust Co. Bldg. Phila. 2, Pa.
Rittenhouse 6-2311

28 SURPLUS NEW BELT CONVEYORS

30 INCH 1-136' - 1-270' - 2-350' - 1-418' 2-500' - 1-1100' & - 2-1500' Long.
36 INCH 1-160' - 2-250' - 1-320' - 1-400' 1-590' - 2-1000' - 1-1600' Long.
42 INCH 1-144' - 1-290' - 1-377' - 1-573' 2-700' - 1-800' - 2-1500' Long.

DARIEN, 60 E. 42nd St., N.Y. 17, N.Y.

MIXERMOBILE

2 Cubic Yard Capacity

Used only on one job

EXCELLENT CONDITION

HODGE & HAMMOND, INC.

720 Garrison Ave. New York 59, N. Y.
Phone: Kilpatrick 2-2400

FOR SALE

1 Lorain 40-A Pull Shovel
1 5 CY LaPlant-Choate Hydraulic Scraper
1 Pippin-Fordson Pull Shovel

WANTED

1 Rogers 40 Ton Low Bed Trailer

UNITED FOUNDATION CORP.

1600 N. Olden Ave. Ext., Trenton, N. J.
Phone 48139

FOR RENT OR SALE

WILL CONSIDER RENTAL PURCHASE

Lorain 40 shovel and dragline—¾ yd—with buckets—can furnish backhoe attachment

Buckeye Model 70 shovel and dragline—¾ yd.—can furnish backhoe attachment & buckets

Lorain Model 820 Dragline and Crane

Browning ⅞ yard crane and dragline

Mack Model LJT Tractor

LaCrosse 30 ton tandem trailer

Caterpillar D-6 with Sideboom

Caterpillar D-8 with Angledozer or stumper

Caterpillar D-8 with DDPCU only

International TD 18 with BE Angledozer

International TD 9 with BE Bulldozer

Garwood 8 yard hydraulic scraper

Bucyrus Erie 8 yard cable scraper

Barber Greene Model 44 B Trencher

Buda Model HBJ Earth Drill

Hendrix 2½ yard dragline bucket

Page 1½ yard dragline bucket

Allis-Chalmers Model L gasoline Tractor

All In Good Working Condition

AL J. GOODMAN

Dealer In

Used Construction Equipment

DAY PHONE 3-6456 — P. O. BOX 263 ASHEVILLE, N. C. — NITE PHONE 5668

RAILROAD EQUIPMENT

3—100 Ton G.E. Diesel Elec. Locomotives.
1—65 Ton G.E. Diesel Elec. Locomotive.
1—20 Ton Whitcomb Gas Locomotive.
1—Jordan R. R. Spreader.
10—12 Yd. Western Dump Cars.
6—10,000 Gal. Cap. R. R. Car Tanks.

DARIEN, 60 E. 42nd St., N.Y. 17, N.Y.

FOR SALE

1—CONCRETE CUTTER, TRI-LINE MODEL TLA, Mfgs. No. 129, 3 ½" x 3 ½". Complete with accessories and 14" Heavy-Duty Blade, Powered by WICO Motor Model TF.
1—CURING COMPOUND SPRAY MACHINE, Tarrant Model HV, Capacity 55 gallons; Gasoline driven Briggs Stratton 1-½ HP.
1200 Feet—10" Blaw-Know Road Forms, Plain
2000 Feet—10" Blaw-Knox Road Forms, with construction joint key form attached. Both items complete with pins and wedges. In 10' 0" lengths.

All of above used on one job only, and in excellent condition. Priced for quick sale.

AYERS-HAGAN-BOOTH, INC.
35 Westminster St. Providence, R. I.
Jackson 1-6254

IF there is anything you want that other readers can supply—
OR . . . something you don't want— that other readers can use—
Advertise it in the SEARCHLIGHT SECTION

Do you know that SANTA CLAUS

(OR "KLAUS") WAS REALLY ST. NICHOLAS, PATRON SAINT OF CHILDREN AND BISHOP OF MYRA, ASIA MINOR?

DO YOU KNOW THAT you can be your own Santa? Get yourself trouble-free, money-saving, "size-for-the-job" construction equipment from ECA! Rent, buy or rental-purchase. Let ECA help make your Christmas really merry, and your New Year right prosperous!

THIS MONTH'S SPECIAL

at our Chicago plant

DIESEL 75 KW AC GENERATOR

1—75 KW Diesel Generator, 220/440/60/3, powered by Cat. D-13000 Diesel engine, complete with electric starting and control panels. LATE MODEL. BARGAIN. $5,500 f.o.b. our Chicago Plant.

Write, Wire or Phone

ECA—CHICAGO 12, ILLINOIS
1155 S. Washtenaw Ave.
Phone NEvada 8-2400

AIR COMPRESSORS

Portable, 2-Stage

1—500' Ing. Rand Mdl. K-500, Ser. 40-T-29621, 100# pressure, 6 cyl. Wauk.-Hesselman Diesel eng Mdl. 6-WAKH, mtd. 4 pneu. tires. Wt. 10,000#. $8,000.00.

1—500' Ing. Rand #40T9627, Waukesha gas engine, 4 pneu. tires.

BOILERS—Horizontal & Vertical

WE HAVE A LARGE STOCK OF HORIZONTAL SELF-CONTAINED BOILERS UP TO 125 HP; ALSO VERTICAL BOILERS FROM 1 TO 80 HP.

BOOMS

1—130' Derrick boom, 10 ton cap., boxing 30x30", main angles 3x3x⅜". Can be used as 70', 100', or 130'.

1—50' #6 Northwest crane boom, main angles 3½x3½x⅜", boxing at center 44½x44½".

1—40' Thew crane boom, Main angles 3½x3½x⅜", boxing at center 26x28".

CRANES, CRAWLER

1—2½ yd. P&H Mdl. 955-LC, Ser. 5309, Cat. D-17000 Diesel eng., 100' boom, 1½ KW light plant, tagline. Operate either from cab or remote control 32' high tower. Ideal for coal dock or similar work. Excel. condition.

1—1¾ yd. Link Belt Mdl. 370 Diesel Crane or Dragline, 90' boom, hi gantry, Cat. D-13000 Diesel eng., long & wide pads. Rental only.

1—1½ yd. P&H 655-A Diesel Crane or Dragline, Ser. 6426, 75' boom, 20' jib. Cat. D-13000 Diesel eng., hi gantry. Wt. 82,900#. Rental only.

1—1½ yd. Link Belt Mdl. K-360, Ser. 1959, Cat. D-13000 Diesel eng., 80' boom, Rudomatic tagline, hi gantry, excel. shape.

1—1¼ yd. Bucyrus Erie Mdl. 33-B, Ser. 16502, 8 cyl. "V" type LeRoi gas eng., 50' boom.

1—¾ yd. P&H Mdl. 255A, Ser. 5750, 6 cyl. Waukesha gas eng., 35' boom, fairleads, Rudomatic tagline, rebuilt, excel. shape.

DERRICKS, STIFFLEG

1—30 ton Wiley Mdl. F Steel Stiffleg, 60, 80 or 100' boom, rated 30 ton at 38', 15 ton at 57'.

PILE HAMMERS—EXTRACTORS

10—McKiernan Terry Pile Hammers, #9B2, #6, #3, #2, and #1.

1—#800A Vulcan Extractor, wt. 5400#.

1—E4 McKiernan Terry Extractor, wt. 4400#.

Partial list only—please let us quote on your requirements.

Clifton Heights, Pa.
Box J-608, Sub. of Phil.
Phone MAdison 6-2200

Pittsburgh 30, Pa.
Box J-933
Phone FEderal 1-2000

ECA
EQUIPMENT CORPORATION OF AMERICA

Chicago 12, Illinois
1155 S. Washtenaw Ave.
Phone NEvada 8-2400

New York 7, N. Y.
30-J Church Street
Phone WOrth 2-0036

COMPLETE TUNNEL EQUIPMENT

For Drilling

3—1035 c.f.m. Ingersoll-Rand Stationary Compressors with 200 H.P. Electric Motors, Air Receivers, Aftercoolers and made-up piping.
10—Ingersoll-Rand No. 229 DJB Drill Booms
16—Ingersoll-Rand DA35, wet type Drifters

For Mucking

3—#40 Elmco Rockershovels
4—#75 Conway Muckers

For Hauling
(all 36" gauge)

6—Greensburg, 11 ton, Electric Locomotives
3—Whitcomb, 10 ton, Electric Locomotives
3—40 K.W. Battery Charging Units
2—20 K.W. Battery Charging Units
1—Plymouth, 10 ton, Gas Locomotive
8—5 yard Side Dump Muck Cars
6—2 yard Koppel Dump Cars
30—Flat Cars

For Ventilation

2—7300 c.f.m. Roots-Connersville Blowers
1—Joy Axivane Fan, series 1000
12,000'—24" Vent Pipe, Lock Joint, 14 gauge

For Concreting

2—¾ yard Hackley Pneumatic Concrete Placers
1—Model 190 Rex Pumperete Machine
Special Placing Equipment for Arch and Invert

Miscellaneous

25—1½" to 4" Electric Pumps
2—60 K.W. Diesel Generator Sets

Subject to prior sale

FRAZIER-DAVIS CONSTRUCTION COMPANY

1319 Macklind Avenue, St. Louis, Mo. — STerling 1950
Box 153—Grahamsville, New York — Grahamsville 2861

FOR RENT

20-10 TON TO 25 TON CAPACITY

TRUCK CRANES

SECTIONAL BOOM LENGTHS TO 130 FEET

LIMA & P & H CRAWLER CRANES

30 TON TO 50 TON CAPACITY

SECTIONAL BOOM LENGTHS TO 175 FEET

THE ROGER SHERMAN TRANSFER CO.
EAST HARTFORD, CONN.

Branches: SPRINGFIELD, MASS. NEW HAVEN, CONN. ALBANY, N. Y.

PIPE

FOR SALE—*Immediate Delivery*
C. I. Water Pipe A.W.W.A. Standard
BELL & SPIGOT— 10 inch, 12 inch, 16 inch, 20 inch, 36 inch and other sizes
FLANGED PIPE— 4 inch, 6 inch, 8 inch, 10 inch, 12 inch
C.I. Water Pipe Fittings—B & S—and Flanged—All kinds and sizes
SOIL PIPE—EXTRA HEAVY
8 Inch—10 Inch—12 Inch—16 Inch
The above subject to prior sales
TAGCO, INC.
111 Front Street Hempstead, L. I., N. Y.
Tel.—Hempstead 2-5535 or 2-8357

For Rent

SPEEDCRANES

LATE MODELS

Manitowoc Diesel Powered Speedcranes for rent. 25, 40 and 60 ton capacities with booms 100' or more, 20' and 30' jibs. Special price on long rentals.

FORSYTHE EQUIPMENT CO., INC.
37-11 Vernon Blvd. Long Island City, New York
Tel. STillwell 4-1030

FOR SALE

Model 655-BLC

P. & H. 40 Ton Crane

New February 1952. Long cats, Heavy Duty Boom. Used for Hoist work only.

For further information write

FS-5974, Engineering News-Record
330 W. 42 St., New York 36, N. Y.

PIPE AND ACCESSORIES

IF IT'S MADE, WE HAVE IT!

Seamless and Welded—Every Size and Wall Thickness—Cast and Wrought Iron, Steel, Alloys

POWER PIPE FABRICATING
Bending, Coiling, Flanging, Threading, Beveling, Lining, etc.

Valves & Fittings
Piling & Fittings
Culverts
SPEED-LAY PIPE SYSTEMS
Write for brochure

ALBERT PIPE SUPPLY CO., INC.
Berry at North 13th St.
Brooklyn 11, N. Y.
Phone EVergreen 7-8100

CRANES FOR RENT

New 802 Lima Caterpillar Cranes, 100' main boom, 40' jib. New P&H Model 255-A, pneumatic tired truck cranes capacity 20 tons, 80' main boom, 30' jib. Prevailing rental rates. Address

CRANES, 1122 Longwood Avenue
Bronx 59, N. Y. or Dayton 3-1065

FOR RENT

Michigan

TRUCK BACKHOE

Cab Job 1951 ½ yd Cap.

FR-6129, Engineering News-Record
330 W. 42 St., New York 36, N. Y.

PIPE FOR SALE

Immediate Delivery

28,000' of 6-⅝" x .188 wall, black steel pipe, electric weld, double random lengths, plain ends with Rotagrip couplings.

22,000' of 3-½" O.D. x .13 Ga. Black Steel tubing, 20 lengths, plain ends with Rotagrip couplings.

12,000' of 24" diameter, 14 gauge, Lock Joint Ventilation Pipe, in 24' lengths with couplings.

Subject to prior sale

FRAZIER-DAVIS CONSTRUCTION CO.
1319 Macklind Avenue St. Louis, Mo.
STerling 1530
Box 153 Grahamsville, New York
Grahamsville 2861

FOR RENT

MANITOWOC SPEEDCRANES

Model 3500 — crane or dragline — 80 ft. boom — manual swing — 20' or 30' jibs — 60 ton lifting capacity — or 2¼ c.y. drag bucket.

Model 2000-B — crane or dragline — 60 ft. boom — manual controls — 20' jib — 25 ton lifting capacity — or 1½ c.y. drag bucket.

McCARRICK BROTHERS, INC.
1700 E. Ridge Pike P. O. Box 291
Norristown, Pa. *Phone 8-4231*

RENT A COMPRESSOR

(STATIONARY - PORTABLE)
FROM
Compressor Men

GAS • DIESEL
ELECTRIC • STEAM
20 lbs. to 3000 lbs.
30 CFM to 2500 CFM
Sale—Rental Purchase
LET US REBUILD YOUR COMPRESSOR
—50 Years of Service—
OVER 300 UNITS AVAILABLE

American
AIR COMPRESSOR CORP.
DELL AVE. & 48th ST., NORTH BERGEN, N. J.

PIPE

VALVES and FITTINGS
All Sizes in Stock
NEW—USED
GREENPOINT IRON & PIPE CO., INC.
Bogart and Stagg Streets Brooklyn, N.Y.

FOR RENT

New Model 3500 Speedcrane, dragline, clamshell and lifterane, 60-ton capacity.
New Ingersoll Rand 600' Gyro-Flo Air Compressor.
New Lorain Truck Crane, 25 Ton capacity.

FOR SALE OR RENT

Marion 392 and Koehring 803 dragline, clamshell, lift crane and pile driver combinations. McKiernan-Terry S-5 and 11B-3 Pile Hammers.

Reply to:

Clemens Construction Co.
P. O. Box No. 266, West New York, N. J.

YOUR BEST CONNECTION

★ PIPING—For all purposes *and for Culverts* 7" to 26".
★ All Sizes; fabricated to your specs.
★ New and Used.
★ Will Ship C.L. and L.C.L., Quantities.
★ In Business Nationally For 30 Years.



Hy Schiffman Co.
1428 W. Pierce St., Milwaukee, Wis.
Mitchell 5-2290

FOR SALE

D-8 Cat. Ser. # 2U11345, w/hyd. angledozer
D-8 Cat. Ser. # 2U4209, w/D.D.P.C.U. cable dozer
D-8 Cat. Ser. # 2U6427, w/D.D.P.C.U. cable dozer
D-8 Cat. Ser. # 2U12462, w/D.D.P.C.U. cable dozer
D-8 Cat. Ser. # 2U12741, w/D.D.P.C.U. cable dozer
Gar Wood 524 Scraper, Serial 524S17
Gar Wood 524 Scraper, Serial 524S19
Gar Wood 524 Scraper, Serial 524S87
LIMA 802 Shovel, Serial No. 3675

ALL equipment is in good operating condition and ready to go to work.

EASTCOAST EQUIPMENT COMPANY
Route 29, Mountainside, New Jersey
Tel. WEstfield 2-5650

Lorain Crawler Shovel Model L-80 Complete.
Lima Crawler Crane Model 1201 3-¼ yd. shovel front.
P&H Crawler Std. shovel Model 855B.
P&H Crawler model 255A, Backhoe Attachment. (2) 1 gas 1 diesel.
Northwest Crawler Shovel model 80-D complete.
Lorain Moto Crane model MC-4.
Steam Crane—Bucyrus-Erie model 41-B.
Byers Moto Crane model 83CC.
Byers Backhoe Crawler mtd. model 83 Diesel, Complete.
Byers Crawler Crane model 83 gas, complete.
Oliver Cletrac crawler model FDE Diesel with dozer attachment (2).
Turn Table Pile Drivers, 75' leads complete with engines & boilers (2).
Rex Pumpcrete 7" line all necessary attachments.

ALL EQUIPMENT SUBJECT TO PRIOR SALE.

FINEST CONSTRUCTION & EQUIPMENT CORP.
147-47 Farmers Blvd., Jamaica 5, N. Y.
Tel. LA 7-3637



FOR SALE G.E. DIESEL ELECTRIC
44-Ton LOCOMOTIVE

Standard Gauge **Excellent Condition**

Write for Details

FRANK M. JUDGE & CO., Inc.
7010 Empire State Bldg. New York 1, N. Y.

FOR SALE

Model 4500 Manitowoc Draglines, caterpillar-mounted, with 140' booms, buckets, Caterpillar engines, 5 cu. yd. 100-ton capacity, one and two years old.

Model 3500 Manitowoc Speedcrane, Liftcrane, clamshell, dragline combination, 2½ cu. yd. 60-ton capacity, new October, 1950.

Model 2000 Manitowoc Dragline, 1¼ cu. yd. capacity.

Model 803 Koehring Liftcrane, Clamshell, Dragline combination, 2 cu. yd. 50-ton capacity.

All located in Florida. Reply to

FS-5844, Engineering News-Record
330 W. 42 St., New York 36, N. Y.

FOR SALE

New Material—Immediate delivery from stock

3 x 3 x ¼ up to and including 6 x 6 x ¾ Angles
4" up to and including 15" Channels
4" I Beams up to and including 36" WF Beams
3/16" up to and including 2½" Plate
H Beams and Pile Sections

Also all sizes Excellent Used Material

Phone or Wire your steel requirements

HY DRACHMAN STEEL CORP.

Warehouse
14-23 34TH AVENUE
ASTORIA, NEW YORK
AStoria 8-4484 8-8023

Sales Office
563 EAST TREMONT AVE.
NEW YORK CITY, N. Y.
CYpress 9-5440

FOR SALE OR RENT

Cat. D7 Bulldozer #4T5988
Cat. D7 Bulldozer #4T6542
Cat. D8 Tractor #8R8926
Cat. D8 Tractor #8R8933

WILLIAMS CONSTRUCTION CO.
Middle River, Maryland Phone: Essex 1310

FOR SALE

D-8 Cat. Bulldozer D.D.P.C.U. Serial #1H8637S.P. $6,000
D-7 Cat. Bulldozer D.D.P.C.U. 4T Series $7,000
TD-18 B. E. Bulldozer 1945..... $4,000
Lorain 40A—¾ yd. Crane, serial 9723 ..... $5,000
Lorain 69 Cat. Diesel, Air Crowd, Vacuum swing and chain crawlers, 1¼ yd. Shovel front and 60 ft. Crane Boom, excellent $15,000
One Nelson Snow Loader, 95% new $2,000
1942 D.G. Cletrac Bulldozer..... $2,000
1942 F.G. Cletrac Bulldozer..... $1,000

D'ADDARIO CONSTRUCTION CO.
513 Boston Ave. Bridgeport, Conn.

FOR SALE

24—1½ yard Blaw Knox, R-46, Bottom Dump Concrete Buckets.

Subject to prior sale

FRAZIER-DAVIS CONSTRUCTION CO.
1319 Macklind Avenue, St. Louis, Mo.
STerling 1950

Box 153 Grahamsville, New York
Grahamsville 2861

Locomotive Cranes	Dredges, Hydraulic
Crawler Cranes	Boilers
Gantry Cranes	Generators
41-B, 50-B, 30-B, DE	Slackline
Steam Cranes	Tugs & Boats
Locomotives	Derricks
Railroad Cars	Hoists
Pumpcrete	Bins

STONE THE CRANE MAN
1132 Prudential Bldg. Buffalo 2, N. Y.

FOR SALE
LORAINE HEAVY DUTY TRUCK CRANE
Model 414—105' Boom & Jib
Excellent Condition
HEYDT-MUGLER CO., INC.
Longfellow & Viele Aves. N. Y. C. 59

ARMY SURPLUS — TRUCK AND CONSTRUCTION TYPE TIRES
NEW—USED AND TAKEOFFS

Suitable For All Types Of Construction Equipment
• Mobile Cranes • Low Bed • Mobile Compressors • Truck • Tractor
Regular Highway and Non-directional on and off the road type tires.

750/20— 8 ply un-used non-directional tires and tubes....$32.50
825/15—12 & 14 ply low bed takeoff tires 85% tread..... 50.00
1000/15—12 ply excellent perfect used L. B. tires..... 35.00
900/20—14 ply or better Army combat takeoffs..... 50.00
1100/20—12 ply non-directional 95% tread takeoffs..... 60.00
1100/20—12 ply highway 95% tread takeoffs..... 55.00
1400/24—16 ply new Goodrich highway tread tires..... 149.50
1400/24—16 ply Goodyear all weather diamond tread takeoffs 85.00
1400/24—20 ply non-directional tread takeoffs—75% tread. 99.00

EVERY TIRE GUARANTEED TO BE IN PERFECT CONDITION
Tires Shipped Everywhere—25% With Orders—FOB Everett, Mass.
Inquiries Promptly Answered • We can supply tires and tubes for all types of grader and heavy duty construction equipment.

TIRE SALES & SERVICE CO. 71 Main St. Everett 49, Mass.

NEW ENGLAND'S GREATEST TIRE BARGAIN CENTER

Tel EV 9-9485

EQUIPMENT FOR SALE

1—D8 Tractor with Bulldozer, new 1949, completely overhauled
1—D4 Tractor with Hydraulic Dozer—electric and/or diesel
1—Austin-Western Motor Grader
1—Oliver, Model 80, Rubber Tired Tractor
1—Model C Scoopmobile with 1 yard bucket
2—60 K.W. Diesel Generators
3—500 c.f.m. Ingersoll-Rand Portable Compressors
1—No. 2½ Kent 2 Hopper Mortar Mixer
2—Cement Guns, Size N-2, with Worthington Pump and necessary hose, nozzles, etc.
2—Single Drum, 40 H.P. Clyde Electric Hoists
24—1½ yard Blaw-Know, R-46, Concrete Buckets

Subject to prior sale

FRAZIER-DAVIS CONSTRUCTION CO.
1319 Macklind Avenue, St. Louis, Mo.
STerling 1950
Box 153 Grahamsville, New York
Grahamsville 2861

FOR SALE:—

2—Caterpillar D-17,000 Engines (Not run enough for first Overhaul).
2—American Skeleton Hoists, 3 Main Drums 16" Diameter, 30" Long, 2 Auxiliary Drums 16" Diameter, 11" Long. All drums with air friction.
4—American Skeleton Hoists, 2 Drums 20" Diameter, 30" Long, air frictions.
2—Air Compressors for air frictions.
2—50 Ton Capacity, all steel, 3 Leg "A" Frame Derricks with all fittings, 85' Booms. Built by American Hoist for Derrick Boats, condition like new.
1—Steel Tug "CARLOTTA" 50' x 14' x 7'7", 265 H.P. Buda Engine, wheel 48 x 44. Inspection at Pier 17 North Wharves, Phila., Pa.

Philadelphia Derrick & Salvage Corp.

FOR SALE
SURPLUS BEARINGS

MAKE		NO.	AMT.
Homer		211	342
SKF		6211	342
CJB		6211	992
TYSON		211	1835
MRC		214	218
HYATT	V	1315	156
HYATT	V	5220	200
NEW DEPA		3211	1210
NEW DEPA		5318	252

MRS. N. E. DORLAND
3031 N. 16TH STREET
PHILA. 32 PA.

FOR SALE

INT'L TD-18A hydr. bulldozer, rebuilt
LORAIN 820-G-2 cy Diesel Shovel, Aug. 1952, only 330 hours
LORAIN TL-50 one cy Diesel Shovel, 1950
CAT & INT'L. tractor parts under list price

BENDIX MACHINERY CO., INC.
401 Broadway, New York - Tel: CAnal 6-5693

RAILS-TIES
TRACK ACCESSORIES

PILING

STEEL SHEET PILING
Available from stock. Will also roll to size and specifications.

LARSSEN Arch Web

High section modulus • Very great durability • Great longitudinal strength • High rigidity • Uniform interlock

UNION Straight Web



For cellular construction
High interlocking strength

Let us design your sheet piling structure ECONOMICALLY.

LARSSEN PILING CORP.
205 East 42nd St., N. Y. 17, N. Y.
Phone: MU 4-7700

RENT STEEL SHEET PILING

"Faster From Foster"—the exact lengths and sections — all standard makes—of Rental Piling to meet your job needs. Also Rent: Pile Hammers and Pile Extractors.

RAILS • TRACK ACCESSORIES • PIPE • WIRE ROPE
L.B. FOSTER CO.
Pittsburgh 30, Pa. New York 7, N.Y.
Chicago 4, Ill. Houston 2, Tex.

We do a Nation-Wide business in
STEEL SHEET PILING
IMMEDIATE SHIPMENT

3700 pcs. 72-16 ft. Carn. MP-101-West Coast
418 pcs. 60-30 ft. Carn. M-116-Illinois
310 pcs. 35-26 ft. Beth. DP-2-Texas
487 pcs. 32 ft. Inland I-23-Chicago
383 pcs. 16-15 ft. Carn. M-112-Missouri

Other lengths & sections used & new at other locations in United States for rent.

We have Nation-wide reputation for effecting QUICKEST SHIPMENTS

All sizes Vulcan & McKiernan Pile Hammers & Extractors for rent—Shop Rebuilt
Regardless of location of job, Wire, Write or Phone

MISSISSIPPI VALLEY EQUIPMENT CO.
509 Locust St., Chestnut 4474 St. Louis, Mo.

WANT BUY
ALL SECTIONS
STEEL SHEET PILING
PILE HAMMERS & EXTRACTORS

DARIEN CORP.
60 E. 42nd St. New York 17, New York

SHEET STEEL PILING
STOCKS—N. Y., FLA., ALABAMA
MINNESOTA & WASHINGTON STATE

450 PCS. Z—27 LB. 40 FT. LENGTHS.
627 PCS. Z—32 LB. 40 & 50 FT. LENGTHS.
560 PCS. BETH DP-2, 28, 40 & 45 FT. LONG
150 PCS. CARNEGIE M-116—60 FT.

4000 PIECES CARNEGIE MP-101—28 LB. STRAIGHT WEB PILING & TEE PCS. 16 to 70 FT. LENGTHS. LOCATED CHIEF JOSEPH, WASH. AVAILABLE FOR EXPORT FROM SEATTLE, WASH.

41B & 42BE & MARION 32 STEAM CRANES
8—11B3 — S5 & 7 McK. T. HAMMERS

STANHOPE, 60 E. 42nd St., N. Y. 17, N.Y.

Locate *Piling*
or Buyers for *Piling*
in the Searchlight Section of
ENGINEERING NEWS-RECORD

EVERYTHING FOR THE TRACK FROM
SWITCH TO BUMPER
NEW & RELAY RAILS
IN STOCK
12# THRU 130# SECTIONS
ACCESSORIES & SWITCH MATERIALS
Inquiries Serviced Promptly

MORRISON RAILWAY SUPPLY CORP.
RAND BLDG. BUFFALO 3, N.Y.
EMPIRE BLDG. BIRMINGHAM 3, ALA.

NEW—RAILS—Relayers
All sizes and weights. Also frogs, switches, spikes, bolts, tie plates, contractors' and mine equipment carried in stock.

M. K. FRANK
480 Lexington Ave. New York, N. Y. Reno, Nevada
Park Bldg. Pittsburgh, Pa. Carnegie, Pa.

IMMEDIATE SHIPMENT
RAILS NEW RELAYING
SWITCH MATERIAL
ALL TRACK ACCESSORIES

MIDWEST STEEL CORPORATION
503 DRYDEN ST. CHARLESTON 31, W. VA.

Your inquiry will have special value . . .

if you mention this magazine, when writing advertisers. Naturally, the publisher will appreciate it . . . but, more important, it will identify you as one of the men the advertiser wants to reach with this message . . . and help to make possible enlarged future service to you as a reader.

PROFESSIONAL SERVICES

Duval Engineering & Contracting Co.

General Contractors

FOUNDATION BORINGS
For Engineers and Architects.

Jacksonville, Florida

Rader Engineering Co.

Water Works, Sewers, Refuse Disposal, Ports, Harbors, Flood Control, Bridges, Tunnels, Highways, Airports, Traffic, Foundations, Buildings, Reports, Investigations, Consultations

1615 duPont Building Miami, Florida

Consult these Specialists:

Let them save your time by bringing their broad experience in their specialty to bear on your problems.

Consoer, Townsend & Associates

Water Supply, Sewerage, Flood Control & Drainage, Bridges, Express Highways, Paving, Power Plants, Appraisals, Reports, Traffic Studies, Airports, Gas & Electric Transmission Lines.
351 East Ohio St., Chicago 11, Illinois

Soil Testing Services, Inc.

Theo. W. Van Zelst Carl A. Mets
John P. Gnaedinger

Soil Borings Rock Coring
Engineering Testing of Soils
Soil & Foundation Reports

4520 W. North Ave. Chicago 39

Metcalf & Eddy

ENGINEERS

Investigations Reports Design
Supervision of Construction and Operation
Management Valuation Laboratory

1300 Statler Building, Boston 16

Ammann & Whitney

Consulting Engineers

Design — Construction Supervision
Bridges, Buildings, Industrial Plants, Special Structures, Foundations, Airport Facilities, Expressways.
76 Ninth Avenue, New York 11, N. Y.
724 E Mason Street, Milwaukee 2, Wis.

Severud-Elstad-Krueger

Consulting Engineers

Structural Design - Supervision
Reports - Buildings - Airports
Special Structures
415 Lexington Avenue
New York 17, N. Y.

Albright & Friel, Inc.

Consulting Engineers

Water, Sewage and Industrial Waste Problems, Airfields, Refuse Incinerators, Power Plants, Industrial Buildings, City Planning, Reports, Valuations, Laboratory.
121 So. Broad St., Philadelphia 7, Pa.

Frederick H. Dechant

Consulting Engineer

Chairman of the Board,
Frederic R. Harris Inc.
Water Works, Industrial Wastes, Sewerage, Recovery Processes, Hydraulic Works, Gas Plants
Phila.: Fidelity Phila. Trust Bldg.
New York: 27 William St.

Inspecting and Testing

Johnson Soils Engineering Laboratory

Engineering design and construction tests run from MOBILE LABORATORY UNITS at construction site. Field load bearing tests.

193 West Shore Ave., Bogota, N. J.
Bogota-Hubbard 7-4408

SEARCHLIGHT SECTION

CEDAR RAPIDS
Asphalt Plant

Model FA—Serial No. 10058A—25 cubic foot size Batch Type with Mixing Unit, Dryer, Fuel Oil Pump and Heater Set, Hot and Cold Elevator, Air Brakes; also includes Automatic Batching Device, Dust Collector, Steam Generator and all Motor Drives, Electric Panel Board. Mixer Unit and Dryer is on Rubber Tires w/5th wheel attachment. Plant in good condition; has not produced 50,000 tons; and believe it is a real buy. Price $40,000.00 F.O.B. Missoula, Montana. Subject to prior sale.

FS-6156, Engineering News-Record
1111 Wilshire Blvd., Los Angeles 17, Calif.

Used EUCLIDS for Sale

13-Yard Bottom Dump
22-Yard End Dump
Attractive prices

FEHRS TRACTOR & EQUIPMENT CO.
1809 Cuming Street, Omaha, Nebraska
Telephone—Atlantic 3127

WANTED

WANTED

Number 1 Vulcan Pile Hammer.
Steam Boiler.
Tankcar Steamheater.
80 to 100 Foot Pile Leads for Crane.

Write Post Office Box 1074
Roanoke, Va.

WANTED

CRANE BOOM, flange type up to 100 Feet for Model 80D, Northwest; will take fairleads, rudomatic, and lagging if available.

A. & J. BUYERS, INC.
3580 Sheridan Dr., Buffalo 21, New York

SURVEYING INSTRUMENTS

USED • REBUILT • SALE • RENT • REPAIRING

GURLEY

FACTORY REBUILDING

of all Modern Surveying Instruments

Gurley maintains a full department for repairing *all* modern makes of surveying instruments. Every repaired instrument goes through the same critical adjustment as a new Gurley.

We guarantee accuracy

W. & L. E. GURLEY
Union Plaza Troy, New York

FROM STOCK

Brand New & Rebuilt

TRANSITS & LEVELS

Fully equipped modern shop—all makes and models repaired — all work guaranteed — instruments rented

Midwest Representative: W. & L. E. Gurley

NATIONAL BLUE PRINT CO.

Established 1914.
210 S. Canal St. Chicago (6), Ill.

RE-BUILT REPAIR RENT REAL EXPERTS

BUFF

ALL MAKES

69 Day St., New York

SPECIALIZED REBUILDING

of surveying and engineering instruments
All makes and models expertly repaired in modern shop. All work guaranteed

USED REBUILT INSTRUMENTS
for sale or rent

ROY D. HICKERSON
8 N. EDMONDSON AVE. INDIANAPOLIS 19, IND.

INSTRUMENT REPAIR BY CRAFTSMEN

Our craftsmen have a completely equipped department fully able to accommodate the repair of all makes of transits, levels and measuring tape. Work includes thorough overhaul, cleaning, oiling and adjustment.

Precision work guaranteed.

DAVID WHITE COMPANY
317 W. Court St., Milwaukee 12, Wis.

INSTRUMENTS FOR RENT

We rent transits and levels on a monthly or yearly basis. Reasonable rates. All instruments are fully guaranteed in first class working order.

DAVID WHITE COMPANY
317 W. Court St. • Milwaukee 12, Wis.

TRANSITS AND LEVELS

New or Rebuilt Sale or Rent

Headquarters for REPAIRS — any make — Factory Service. We will also *buy* your old instruments or *take them in trade.*
A complete line of Engineering Instruments and Equipment for field or office. Write for catalog N.R. 2-12.

WARREN-KNIGHT CO.

Manufacturers of Sterling Transits and Levels
136 No. 12th St., Philadelphia 7, Penna.



Power anywhere on the job with new portable generator

A host of electric-powered tools is available to speed every phase of construction, but it's often neither practicable nor possible to string wires or run conduit to every section of a job where they can be used. Wincharger Corp. has solved that problem with its new 1800 series Winco portable generators together with "Speedy-Shift" wheel and handle arrangements for quick spotting on even remote sections of a project.

Five models in this 1800 series have watt output of 1000, 1250 or 1350, powered by a Briggs & Stratton 8, Clinton D1100, Cushman M6, Lauson TLH or Wisconsin ABN engine.

In addition they've manufactured Model 4500, a general purpose rig which produces 4500 watts (at 100% P. F.) motor starting capacity and 2500 watts continuously at 115 volts, 60-cycle, ac, single phase.

In the picture at left above a 4500 is being used to power a masonry saw for Chris Hansen Construction Co.'s Grant School addition in Sioux City, Iowa.

The photo at right above shows a Jackson electric vibrator being powered by a Winco 4500 on an undisclosed military project.

The portable generators have proved particularly helpful on bridge jobs where electricity often is not available for vibrators, saws, drills, etc. Wincharger Corp., Sioux City 2, Iowa.

Unit combines crusher, mill, screen

Universal Engineering Corporation, Cedar Rapids, Iowa (a division of Pettibone Mulliken Corp.), announces a new addition to its plants. Designed for 100% crushing, this new plant features an 18x30-in. roller bearing jaw crusher, an 18x31-in. hammer mill, and a 4x10-ft three-deck gyrating screen with ball tray. Special by-passes are built in to give product control making it possible to produce aglime, road rock, chips or any simultaneous combination of the three products.

The primary jaw crusher, apron feeder with by-pass, operator's platform, and structural supports are mounted as a separate unit, on skids, which is bolted to the main frame.

It can be removed easily when it becomes necessary to cut weight when traveling.

Other features include side drive through universal joint connection from truck mounted power. Feed is direct from shovel or dump trucks from ramp set-up.

With the addition of this new size, the Universal 293QH Limerock plants are now available in balanced combinations with 18x24, 18x30, and 20x36-in. jaw crushers; 18x31 and 26x36-in. hammer mills, and 4x10 and 4x12-ft screens. Universal Engineering Corp., 625 C Avenue N. W., Cedar Rapids, Iowa.

Airco announces automatic Heliweld hardfacing process

As a result of the need for improved methods in depositing tungsten carbide hardfacing material on tool joints for well-drilling rigs, Air Reduction Sales Co. has developed an automatic Heliweld hardfacing unit. The new process uses a standard Heliweld head and a unit for feeding the bulk tungsten carbide. It's limited only by the ability to position the work and the arc in proper relationship to each other.



In operation, the Heliweld arc melts the base metal, producing an elongated pool and the tungsten carbide particles are poured into this pool behind the arc, as the photo clearly illustrates. The rate of particle feed is accurately controlled by electricity.

According to the manufacturer, tests have repeatedly shown that abrasion

(Continued to page 138)




IRON
• Downspouts
• All Gas Piping
• Steam Supply and Returns
• Freon Lines over 2-inches
• Sprinkler System and Fire Lines
• Waste, Drain and Vents less than 2-inches
• Hot and Cold Water Lines 2-inches and over
• Chilled and Condenser Water Lines over 2-inches
• All Compressed Air Lines

BYERS WROUGHT IRON PIPE

Keeps 15 Vital Services "OUT OF TROUBLE"

The designers of this modern hospital took every precaution to ban piping ills. In virtually every service they put genuine wrought iron on the job to forestall the maintenance threat of premature failure and costly replacement.

Built under the Hospital Construction Program of the United States Public Health Service, this 100-bed structure is located in Corsicana, Texas. The hospital was designed by W. G. Clarkson & Company, Architects, A. George King, Associate, Fort Worth, Texas. Leonard E. Kanto, Consulting Mechanical Engineer, also of Fort Worth, was responsible for the sound piping specifications. The mechanical contract was awarded to Beals Plumbing and Heating Company, Inc., Fort Worth.

Maintenance records provide plenty of examples of the consequences of using non-durable materials in these services—and of the wisdom of using genuine wrought iron. In a number of reported cases, genuine wrought iron pipe has doubled, tripled and even quadrupled the useful service life previously obtained from low-first-cost piping, and ended maintenance headaches that had been regarded as incurable.

Our bulletin, WROUGHT IRON FOR PIPING SYSTEMS, discusses corrosive conditions encountered in various services, and illustrates a few of the many places where genuine wrought iron has been successfully applied. Write for your copy today.

A. M. Byers Company, Pittsburgh, Pa. Established 1864. Boston, New York, Philadelphia, Washington, Atlanta, Chicago, St. Louis, Houston, San Francisco. Export Division: New York, N.Y.

Why Genuine Wrought Iron Lasts

This notch-fracture test specimen illustrates the unique fibrous structure of genuine wrought iron—which is responsible for the high corrosion resistance of the material. Tiny threads of glass-like silicate slag, distributed through the body of high-purity iron, halt and disperse corrosive attack, and discourage pitting and penetration. They also anchor the initial protective scale, which shields the underlying metal.

BYERS

CORROSION COSTS YOU MORE THAN WROUGHT IRON

WROUGHT IRON

TUBULAR AND HOT ROLLED PRODUCTS

ELECTRIC FURNACE QUALITY ALLOY AND STAINLESS STEEL PRODUCTS



ROOSHORS GIVE... *More Adjustment per Shore!*

● The longer adjustment feature of Rooshors means fewer different sizes of shores to have on hand. Two sizes have full 6 ft. adjustment and the smaller size a 4 ft. adjustment . . . 8 ft. to 14 ft.; 7 ft. to 13 ft. and 5 ft. to 9 ft. Each Rooshor will handle more jobs. Wooden upper members permit ease in diagonal and horizontal bracing when required. Hairline adjustment with the exclusive Rooshor Lock . . . there are no pins or bolts to lose and no screw adjustments to become clogged. *You save time, labor and material every time you use Rooshors.*

SPEED COLUMN FORMING WITH ROOS COLUMN CLAMPS

The Roos Clamp is foolproof . . . they can't be put on wrong (there are no "rights" or "lefts") thereby speeding column forming operations. They automatically square the column forming and the larger bars give greater strength.

Rooshors and Roos Column Clamps are available for rental or purchase from warehouse stocks in principal cities.



BAKER-ROOS, INC.

602 WEST McCARTY STREET
INDIANAPOLIS 6, INDIANA

Write today for Bulletin 252

"GUNITE" CONCRETE

(Since 1918)

FOR • STEEL PLATE LINING • STEEL ENCASEMENT • BUILDING NEW WALLS • LINING WATER RESERVOIRS, TUNNELS AND SEWERS • PLATE LINING OF STEEL STACKS, BUNKERS, DUCTS • REPAIR OF DISINTEGRATED CONCRETE AND MASONRY • CANAL, DITCH AND DRAIN LINING

GUNITE CONCRETE & CONST. CO
1301 Woodswether Rd., Kansas City 6, Mo

District Branch Offices

Paul B. Watts, 228 N. LaSalle St., Chicago 1, Ill.
George R. Lewis Co., 2836 Queen Ave. S., Minneapolis 5, Minn.
G. H. Mueller Co., 8626 Delmar Blvd., St. Louis 5, Mo.
Ole K. Olsen Co., 823 Perdido St., New Orleans, La.
Phillip D. Barnard, 2038 Addison, Houston 5, Tex.
Western Steel Prod. Co., 1758 W. 13th Ave., Denver 4, Colo.

from
●
●
OFFICE MANAGER
●
to
●
GENERAL MANAGER
●
●

yes, that is the quality of the personnel available to your organization through the Classified Advertising pages of ENGINEERING NEWS-RECORD.

Classified Advertising Division
ENGINEERING NEWS-RECORD
330 W. 42nd St. New York 36, N. Y.

NEW PRODUCTS

(*Continued from page 136*)
resistance of deposits made by this process is considerably better than that attainable through using other arc methods. AIR REDUCTION SALES CO., 60 EAST 42ND STREET, NEW YORK 17, N. Y.

Angle-type air tools for drilling in light metals

A series of three angle-type drills, to be known as the 11C series, has just been announced by Keller Tool Co. They are powered to drill holes at right angles in aluminum or brass from $\frac{7}{16}$ to $\frac{3}{4}$ in. diameter and in mild steel from $\frac{1}{4}$ to $\frac{1}{8}$ in. diameter, and are especially desirable for close-quarter work, as illustrated, where larger size drills are required. Since they are air-powered, stalling of these drills will not injure them or their air motor.

The series comprises three motors of different speeds and five angle attachments—all interchangeable—so that fifteen variations of speed and chuck sizes are made available. KELLER TOOL COMPANY, GRAND HAVEN, MICHIGAN.

Payloader tractor designed for heavy-duty pushing

If you picture the Hough TM "Payloader" with its front end bucket replaced by a huge steel push plate, you will have a good idea of just what the new Payloader tractor looks like.

Like the regular Payloader, it has full reversing transmission which provides four gear ratios in both forward and reverse; speeds up to 27 miles per hour; a torque converter drive in addition to a friction clutch; rear wheel steer with hydraulic power booster; 16.00-24 tires all around.

The new rubber-tired tractor is available with either a 106-hp gasoline engine or a 90-hp diesel engine, which

develops up to 16,000 and 14,000 lb drawbar pull, respectively. Total weight is 25,000 lb, and the unit is recommended for heavy-duty drawbar and pushing work.

It makes a flexible, efficient railroad car switcher and spotter for industrial plants and yards, and the manufacturer says it can pull or push 8 to 10 loaded cars. The big earthmover tires walk readily over ties and across tracks and the torque converter assures precise control for careful spotting and slow, steady application of power for starting heavy loads. The Frank G. Hough Company, Seventh Street, Libertyville, Illinois.

Rear half of new trailer tilts for loading machinery

The latest Rogers trailer is a divided-deck gooseneck type which has a longer deck to carry heavier loads of greater area. This divided deck is so well balanced as to be tipped or returned to the traveling position by the weight of one man. A double-acting hydraulic ram checks and cushions the upward and downward movement of the deck. Rogers Bros. Corp., Albion, Penna.



Ring and wedge principle fastens reinforcing bars

An inexpensive clamp which provides an easy, positive union for reinforcing rods utilizes two oval rings as yokes with tapered wedges driven under them in the directions of the stresses. The device binds tighter when tension on the rods is increased, and is said to hold rods firmly during pouring or vibrating of concrete.

The clamps have proved useful in attaching rods to dowels in footings and at corners. They also allow use of short rods in tight spots where long lengths can't be used, as well as in box-type basement walls and floor slabs. Jerome P. Costello Company, 3527 Bevis Avenue, Cincinnati, Ohio



Accurate Handling... SAVES TIME

This sturdy UNIT Crawler Crane offers plenty of power plus accurate control. Spots heavy sewer pipe perfectly into the desired position. Adjustable Hook Rollers, Extra Long Crawlers and Wide Multiple Hinged Crawler Shoes provide all-around stability. Full Circle Swing, controlled from within UNIT'S FULL VISION CAB, provides safe and efficient operation. The operator has a complete view of the entire job at all times. GET THE FACTS! Investigate this modern UNIT and its many features. Write today for literature.

UNIT CRANE & SHOVEL CORPORATION
6315 WEST BURNHAM STREET • MILWAUKEE 14, WISCONSIN, U. S. A.

½ or ¾ YARD EXCAVATORS... CRANES UP TO 20 TONS CAPACITY
CRAWLER OR MOBILE MODELS . . . GASOLINE OR DIESEL



All Models Convertible to ALL Attachments!

PERMANENTLY *Smooth*
FOR WALKING • WORKING WHEELING

★Cement filled IRVING GRATING is the perfect ARMOURING for Heavy Duty Floors, Trucking Aisles and Loading Platforms. Very low installation and maintenance costs. Smooth, unbroken surface gives a Safe, Fireproof, Durable and Economical Floor.

For Further Information Write For Booklet

IRVING SUBWAY GRATING CO., INC.
ESTABLISHED 1902
OFFICES and PLANTS at
5063 27th St., Long Island City 1, N. Y.
1863 10th St., Oakland 20, California

SAMSON BAR CUTTERS

- All Steel Construction
- Unbreakable Frame
- Easy Operation
- Immediate shipment

Write for catalog of Metal Working Equipment.

CAPACITY	No. 20	No. 23	No. 26
Rounds	5/8"	3/4"	7/8"
Squares	1/2"	5/8"	3/4"
Flats	2"x1/4"	2 1/2"x5/16"	2 1/2"x3/8"
PRICE	$47.15	$63.00	$72.00

f.o.b. New York, subject to change

JULIUS BLUM & CO., Inc.
534A West 22nd St. New York 11 • WAtkins 9-0[illegible]



Flexible metal hose solves air line maintenance problems on Unit cranes

On Unit's 357 mobile crane, compressed air is piped from a reservoir tank through two-way brake and transmission control valves, indicated by arrows in the photo, and a vertical propel shaft to a central rotating joint on the undercarriage. From this joint, pressure lines carry the air to the front and rear axle brake pistons and from there to the two-speed, air-operated transmission.

Any air escape on these lines might cause loss of braking power or transmission control. Wear fractures and vibration stresses constantly caused failures in in-field testing.

Engineers from Titeflex Inc. were invited by the Unit Crane and Shovel Corp. to investigate the use of flexible metal hose.

After months of field testing and through thousands of hours of actual operating life on the job, the Titeflex lines have stood up extremely well, according to both manufacturers. The convoluted flexible metal hose with round wire braid reinforcing can readily withstand the constant vibrations set up when the rig is working.

In addition it acts as a vibration absorber to eliminate strain and wear around couplings, where air lines are most prone to fail. TITEFLEX INC., 500 FRELINGHUYSEN AVE., NEWARK 5, NEW JERSEY.

Latest GM development: Air bellows replace springs

A radically new type of coach body suspension—employing air "balloons" instead of leaf springs—was announced by the Truck and Coach Division of General Motors Corp. First use is on coaches, but experiments will continue with other types of transportation. A result of more than 12 years of research and development, the Air Suspension Ride employs eight heavy, flexible air bellows of rubberized nylon tire fabric, two to each wheel, and, at the same time, eliminates conventional metal leaf springs.

Where a metal leaf spring has a uniform rate throughout its deflection, compressed air increases its resistance as it is compressed. Leveling valves automatically meter the compressed air into the system so that, as a vehicle is loaded, it retains its level. With unloading, these valves release the proper amount of air. TRUCK AND COACH DIVISION, GENERAL MOTORS CORP., PONTIAC 11, MICHIGAN.

Improved safety solvents for metal parts degreasing

Orthosene, Per-Trolene and Frigisol are safety solvents for electrical, mechanical and metal parts degreasing and for refrigeration equipment cleaning. All three have been designed to replace carbon tetrachloride and are claimed to be a marked improvement over safety solvents heretofore available.

Orthosene is a slow-drying solvent with a high flash point. It has excellent degreasing qualities and is said to leave no residual oily film.

Per-Trolene is a rapid-drying solvent, with a flash point of 140 deg F. It is designed for wide application in electrical and mechanical maintenance shops where drying and exceptional degreasing qualities are needed.

Frigisol is also a rapid-drying safety solvent, similar in many qualities to Per-Trolene, but also capable of displacing water. It has a flash point of 235 deg F which makes it applicable to many spot locations where lower flash solvents might present fire hazards.

The safety qualities of all three solvents have been improved by eliminating toxic inhibitors, as well as harmful isomers normal to some chlorinated products. JOHN B. MOORE CORPORATION, P. O. BOX #3, NUTLEY 10, N. J.

New Product briefs . . .

Dart Manufacturing Company, Mason, Michigan is manufacturing a new **steel rule** that's been designed to give more viewing area when taking inside measurements. Readings are seen at indicator points and "anti-pop-out" design keeps blade from creeping in or out. Blades are replaceable in seconds without tools, available in 6-, 8- and 10-ft lengths.

A new **200-ampere, engine-driven dc arc welder** with a 60 percent duty cycle has been announced by the **Welding Department of General Electric Company, Schenectady 5, N. Y.** Designated as Type WD-42AGW, the new welder has a current range of 40 to 250 amperes, and can be used with a variety of electrode sizes for repair, maintenance and construction work.

Two new electric hand drills are now being introduced by the **Porter-Cable Machine Company of Syracuse, N. Y.** One, model 107, is a general duty type with ¼-in. chuck; the other, model 109 has ½-in. capacity for higher resistance work.

Blueprint for Tomorrow's New Processes

the DORRCO d-i system



DIAGRAMMATIC FLOWSHEET—COMPLETE DE-IONIZATION

In processing practically any chemical or petro-chemical you can name, there's the problem of purification or demineralization. It may be purification of water, or any solution bearing sugar, chemical or metallic compounds.

Early in the development of synthetic resins, Dorr started a continuous research program aimed at full development of ion-exchange technique. Today, the Dorrco D-I system can be used to completely remove ionized materials from solutions, to separate ionizable compounds and, by taking advantage of selective exchange, to separate one ionizable salt from another.

It's a good plan to talk to Dorr about your new ideas. Whenever a process involves the separation of finely divided solids in suspension, the use of ion-exchange, or fluid techniques, we can probably help you.

Better tools TODAY to meet tomorrow's demand

DORR

WORLD-WIDE RESEARCH • ENGINEERING • EQUIPMENT

THE DORR COMPANY • ENGINEERS • STAMFORD, CONN.

Offices, Associated Companies or Representatives in principal cities of the world

The MAJORITY of Your Heavy Hauling Jobs can be handled PROFITABLY with... the POPULAR

ROGERS Type "T"

LARGE CAPACITY IN AN 8 FT. DECK WIDTH—LEGAL IN ALL STATES. 8 TIRES ON 2 ROCKING STUB AXLES WITH LEVEL OR DROP DECK IN 15, 20, 25, 30 and 35 TON CAPACITIES

By reason of its versatile adaptability to all kinds of heavy hauling jobs, the Rogers Type "T" has steadily increased in popularity.

It's a "natural" for small and large contractors and haulers.

If you are considering the purchase of one or more trailers, by all means investigate the Type "T".

It packs powerful advantages in a multi-purpose single unit.

Write for full details and catalog.



A worms-eye view of the sturdy rear end and frame construction of the famous "T".

The rear end design of the Type "T" has proved so efficient it has been adopted as standard construction in Rogers Power-Lift Detachable Gooseneck Trailers.

EXPERIENCE *builds 'em* PERFORMANCE *sells 'em*

ROGERS BROS. CORP.

ALBION, PENNA.



A Rogers Type "D" Trailer

Export Office: 50 Church St., N. Y. 7, N. Y.—Cable address: Brosites

PUBLICATIONS

Aluminum Forming—Anyone who works with metal will find a wealth of information on how to draw and form aluminum sheet, plate, tubing and pipe in this 148-p technical manual. It points out that the most common mistake is the attempt to work and form aluminum by the identical technique used for other metals. While similar techniques may be employed in some operations, others require special procedures, and this compact illustrated book explains them completely. Two important sections are devoted to metallurgical data—one on aluminum sheet and plate; the other on aluminum tubing and pipe.—Reynolds Metals Co., 2500 S. Third St., Louisville, Ky.

Metal Grating—This 24-p booklet is entitled "Open Steel Grating and Stair Tread Catalog" and has been published by the Klemp Metal Grating Corporation. It is fully illustrated and complete with engineering data, charts, and a safe load table for welded and diamond riveted grating. The catalog illustrates the company's feature which is a grating made from round steel crossbars, so formed as to provide a peak, or crest, on the top side of the bar. These bars are placed at right angles on top of flat bearing bars set on edge and then electro-welded under pressure.

Another 4-p catalog is entitled "Klemp 4 Grates Serving the Nation's Major Oil Companies" and describes the construction of the new "Klemp-Krest" welded grating which has been used extensively in fractionating vessels and pipes leading to and from catalyst regenerators.—Klemp Metal Grating Corp., 1371 North Branch St., Chicago 22, Ill.

Guide to Selection of Centrifugal Pumps—Allis-Chalmers' broad line of centrifugal pumps applicable to most industries is highlighted in a newly-released handy guide to selection of centrifugal pumps.

In addition to covering general purpose, double suction, multi-stage, special-purpose, marine and mixed and axial flow pumps, the 12-p bulletin has a head-capacity table for single-stage, double suction A-C pumps.

Special purpose pumps mentioned include solids handling, paper stock, sewage, rubber-lined process, fractional horsepower and coolant and circulating units. Labeled No. 52C6059J, it is available from Allis-Chalmers Manufacturing Co., 840 S. 70th St., Milwaukee, Wis.

ADVERTISERS IN THIS ISSUE

Acker Drill Co. 86
Aeroquip Corp. 9
Allis-Chalmers Mfg. Co. 72, 73
Aluminum Co. of America 95
American Manganese Steel Div., American Brake Shoe Co. 10
American Trailer Co., Inc. 96
Armco Drainage & Metal Prod. Inc. ..... 2nd Cover
Atlantic Steel Corp. 118
Atlantic Steel Corp. 119

Baker-Roos, Inc. 138
Baldwin-Lima-Hamilton Corp. 54, 55
Bay City Shovels, Inc. 53
Bayley Co., The William 83
Belmont Iron Works 74
Besser Mfg. Co. 98
Blood Brothers Machine Co. 74
Blum & Co., Inc., Julius 140
Brunson Instrument Co. 69
Byers Co., A. M. 137

Cement Gun Company 103
Chicago Pneumatic Tool Co. 97
Cleaver Brooks Company 71
Clipper Mfg. Co. 65
Complete Machy. & Equip. Co. 82
Continental Motors Corp. 88
Continental Steel Corp. 76

Dicalite Div. Great Lakes Carbon Corp. 86
Dodge Div., Chrysler Corp. 37
Dorr Co. 141
Dow Chemical Co. 58
Dravo Corp. 89
Dresser Mfg. Div., Dresser Ind. 93
Dudgeon Inc., Richard 121

Eastman Kodak Co. 63
Economy Forms Corp. 82
Eimco Corp., The 107
Electric Tamper & Equipment Co. 62
Ellicott Machine Corp. 15

Fenestra Building Products 87
Foundation Equip. Corp. 91

Gardner-Denver Company 61
Gateway Engrg. Co. 69
General Electric Company Electronics Dept. 52
Griffin Wellpoint Corp. 86
Gunite Concrete & Const. Co. 138
Gunite Construction Company 85

Hendrix Mfg. Co. 6
Herman Nelson Div., American Air Filter Co., Inc 115
Hetherington & Berner, Inc. 67
Homelite Corp. 101
Huber Mfg. Co., The 84

Insurance Co. of North Amer. 112
International Steel Co. 70
Irving Subway Grating Co. 140
Irvington Form & Tank Corp. 120
Jaeger Machine Co. 92
Jenkins Bros. 68
Johns-Manville Corp. 90
Joy Mfg. Co. 67

Kinnear Mfg. Co. 100

Lewis & McDowell, Inc. 120
Lighthouse Trailer Co. 99
Lock Joint Pipe Co. 66
Lone Star Cement Corp. 16

MacArthur Concrete Pile Co. 76
Mack Trucks, Inc. 57
Mahon Co., R. C. 77
Maintenance Co., Inc. 79
Maintowoc Engineering Works 94
Marion Power Shovel Co. 80
Marsh Company 92
Maxon Construction Co., Dumpcrete Div. 85
Mayo Tunnel Equipment Co. 119
McGraw-Hill Book Co. 60
McKiernan-Terry Corp. 30
McKissic Products Corp. 143
Michigan Power Shovel Co. ..... 3rd Cover
Moretrench Corp. 108

Northwest Engineering Company 3

Ohio Locomotive Crane Co. 119

Pennsylvania Drilling Co. 121
Permutit Co., The 14
Philadelphia Gear Works 79
Pittsburgh Plate Glass Co. 75
Plasteel Products Co. 121
Portland Cement Assn. 104
Powder Power Tool Corp. 33

Raymond Concrete Pile Co. 7
Rodgers Hydraulic, Inc. 43
Rogers Bros. Corp. 142
Russell, Burdsall & Ward Bolt & Nut Co. 50
Ryerson & Sons, Inc., Jos. T. 18

Sauerman Bros., Inc. 100
Scheu Products Co. 92
Seaman Motors 8
Servicised Products Company 100
Sherman Products, Inc. 91
Sika Chemical Corp. 120
Six-Wheels, Inc. 51
Smith Co., S. Morgan 1
Smith Engineering Works 12, 13
Snow-Nabstedt Gear Corp. 96
Sofarell Bros. 49
Solvay Process Div., Allied Chem. & Dye Corp. 64
Sprague & Henwood, Inc. 74
Stang Corp., John W. 118
Superior Concrete Accessories 102

Tapecoat Company 56
Texas Company 4, 5
Timken Roller Bearing Co. ..... 4th Cover
Tinney Drilling Company 115
Torrington Co., Bantam Bearings Div. 38
Trailer Village, Inc. 115
Trans-Global Co. 2
Tulsa Winch Mfg. Co. 113

Unit Crane & Shovel Corp. 139
Universal Atlas Cement Co. 20
Universal Concrete Pipe Co. 114
Universal Form Clamp Co. 46

Victaulic Co. of America 11
Vulcan Iron Works 82

Waukesha Motor Co. 59
Webb Mfg. Co. 103
Williams Co., J. H. 85
Wisconsin Motors Corp. 99
Wolverine Tube Div., Calumet & Hecla, Inc. 111

PROFESSIONAL SERVICES 135

SEARCHLIGHT SECTION

(Classified Advertising)
H. E. Hilty, Mgr.

Employment
Positions Vacant 125, 126, 127
Selling Opportunities Offered 126
Positions Wanted 125
Part Time Work 125
Employment Services 125
Special Services 125

Educational
Schools 125
Tutoring 125

Business Opportunities
Offered 125

Notices
Proposals 122, 123, 124

Property
Wanted 125

Equipment
(Used or Surplus New)
For Rent 132
For Sale 125-135
Piling 134
Pipe 132
Rail 134
Surveying Instruments 134

Wanted
Equipment 135
Miscellaneous 125

ADVERTISERS INDEX 124

ENGINEERING NEWS-RECORD

D. S. Robertson, *Adv. Sales Manager* — Howard T. Olsen, *Assistant Manager*
J. G. Johnson, *Business Manager*

Sales Representatives: M. J. Storz and E. A. Callahan, Jr., 330 W. 42nd St., *New York;* F. G. Hudson, L. H. Hunt, W. G. Payne, 520 N. Michigan Ave., *Chicago;* R. E. Dorland, 68 Post St., *San Francisco;* A. B. Cozzens, 17th & Sansom Streets, *Philadelphia;* F. E. Duff, Jr., Hanna Bldg., *Cleveland;* B. F. Horn, Penobscot Bldg., *Detroit;* W. F. Donnell, Continental Bldg., *St. Louis;* H. L. Keeler, 1111 Wilshire Bldg., *Los Angeles;* R. C. Maultsby, Rhodes-Haverty Bldg., *Atlanta;* James Cash, First National Bank Bldg., *Dallas. Other Sales Offices:* 738-39 Oliver Bldg., *Pittsburgh;* 350 Park Sq. Bldg., *Boston;* McGraw-Hill House, *London.*



A BETTER BLOCK
FOR EVERY PURPOSE

McKISSICK
Super Champion
SNATCH BLOCKS
FOR LOADS UP TO 40 TONS

- **Top Performance**
- **Real Endurance**
- **Extra Duty Service**

Large diameter center pin. Drop forged, heat treated swivel hook or shackle . . . 8" - 10" - 12" and 14" steel sheaves grooved to line size. High speed bronze bushings or roller bearings.

Alemite lubrication.

Request catalog

McKISSICK PRODUCTS CORPORATION
Box 2496 Tulsa, Oklahoma

EDITORIAL

Concrete surfacing for roads

Is CONCRETE PAVING becoming simply a top layer for a two, three or even four-layer pavement? That question is raised by the account of New Jersey's field studies of concrete pavements without reinforcing and without expansion joints, published in our issue of Sept. 25, p. 38. The latest of the pavements described in that article consists of a 10-in. thick plain concrete slab laid on 4 in. of crushed stone and 8 in. of bank-run gravel selected and graded to give a high degree of stability. That pavement is on U.S. 22 near Clinton, N.J.

Bituminous materials, quite generally, have been used as a surfacing for a two or three-layer pavement, going back to the days when such materials were used to surface old water-bound macadam roads. But concrete, until fairly recently, was looked upon as a complete paving unit when laid over reasonably stable soils.

Concrete paving was so considered in New Jersey 20 years ago when the State Highway Department began the reconstruction of U.S. 22, the state's major east-west highway, and the one on which the pavement described in our Sept. 25 issue was laid. The base and subbase under the concrete top of that new pavement are believed to have sufficient stability in themselves to carry a considerable part of the traffic load.

Back of this change from a concrete pavement laid on the natural soil to a thicker slab laid on two layers of granular material lies bitter experience with pumping at pavement joints which grew progressively worse as traffic increased in volume and weight. Across all of northern New Jersey, where the greatest volume of heavy traffic must be handled, lie soils of predominantly glacial origin. The better ones, having a fair percentage of granular materials, did not pump under light traffic. So they were used with confidence under concrete laid on U.S. 22 in the earlier years of rebuilding that highway, only to find in later years that pumping began to occur in many places as traffic volume rose.

As a result, bases of granular material were added, first in 8-in. layers and then in thicker layers as experience showed that more depth was needed to prevent pumping or to minimize the effect of frost.

WHAT OF THE FUTURE? Enthusiastic advocates of prestressed concrete already have declared that the next step will be the use of thin slabs of prestressed concrete as a surface layer. As examples of what can be done, they cite Freyssinet's prestressed concrete pavement on Orly Field in France, a prestressed concrete floor slab in the Roebling Company's warehouse in Cicero, Ill., and a diagonally reinforced concrete pavement, 6-in. thick, laid in the town of Crawley in Sussex, England.

We would not be so bold or pessimistic as to say that a prestressed-concrete design less costly than a thick slab of plain concrete will not be developed. However, no one of the prestressed pavements cited by advocates of that method appears to be an answer to the highway designer's problem because of cost or because of the new joint problem the design introduces, or both. The Roebling warehouse design shows no saving in concrete as the 3-in. prestressed slab is laid on a 9-in. plain concrete slab.

Doubtless some prestressed pavement designs will be developed and laid in the not too distant future. But a step that has more immediate promise of being fruitful is a reduction in thickness of the concrete slab to determine whether a surfacing that is adequate structurally can be obtained at less cost by that means. New Jersey already has taken the first step. On Route 25, near Deans, an 8-in. thick reinforced concrete pavement has been laid on a 7-in. base and 5-in. subbase of carefully graded granular material, all of which was laid on a 6-in. subgrade of selected material.

FURTHER STEPS, presumably, might include trial of a 6-in. reinforced-concrete slab and an 8-in. slab of unreinforced concrete similar to the 10-in. slab put down recently on U.S. 22 near Clinton, N.J. That pavement was laid on an unusually substantial base and subbase to offset any structural deficiency resulting from absence of reinforcing in the slab and dowels at the joints. Tests might show that a thinner unreinforced slab would still be adequate on such a substantial base.

Every inch cut off the thickness of the plain concrete slab will make more difficult a demonstration of savings through the use of simple reinforcing or prestressing.

ADDING TO THE SUPPORTING VALUE of the subgrade by stabilizing it with cement, asphalt, lime, or possibly one of the ion-exchange processes now being studied might prove to be a route to further economies. To date, most experience in this field has been on secondary roads not carrying the heavy concentrations of loads and volume of traffic found on main highways.

In California, concrete pavements for main highways now are being laid directly on a soil-cement subgrade. There, however, the objective of cement stabilization is not greater structural support for the pavement. Its purpose is to provide a subgrade that will not wash away under pumping action.

What California learns about the effectiveness of cement stabilization in checking pumping will be helpful, but for regions where frost is a factor, it appears probable that concrete pavement design studies will continue to include one or more layers of granular material of known stability under frost action.

NAVAL YARD SEWAGE PROJECT . . .

Michigan Model C-16, ½ yd. clamshell, equipped with 30-inch crawler pads.

Construction of 4,500 feet of sewage lines to connect the Norfolk Naval Yard system with that of Portsmouth, Virginia, is being handled by A. G. Pinkston Company, Portsmouth. Trenches are 6 feet wide, 6 feet to 16 feet deep and carry 4-inch to 30-inch main and lateral pipe.

Three MICHIGAN Crawler Excavators and a MICHIGAN Truck Crane are working on the job. Their speed and handling ease are major factors in keeping the job moving on schedule. "With the MICHIGAN air controlled clutches we gain one to two bucket loads over every ten handled by other shovels. This adds 10%-15% to our daily production," states A. G. Pinkston, Jr.

Take a tip from contractors who know! When you need an excavator-crane . . . investigate MICHIGAN.



Model T6K
⅜ yd., 6 ton

Model TMDT-16
½ yd., 10 ton



Model TLDT-20
12 ton



Series 8
½ yd., 8 ton

Model C-16
½ yd., 8 ton

MICHIGAN POWER SHOVEL COMPANY

500 Second Street, Benton Harbor, Michigan, U. S. A.

For long-lived, heavy-duty conveyors...



Belt idlers manufactured by Bartlett and Snow Company carry 150 tons of coal per hour at this Midwest power plant. Timken bearings in the idlers assure long idler life with minimum maintenance.



This Chain Belt Company installation at a Wisconsin foundry handles 50 tons of molding sand per hour at a belt speed of 125 ft. per minute. Timken bearings in the Rex idlers make closures more effective, keep lubricant in—dirt and sand out.



8,566 Timken bearings are used in the Barber-Greene idlers of this lime-stone conveyor in Virginia. The conveyor moves 350 tons of crushed lime-stone per hour. Timken bearings reduce friction, take the heavy loads with a minimum of wear.

IT'S TIMKEN... AND TIMKEN... AND TIMKEN AGAIN!

AND HERE ARE 6 BIG REASONS WHY:

1. **THOROUGHLY PROVED.** The Timken bearing is the only tapered roller bearing proved by 15 years or more of service in heavy-duty conveyor installations using the popular dead shaft construction.

2. **EXTRA CAPACITY.** Line contact between rollers and races gives Timken bearings high load capacity. And by using Timken bearing sizes that are mass produced for the automotive industry, you get extra-capacity bearings that actually cost *less* than the smaller sizes you'd normally use.

3. **LONG-LIFE LUBRICATION.** Not just lubricated for "life", but lubricated yearly, or as conditions require, to insure *long* life. Fresh lubricant ends any chance of gummy, sticky, jammed bearings.

4. **LONGER ROLLER AND BELT LIFE.** Less sliding and scuffing between idlers and belt.

5. **FRICTION MINIMIZED.** Timken bearings' true rolling motion and extremely smooth surface finish practically eliminate friction.

6. **MAINTENANCE REDUCED.** Long life and dependable performance of Timken tapered roller bearings cut maintenance to a minimum.

Remember "Timken" is not a bearing type. It is a trade-mark applying only to bearings made by The Timken Roller Bearing Company. Always insist on Timken bearings in the conveyors you build or buy. The Timken Roller Bearing Company, Canton 6, Ohio. Canadian plant: St. Thomas, Ontario. Cable address: "TIMROSCO".

Wherever the going's tough industry turns to

TIMKEN

TAPERED ROLLER BEARINGS



Typical application of Timken bearings for conveyor idlers.

NOT JUST A BALL ○ NOT JUST A ROLLER ⊂⊃ THE TIMKEN TAPERED ROLLER ⊂⊃ BEARING TAKES RADIAL ◐ AND THRUST ←◐→ LOADS OR ANY COMBINATION